

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0136  
Expires November 30, 2000



APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		<b>CONFIDENTIAL</b>	5. Lease Serial No. UTU 0806
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone			6. If Indian, Allottee or Tribe Name UTE TRIBAL
2. Name of Operator SHENANDOAH ENERGY INC.		Contact: JOHN BUSCH E-Mail: jbusch@shenandoahenergy.com	7. If Unit or CA Agreement, Name and No. WONSITS VALLEY
3a. Address 11002 E. 17500 S. VERNAL, UT 84078	3b. Phone No. (include area code) Ph: 435.781.4341 Fx: 435.781.4323		8. Lease Name and Well No. WONSITS VALLEY 4W-12-8-21
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface NWNW 356FNL 475FWL At proposed prod. zone			9. API Well No. 43-047-34268
14. Distance in miles and direction from nearest town or post office* 15 MILES SOUTHWEST OF REDWASH UTAH			10. Field and Pool, or Exploratory WONSITS VALLEY
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 356			11. Sec., T., R., M., or Blk. and Survey or Area Sec 12 T8S R21E Mer SLB
16. No. of Acres in Lease 2480.00			12. County or Parish UINTAH
17. Spacing Unit dedicated to this well 40.00			13. State UT
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 1500			20. BLM/BIA Bond No. on file U-0969
19. Proposed Depth 7940 MD 7940 TVD			21. Elevations (Show whether DF, KB, RT, GL, etc.) 5015 KB
22. Approximate date work will start 08/24/2001			23. Estimated duration 10 DAYS

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature 	Name (Printed/Typed) JOHN BUSCH	Date 08/24/2001
Title OPERATIONS		
Approved by (Signature) 	Name (Printed/Typed) BRADLEY G. HILL	Date 09-05-01
Title RECLAMATION SPECIALIST III		

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #6306 verified by the BLM Well Information System  
For SHENANDOAH ENERGY INC., sent to the Vernal


Federal Approval of this  
Action Is Necessary

\*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\*

T8S, R21E, S.L.B.&M.


SHENANDOAH ENERGY, INC.

Well location, WV #4W-12-8-21, located as shown in the NW 1/4 NW 1/4 of Section 12, T8S, R21E, S.L.B.&M. Uintah County, Utah.



### BASIS OF ELEVATION

BENCH MARK (45 EAM) LOCATED IN THE N 1/2 OF SECTION 5, T8S, R21E, S.L.B.&M. TAKEN FROM THE BRENNAN BASIN QUADRANGLE, UTAH, UINTAH COUNTY 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4689 FEET.



### CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE MAP WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

NO. 161319  
ROBERT L. JENSEN  
REGISTERED LAND SURVEYOR  
REGISTRATION NO. 161319  
STATE OF UTAH

**CONFIDENTIAL**

### LEGEND:

└─┘ = 90° SYMBOL

● = PROPOSED WELL HEAD.

▲ = SECTION CORNERS LOCATED.

LATITUDE = 40°08'41"

LONGITUDE = 109°30'37"

BASIS OF BEARINGS IS THE EAST LINE OF THE NE 1/4 OF SECTION 13, T8S, R21E, S.L.B.&M. WHICH IS ASSUMED FROM G.L.O. INFORMATION TO BEAR N0°49'W.

UINTAH ENGINEERING & LAND SURVEYING  
85 SOUTH 200 EAST - VERNAL, UTAH 84078  
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 8-6-01	DATE DRAWN: 8-13-01
PARTY D.A. J.A. D.COX	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE SHENANDOAH ENERGY, INC.	

**Additional Operator Remarks:**

Shenandoah Energy Inc. proposes to drill a well to 7940' to test the Wasatch. If productive, casing will be run and the well completed. If dry, the well will be plugged and abandoned as per BLM and State of Utah requirements.

Operation will be according to the Standard Operating Practices for Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in T7S, R21-24E and T8S, R21-24E.

See Onshore Order No. 1 attached.

Please be advised that Shenandoah Energy Inc. is considered to be the operator of the above mentioned well. Shenandoah Energy Inc. agrees to be responsible under the terms and conditions of the lease for the operations conducted upon the lease lands.

Bond coverage for this well is provided by Bond No. U-0969. The principal is Shenandoah Energy Inc. via surety as consent as provided for in 43 CFR 3104.2.

# SHENANDOAH ENERGY, INC.

**WV #4W-12-8-21**

LOCATED IN UINTAH COUNTY, UTAH  
SECTION 12, T8S, R21E, S.L.B.&M.



PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: SOUTHEASTERLY



- Since 1964 -

**UELS** Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

**LOCATION PHOTOS**

**8 15 01**  
MONTH DAY YEAR

**PHOTO**

TAKEN BY: D.A. DRAWN BY: K.G. REVISED: 00-00-00

**CONFIDENTIAL**



SHENANDOAH ENERGY INC.  
WELL # WV 4W-12-8-21

ONSHORE OIL & GAS ORDER NO. 1  
Approval of Operations on Onshore  
Federal Oil and Gas Leases

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas No. 1, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

1. Formation Tops

The estimated tops of important geologic markers are as follows:

<b>Formation</b>	<b>Depth</b>	<b>Prod. Phase Anticipated</b>
Uinta	Surface	
Green River	2905'	
Mahogany Ledge	3665'	
Wasatch	6235'	
TD (Wasatch)	7940'	Gas

2. Anticipated Depths of Oil, Gas, Water and Other Mineral Bearing Zones

The estimated depths at which the top and bottom of the anticipated water, oil, gas or other mineral bearing formations are expected to be encountered are as follows:

<b>Substance</b>	<b>Formation</b>	<b>Depth</b>
Oil/Gas	Wasatch	7940'

All fresh water and prospectively valuable minerals encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

All water shows and water-bearing sands will be reported to the BLM in Vernal, Utah. Copies of State of Utah form OGC-8-X are acceptable. If no flows are detected, samples will be submitted to the BLM along with any water analyses conducted.

3. Anticipated Bottom Hole Pressures

Maximum anticipated bottom hole pressure equals approximately 3176.0 psi.

SHENANDOAH ENERGY INC.  
WONSITS VALLEY UNIT #4W-12-8-21  
356' FNL 475' FWL NWNW  
SECTION 12, T8S, R21E, SLB&M  
UINTAH COUNTY, UTAH  
LEASE # UTU-0806

ONSHORE ORDER NO. 1

MULTI – POINT SURFACE USE & OPERATIONS PLAN

1. **Existing Roads:**

Refer to Topo Maps A and B for location of access roads within a 2 – mile radius.

There will be no improvements made to existing access roads.

2. **Planned Access Roads:**

*Please see the Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in T7S, R21-24E and T8S, R21-24E Standard Operating Practices (SOP).*

Refer to Topo Map B for the location of the proposed access road.

3. **Location of Existing Wells Within a 1 – Mile Radius:**

Please refer to Topo Map C.

4. **Location of Existing & Proposed Facilities:**

*Please see the Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in T7S, R21-24E and T8S, R21-24E Standard Operating Practices (SOP).*

Refer to Topo Map D for the location of the proposed pipeline.

5. **Location and Type of Water Supply:**

*Please see the Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in T7S, R21-24E and T8S, R21-24E Standard Operating Practices (SOP).*

6. **Source of Construction Materials:**

*Please see the Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in T7S, R21-24E and T8S, R21-24E Standard Operating Practices (SOP).*

7. **Methods of Handling Waste Materials:**

*Please see the Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in T7S, R21-24E and T8S, R21-24E Standard Operating Practices (SOP).*

8. **Ancillary Facilities:**

*Please see the Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in T7S, R21-24E and T8S, R21-24E Standard Operating Practices (SOP).*

9. **Well Site Layout:** (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

10. **Plans for Reclamation of the Surface:**

*Please see the Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in T7S, R21-24E and T8S, R21-24E Standard Operating Practices (SOP).*

11. **Surface Ownership:**

The well pad and access road are located on lands owned by:

Ute Indian Tribe  
P.O. Box 143  
Ft. Duchesne, UT 84026

12. **Other Information**

A Class III archaeological survey was conducted by Montgomery Archaeology Consultants. A copy of this report was submitted directly to the appropriate agencies by Montgomery Archaeology Consultants. Cultural resource clearance was recommended for this location.

**Lessee's or Operator's Representative:**

John Busch  
Red Wash Operations Rep.  
Shenandoah Energy Inc.  
11002 East 17500 South  
Vernal, Utah 84078  
(435) 781-4341

**Certification:**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil & Gas Orders, the approved plan of operations, and any applicable Notice to Lessees.

Shenandoah Energy Inc. will be fully responsible for the actions of their subcontractors.

A complete copy of the approved Application for Permit to Drill will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Shenandoah Energy Inc. its' contractors and subcontractors in conformity with this plan and the terms and Conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.


John Busch  
John Busch  
Red Wash Operations Representative

Aug 27-01  
Date

# SHENANDOAH ENERGY, INC.

## LOCATION LAYOUT FOR



WV #4W-12-8-21  
SECTION 12, T8S, R21E, S.L.B.&M.  
356' FNL 475' FWL



SCALE: 1" = 50'  
DATE: 8-13-01  
Drawn By: D.COX

### NOTE:

Flare Pit is to be located  
a min. of 100' from the  
Well Head.



### NOTES:

Elev. Ungraded Ground At Loc. Stake = 5008.2'  
FINISHED GRADE ELEV. AT LOC. STAKE = 5006.9'

**CONFIDENTIAL**

FIGURE #1

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017



# SHENANDOAH ENERGY, INC.

## TYPICAL CROSS SECTIONS FOR

WV #4W-12-8-21


SECTION 12, T8S, R21E, S.L.B.&M.

356' FNL 475' FWL

FIGURE #2

1" = 20'  
X-Section  
Scale  
1" = 50'

DATE: 8-13-01  
Drawn By: D.COX




### APPROXIMATE YARDAGES

CUT  
(12") Topsoil Stripping = 2,520 Cu. Yds.  
Remaining Location = 4,080 Cu. Yds.  
TOTAL CUT = 6,600 CU.YDS.  
FILL = 2,760 CU.YDS.

EXCESS MATERIAL AFTER  
5% COMPACTION = 3,690 Cu. Yds.  
Topsoil & Pit Backfill  
(1/2 Pit Vol.) = 3,690 Cu. Yds.  
EXCESS UNBALANCE = 0 Cu. Yds.  
(After Rehabilitation)

**CONFIDENTIAL**

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017



# LEGEND:

○ PROPOSED LOCATION



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813



**SHENANDOAH ENERGY, INC.**

WV #4W-12-8-21  
 SECTION 12, T8S, R21E, S.L.B.&M.  
 356' FNL 475' FWL

TOPOGRAPHIC  
 MAP


8 15 01  
 MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: K.G. REVISED: 00-00-00



**CONFIDENTIAL**





# LEGEND:

----- PROPOSED ACCESS ROAD  
 ————— EXISTING ROAD



## SHENANDOAH ENERGY, INC.

WV #4W-12-8-21  
 SECTION 12, T8S, R21E, S.L.B.&M.  
 356' FNL 475' FWL



Uintah Engineering & Land Surveying  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813

TOPOGRAPHIC  
 MAP

8 15 01  
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: K.G. REVISED: 00-00-00

B  
 TOPO

CONFIDENTIAL





**U  
E  
S** **Uintah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

WV #4W-12-8-21  
SECTION 12, T8S, R21E, S.L.B.&M.  
356' FNL 475' FWL


**TOPOGRAPHIC  
MAP**

<b>8</b>	<b>15</b>	<b>01</b>
MONTH	DAY	YEAR

SCALE: 1" = 2000'    DRAWN BY: K.G.    REVISED: 00-00-00

C  
TOPO





**APPROXIMATE TOTAL PIPELINE DISTANCE = 300' +/-**

**LEGEND:**

- EXISTING PIPELINE
- - - PROPOSED PIPELINE
- PROPOSED ACCESS



**SHENANDOAH ENERGY, INC.**

**WV #4W-12-8-21**  
**SECTION 12, T8S, R21E, S.L.B.&M.**  
**356' FNL 475' FWL**



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813

**TOPOGRAPHIC**  
**MAP**

**8 15 01**  
 MONTH DAY YEAR

SCALE: 1" = 1000' DRAWN BY: K.G. REVISED: 00-00-00

**D**  
**TOPO**

**CONFIDENTIAL**



**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 08/29/2001

API NO. ASSIGNED: 43-047-34268

WELL NAME: WV 4W-12-8-21

OPERATOR: SHENANDOAH ENERGY INC ( N4235 )

CONTACT: JOHN BUSCH

PHONE NUMBER: 435-781-4341

PROPOSED LOCATION:

NWNW 12 080S 210E

SURFACE: 0356 FNL 0475 FWL

BOTTOM: 0356 FNL 0475 FWL

UINTAH

WONSITS VALLEY ( 710 )

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-0806

SURFACE OWNER: 2 - Indian

PROPOSED FORMATION: WSTC

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering		
Geology		
Surface		

RECEIVED AND/OR REVIEWED:

☒ Plat

☒ Bond: Fed[1] Ind[] Sta[] Fee[]  
(No. U-0969 )

☒ Potash (Y/N)

☒ Oil Shale 190-5 (B) or 190-3 or 190-13

☒ Water Permit  
(No. 43-8496 )

☒ RDCC Review (Y/N)  
(Date: )

☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:

\_\_\_ R649-2-3. Unit WONSITS VALLEY

\_\_\_ R649-3-2. General

Siting: 460 From Qtr/Qtr & 920' Between Wells

\_\_\_ R649-3-3. Exception

☒ Drilling Unit

Board Cause No: 187-06


Eff Date: 8-2-2001

Siting: 460' fr. Unit Boundary


\_\_\_ R649-3-11. Directional Drill

COMMENTS: WV Field Sol, separate file.

STIPULATIONS: 1-Fed.



COUNTY: UINTAH UNIT: WONSITS VALLEY  
CAUSE: 187-06



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

September 5, 2001

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2001 Plan of Development Wonsits Valley Unit,  
Uintah County, Utah.

Pursuant to email between Lisha Cordova, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management. The following wells are planned for calendar year 2001 within the Wonsits Valley Unit, Uintah County, Utah.

Api Number	Well	Location
(Proposed PZ Wasatch)		
43-047-34263	WV 1W-11-8-21	Sec. 11, T8S, R21E 0699 FNL 0615 FEL
43-047-34264	WV 2W-11-8-21	Sec. 11, T8S, R21E 0791 FNL 1996 FEL
43-047-34265	WV 2W-12-8-21	Sec. 12, T8S, R21E 0948 FNL 1818 FEL
43-047-34266	WV 3W-11-8-21	Sec. 11, T8S, R21E 0440 FNL 1946 FWL
43-047-34267	WV 3W-12-8-21	Sec. 12, T8S, R21E 0788 FNL 1941 FWL
43-047-34268	WV 4W-12-8-21	Sec. 12, T8S, R21E 0356 FNL 0475 FWL
43-047-34269	WV 5W-11-8-21	Sec. 11, T8S, R21E 2109 FNL 0676 FWL
43-047-34270	WV 5W-12-8-21	Sec. 12, T8S, R21E 2167 FNL 0586 FWL
43-047-34271	WV 6W-14-8-21	Sec. 14, T8S, R21E 2194 FNL 2012 FWL
43-047-34273	WV 7W-11-8-21	Sec. 11, T8S, R21E 2094 FNL 2092 FEL
43-047-34274	WV 9W-11-8-21	Sec. 11, T8S, R21E 1921 FSL 0758 FEL
43-047-34275	WV 10W-14-8-21	Sec. 14, T8S, R21E 1787 FSL 2028 FEL
43-047-34276	WV 11W-11-8-21	Sec. 11, T8S, R21E 1911 FSL 2075 FWL
43-047-34277	WV 11W-14-8-21	Sec. 14, T8S, R21E 1690 FSL 2145 FWL
43-047-34278	WV 12W-11-8-21	Sec. 11, T8S, R21E 1919 FSL 0917 FWL
43-047-34279	WV 12W-14-8-21	Sec. 14, T8S, R21E 2341 FSL 0841 FWL
43-047-34280	WV 14W-11-8-21	Sec. 11, T8S, R21E 0657 FSL 2058 FWL
43-047-34281	WV 14W-14-8-21	Sec. 14, T8S, R21E 0662 FSL 2002 FWL
43-047-34282	WV 15W-11-8-21	Sec. 11, T8S, R21E 0607 FSL 1933 FEL
43-047-34283	WV 16W-14-8-21	Sec. 14, T8S, R21E 0684 FSL 0537 FEL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Wonsits Valley Unit  
Division of Oil Gas and Mining  
Agr. Sec. Chron



State of Utah  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt  
Governor

Kathleen Clarke  
Executive Director

Lowell P. Braxton  
Division Director

1594 West North Temple, Suite 1210  
PO Box 145801  
Salt Lake City, Utah 84114-5801  
801-538-5340  
801-359-3940 (Fax)  
801-538-7223 (TDD)

September 5, 2001

Shenandoah Energy Inc.  
11002 East 17500 South  
Vernal, UT 84078


Re: Wonsits Valley 4W-12-8-21 Well, 356' FNL, 475' FWL, NW NW , Sec. 12, T. 8 South,  
R. 21 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-34268.

Sincerely,



John R. Baza  
Associate Director

dm

Enclosures

cc: Uintah County Assessor  
Bureau of Land Management, Vernal District Office



Operator: Shenandoah Energy Inc.  
Well Name & Number Wonsits Valley 4W-12-8-21  
API Number: 43-047-34268  
Lease: UTU 0806

Location: NW NW Sec. 12 T. 8 South R. 21 East

### Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENTFORM APPROVED  
OMB No. 1004-0136  
Expires November 30, 2000

## APPLICATION FOR PERMIT TO DRILL OR REENTER


1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		<b>CONFIDENTIAL</b>	5. Lease Serial No. UTU 0806
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone			6. If Indian, Allottee or Tribe Name UTE TRIBAL
2. Name of Operator SHENANDOAH ENERGY INC.			7. If Unit or CA Agreement, Name and No. WONSITS VALLEY
3a. Address 11002 E. 17500 S. VERNAL, UT 84078		3b. Phone No. (include area code) Ph: 435.781.4341 Fx: 435.781.4323	8. Lease Name and Well No. WONSITS VALLEY 4W-12-8-21
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NWNW 356FNL 475FWL At proposed prod. zone		<b>RECEIVED</b> <b>SEP 11 2001</b>	9. API Well No.
14. Distance in miles and direction from nearest town or post office* 15 MILES SOUTHWEST OF REDWASH UTAH			10. Field and Pool, or Exploratory WONSITS VALLEY
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 356		16. No. of Acres in Lease 2480.00	11. Sec., T., R., M., or Blk. and Survey or Area Sec 12 T8S R21E Mer SLB
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 1500		19. Proposed Depth 7940 MD 7940 TVD	12. County or Parish UINTAH
21. Elevations (Show whether DF, KB, RT, GL, etc.) 5015 KB		22. Approximate date work will start 08/24/2001	13. State UT
		20. BLM/BIA Bond No. on file U-0969	17. Spacing Unit dedicated to this well 40.00
		23. Estimated duration 10 DAYS	

## 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature	Name (Printed/Typed) JOHN BUSCH	Date 08/24/2001
Title OPERATIONS		
Approved by (Signature) 	Name (Printed/Typed) EDWIN I FORSMAN	Date 11/1/01
Title ACTING Assistant Field Manager Mineral Resources	Office	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.**NOTICE OF APPROVAL**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #6306 verified by the BLM Well Information System  
For SHENANDOAH ENERGY INC., sent to the Vernal  
Committed to AFMSS for processing by LESLIE CRINKLAW on 09/11/2001 ()DIVISION OF  
OIL, GAS AND MINING**CONDITIONS OF APPROVAL ATTACHED**

\*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\*

OILC324/AF

NO N45

CONDITIONS OF APPROVAL  
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Shenandoah Energy Inc.

Well Name & Number: WVFU #4W-12-8-21

API Number: 43-047-34268

Lease Number: U- 0806

Location: NWNW Sec. 12 T.8S R. 21E

Agreement: Wonsits Valley Unit

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

**CONDITIONS OF APPROVAL**

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

DRILLING PROGRAM

The base of the usable water zone identified at 2149'. To protect this resource, the cement behind the production casing must extend a minimum of 200' above this point.

Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

Other Information

In the event after-hours approvals are necessary, you must contact one of the following individuals:

Ed Forsman (435) 828-7874  
Petroleum Engineer

Kirk Fleetwood (435) 828-7875  
Petroleum Engineer

BLM FAX Machine (435) 781-4410

**SURFACE USE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

Shenandoah Energy, INC. (Shenandoah) will assure the Ute Tribe that any/all contractors and subcontractors have acquired a current Tribal Business License and have updated "Access Permits" prior to construction. All Shenandoah personnel, contractors and subcontractors will have these permits in their vehicles at all times. Companies that have not complied with this COA will be in violation of the Ute Tribal Business License Ordinance, and will be subject to fines and penalties.

Shenandoah employees, representatives, and/or authorized personnel (subcontractors) shall not carry firearms on their person or in their vehicles while working on the Uintah and Ouray Indian Reservation.

Shenandoah employees and/or authorized personnel (subcontractors) in the field will have approved applicable APDs and/or ROW permits/authorizations on their person(s) during all phases of construction.

Shenandoah will notify the Ute Tribe and Bureau of Indian Affairs (BIA) in writing of any requested modification of APDs or Rights-Of Way (ROW). Shenandoah shall receive written notification of authorization or denial of the requested modification. Without authorization, Shenandoah will be subject to fines and penalties.

The Ute Tribe Energy & Minerals Department shall be notified in writing 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday. A Tribal Technician is to routinely monitor construction. Shenandoah shall make arrangements with the Ute Energy & Minerals Department for all monitoring that will exceed regular working hours for Tribal Technicians. A qualified Archaeologist accompanied by a Tribal Technician will monitor any trenching required for the construction of the pipeline in the ROW corridor. Shenandoah is to inform contractors to maintain construction of the pipelines within the approved right of ways.

Shenandoah shall maintain cattleguards and fence integrity as originally constructed for any access roads or pipeline routes which cross the Ute Indian Reservation Boundary Fence.

A corridor ROW, 30 feet wide and 298 feet long, shall be granted for the pipeline. About 122 feet of new access road ROW, 30 feet wide, will be needed to reach the location from existing roads. The new access road and the pipeline do not coincide. Upon authorization by the Ute Tribe Energy & Minerals Department, the ROW may be wider where sharp curves; deep cuts and fills occur; or, where intersections with other roads are required.

Upon completion of the pertinent APD and ROWs, Shenandoah will notify the Ute Tribe Energy & Minerals Department for a Tribal Technician to verify the Affidavit of Completion. When each pipeline has been constructed and completed as built descriptions will be filed with the Ute Tribal Energy and Minerals Department.

Production waters, oil, and other byproducts shall not be placed on access roads or the well pad.

All vehicular traffic, personnel movement, construction and restoration operations will be confined to the areas examined and approved and to the existing roadways and/or evaluated access routes.

Shenandoah will implement "Safety and Emergency Plan" and ensure plan compliance.

Shenandoah shall stop construction activities and notify personnel from the Ute Tribe Energy & Minerals Department and BIA if cultural remains including paleontologic resources (vertebrate fossils) are exposed or identified during construction. The Ute Tribe Department of Cultural Rights and Protection and the BIA will provide mitigation measures prior to allowing construction.

Shenandoah employees and/or authorized personnel (subcontractors) will not be allowed to collect artifacts and paleontologic fossils. No significant cultural resources shall be disturbed.

Shenandoah will control noxious weeds on the well site and ROWs. Shenandoah will be responsible for noxious weed control if weeds spread from the project area onto adjoining land.

Reserve pits will be lined with an impervious synthetic liner. A fence will be constructed around the reserve pit until it is backfilled. Prior to backfilling the reserve pit, all fluids will be pumped from the pit into trucks and hauled to approved disposal sites. When the reserve pits are backfilled, the surplus oil and mud, etc., will be buried a minimum of 3 feet below the surface of the soil.

A closed system will be used during production. This means that production fluids will be contained in leak-proof tanks. All production fluids will be disposed of at approved disposal sites.

Surface pipelines will be constructed to lay on the soil surface. The ROW will not be bladed or cleared of vegetation without authorization of the BIA. Surface pipelines shall be welded in place at well sites or on access roads and on other existing roads then pulled into place with suitable equipment. Vehicles shall not use pipeline ROWs as access roads unless specifically authorized.

Before the site is abandoned, Shenandoah will be required to restore the well site and ROWs to near their original state. The disturbed areas will be reseeded with desirable perennial vegetation.

Soil erosion will be mitigated by reseeding all disturbed areas.



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB NO. 1004-0135  
Expires: November 30, 2000

**SUNDRY NOTICES AND REPORTS ON WELLS**  
**Do not use this form for proposals to drill or to re-enter an**  
**abandoned well. Use form 3160-3 (APD) for such proposals.**

**SUBMIT IN TRIPLICATE - Other instructions on reverse side.**

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. UTU-0806
2. Name of Operator SHENANDOAH ENERGY INC.		6. If Indian, Allottee or Tribe Name UTE TRIBE
3a. Address 11002 EAST 17500 SOUTH VERNAL, UT 84078		7. If Unit or CA/Agreement, Name and/or No. WONSTIS VALLEY
3b. Phone No. (include area code) Ph: 435.781.4309 Fx: 435.781.4329		8. Well Name and No. WONSITS VALLEY 4W-12-8-21
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Sec 12 T8S R21E NWNW 356FNL 475FWL		9. API Well No. 43-047-34268
		10. Field and Pool, or Exploratory WONSITS VALLEY
		11. County or Parish, and State UINTAH COUNTY, UT

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Shenandoah Energy Inc. hereby requests an 1 year extension on the APD for WV 4W-12-8-21.

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date:

By:

RECEIVED

SEP 23 2002

DIVISION OF  
OIL, GAS AND MINING

14. I hereby certify that the foregoing is true and correct. <b>Electronic Submission #14401 verified by the BLM Well Information System For SHENANDOAH ENERGY INC., will be sent to the Vernal</b>	
Name (Printed/Typed) RALEEN SEARLE	Title REGULATORY AFFAIRS ANALYST
Signature <i>Raleen Searle</i>	Date 09/19/2002

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved By _____	Title _____	Date _____
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		
Office _____		

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**\*\* DRAFT \*\* DRAFT \*\* DRAFT \*\* DRAFT \*\* DRAFT \*\* DRAFT \*\* DRAFT \*\***

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB NO. 1004-0135  
Expires: November 30, 2000

**SUNDRY NOTICES AND REPORTS ON WELLS**  
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.*

**SUBMIT IN TRIPLICATE - Other instructions on reverse side.**

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. UTU-0806
2. Name of Operator SHENANDOAH ENERGY INC.		6. If Indian, Allottee or Tribe Name UTE TRIBE
3a. Address 11002 EAST 17500 SOUTH VERNAL, UT 84078		7. If Unit or CA/Agreement, Name and/or No. WONSTIS VALLEY
3b. Phone No. (include area code) Ph: 435.781.4309 Fx: 435.781.4329		8. Well Name and No. WONSITS VALLEY 4W-12-8-21
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Sec 12 T8S R21E NWNW 356FNL 475FWL		9. API Well No. 43-047-34268
		10. Field and Pool, or Exploratory WONSITS VALLEY
		11. County or Parish, and State UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	


13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Shenandoah Energy Inc. hereby requests an 1 year extension on the APD for WV 4W-12-8-21.

**CONDITIONS OF APPROVAL ATTACHED**

14. I hereby certify that the foregoing is true and correct. Electronic Submission #14401 verified by the BLM Well Information System For SHENANDOAH ENERGY INC., sent to the Vernal Committed to AFMSS for processing by LESLIE WALKER on 12/03/2002 ( )		<b>RECEIVED</b>
Name (Printed/Typed) RALEEN SEARLE	Title REGULATORY AFFAIRS ANALYST	
Signature (Electronic Submission)	Date 11/26/2002	DIV. OF OIL, GAS & MINING

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved By 	Title Petroleum Engineer	Date 12/5/02
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		
Office		

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**\*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\***

UDOGM  
03/26/2002  
cc: BIA  
cc: UDOGM

Shenandoah Energy Inc.  
APD Extension

Well: Wonsits Valley 4W-12-8-21

Location: NWNW Sec. 12, T8S, R21E

Lease: UTU 0806

**CONDITIONS OF APPROVAL**

An extension for the referenced APD is granted with the following conditions:

---

1. The extension will expire 11/01/03
2. No other extensions beyond that time frame will be granted or allowed.

If you have any other questions concerning this matter, please contact Kirk Fleetwood of this office at (435) 781-4486

## OPERATOR CHANGE WORKSHEET

## ROUTING

1. GLH

2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

X Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

2/1/2003

<b>FROM:</b> (Old Operator):	<b>TO:</b> ( New Operator):
N4235-Shenandoah Energy Inc 11002 E 17500 S Vernal, UT 84078-8526 Phone: (435) 781-4341	N2460-QEP Uinta Basin Inc 11002 E 17500 S Vernal, UT 84078-8526 Phone: (435) 781-4341

CA No.

Unit:

WONSITS VALLEY UNIT

## WELL(S)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS	Confid
WV 16W-10-8-21	10	080S	210E	4304734250	12436	Federal	GW	P	
WV 1W-11-8-21	11	080S	210E	4304734263		Federal	GW	APD	C
WV 2W-11-8-21	11	080S	210E	4304734264		Federal	GW	APD	C
WV 3W-11-8-21	11	080S	210E	4304734266		Federal	GW	APD	C
WV 5W-11-8-21	11	080S	210E	4304734269		Federal	GW	APD	C
WV 6W-12-8-21	12	080S	210E	4304734245	12436	Federal	GW	TA	
WV 12W-12-8-21	12	080S	210E	4304734248	12436	Federal	GW	TA	
WV 2W-12-8-21	12	080S	210E	4304734265	12436	Federal	GW	DRL	C
WV 3W-12-8-21	12	080S	210E	4304734267		Federal	GW	APD	C
WV 4W-12-8-21	12	080S	210E	4304734268		Federal	GW	APD	C
WV 4W-14-8-21	14	080S	210E	4304734244	12436	Federal	GW	P	
WV 2W-15-8-21	15	080S	210E	4304734242	12436	Federal	GW	P	
WV 7W-15-8-21	15	080S	210E	4304734246	12436	Federal	GW	P	
WV 8W-15-8-21	15	080S	210E	4304734247	12436	Federal	GW	P	
WV 14W-15-8-21	15	080S	210E	4304734249	12436	Federal	GW	P	
WV 16W-15-8-21	15	080S	210E	4304734251	12436	Federal	GW	P	
WV 14W-16-8-21	16	080S	210E	4304734192	12436	State	GW	P	
WV 15W-16-8-21	16	080S	210E	4304734224	12436	State	GW	P	
WV 16W-16-8-21	16	080S	210E	4304734225	12436	State	GW	P	
WV 2W-22-8-21	22	080S	210E	4304734243	12436	Federal	GW	P	

## OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 6/2/2003
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 6/2/2003
3. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 6/19/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 5292864-0151
5. If NO, the operator was contacted on: \_\_\_\_\_

6. (R649-9-2) Waste Management Plan has been received on:

IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: 7/21/2003

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 7/21/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: n/a

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: n/a

**DATA ENTRY:**

1. Changes entered in the **Oil and Gas Database** on: 9/16/2003

2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 9/16/2003

3. Bond information entered in RBDMS on: n/a

4. Fee wells attached to bond in RBDMS on: n/a

**STATE WELL(S) BOND VERIFICATION:**

1. State well(s) covered by Bond Number: 965-003-032

**FEDERAL WELL(S) BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: ESB000024

**INDIAN WELL(S) BOND VERIFICATION:**

1. Indian well(s) covered by Bond Number: 799446

**FEE WELL(S) BOND VERIFICATION:**

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 965-003-033

2. The **FORMER** operator has requested a release of liability from their bond on: n/a

The Division sent response by letter on: n/a

**LEASE INTEREST OWNER NOTIFICATION:**

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

**COMMENTS:**

May 28, 2003

Division of Oil, Gas, & Mining  
1594 West North Temple, Suite 1210  
P. O. Box 145801  
Salt Lake City, Utah 84114-5801

**Attention: John Baza/Jim Thompson**

Gentlemen:

This will serve as notice that through the internal corporate changes described below, activities formerly conducted in the name of either Shenandoah Operating Company, LLC (SOC) and/or Shenandoah Energy, Inc. (SEI) will hereafter be conducted in the name of QEP Uinta Basin, Inc.: i) the Shenandoah entities were purchased in July, 2001 by Questar Market Resources, Inc., which is a mid-level holding company for the non-utility businesses of Questar Corporation, ii) Shenandoah Operating Company, LLC has now been merged into Shenandoah Energy, Inc. (SEI), iii) Shenandoah Energy, Inc. has now been re-named **QEP Uinta Basin, Inc.** pursuant to a State of Delaware Amended and Restated Certificate of Incorporation, iv) the same employees will continue to be responsible for operations of the former SOC and SEI properties, both in the field and in the office. Accordingly, the change involves only an internal corporate name change and no third party change of operator is involved. Please alter your records to reflect the entity name change. Attached is a spreadsheet listing all wells affected by this change.

Should you have any questions, please call me at 303 - 308-3056.

Yours truly,



Frank Nielsen  
Division Landman

Enclosure

RECEIVED

JUN 02 2003

DIV. OF OIL, GAS & MINING





# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, UT 84145-0155

IN REPLY REFER TO  
UT-922

June 9, 2003

QEP Uinta Basin, Inc.  
1050 17<sup>th</sup> Street, Suite 500  
Denver, Colorado 80265

Re: Wonsits Valley Unit  
Uintah County, Utah

Gentlemen:

On May 30, 2003, we received an indenture dated February 1, 2003, whereby Shenandoah Energy, Inc. changed its name and QEP Uinta Basin, Inc. was designated as Successor Unit Operator for the Wonsits Valley Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective June 9, 2003. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under Wonsits Valley Unit Agreement.

Your nationwide (Eastern States) oil and gas bond No. B000024 will be used to cover all operations within the Wonsits Valley Unit.

It is requested that you notify all interested parties of the name change of unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks  
Chief, Branch of Fluid Minerals

Enclosure

bcc: Field Manager - Vernal (w/enclosure)  
SITLA  
Division of Oil, Gas & Mining  
Minerals Adjudication Group  
File - Wonsits Valley Unit (w/enclosure)  
Agr. Sec. Chron  
Fluid Chron

UT922:TAThompson:tt:6/9/03

JUL 07 2003

3104 (932.34)WF  
Nationwide Bond ESB000024

NOTICE

QEP Uinta Basin, Inc.  
1050 17<sup>th</sup> Street Suite 500  
Denver, Colorado 80265

:  
: Oil and Gas  
: lease  
:

Name Change Recognized

Acceptable evidence has been filed in this office concerning the name change of Shenandoah Energy Incorporated into QEP Uinta Basin, Incorporated. QEP Uinta Basin, Incorporated is the surviving entity. This name change is recognized effective April 17, 2003.

Eastern States will notify the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice.

If you identify other leases in which the merging entity maintain an interest, please contact this office and we will appropriately document those files with a copy of this notice.

If you have any questions, please contact Bill Forbes at 703-440-1536.

*S/Wilbert B. Forbes*

Wilbert B. Forbes  
Land Law Examiner  
Branch of Use Authorization  
Division of Resources Planning,  
Use and Protection

bc: JFO,MMS, ES RF, 930 RF, 932.34 RF, E-932: wbf:07 /07/03:440-1536/ QEP Uinta Basin  
MFO

## SEI (N4235) to QEP (N2460) WONSITS VALLEY UNIT

well_name	Sec	T	R	api	Entity	Lease Type	type	stat	unit_name	field	county	type	lease #	bond #
WVU 16	15	080S	210E	4304715447	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 21	16	080S	210E	4304715452	99990	State	WI	A	WONSITS VALLEY	710	S	UINTAH	3 ML-2237	159261960
WVU 31	14	080S	210E	4304715460	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 35	14	080S	210E	4304715463	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 36	10	080S	210E	4304715464	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0806	UT-0969
WVU 41	15	080S	210E	4304715469	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 43	11	080S	210E	4304715471	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0806	UT-0969
WVU 48	10	080S	210E	4304715476	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0806	UT-0969
WVU 50	15	080S	210E	4304715477	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 32	16	080S	210E	4304716513	5265	State	OW	P	WONSITS VALLEY	710	S	UINTAH	3 ML-2237	159261960
WVU 53	10	080S	210E	4304720003	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0806	UT-0969
WVU 55	14	080S	210E	4304720005	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 59	14	080S	210E	4304720018	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 60	15	080S	210E	4304720019	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 62	10	080S	210E	4304720024	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0806	UT-0969
WVU 65	15	080S	210E	4304720041	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 67	15	080S	210E	4304720043	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 68	15	080S	210E	4304720047	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 72	16	080S	210E	4304720058	99990	State	WI	A	WONSITS VALLEY	710	S	UINTAH	3 ML-2237A	159261960
WVU 73	16	080S	210E	4304720066	5265	State	WI	A	WONSITS VALLEY	710	S	UINTAH	3 ML-2237	159261960
WVU 74	16	080S	210E	4304720078	5265	State	OW	P	WONSITS VALLEY	710	S	UINTAH	3 ML-2237	159261960
WVU 75	16	080S	210E	4304720085	5265	State	OW	P	WONSITS VALLEY	710	S	UINTAH	3 ML-2237	159261960
WVU 78	16	080S	210E	4304720115	99990	State	WI	A	WONSITS VALLEY	710	S	UINTAH	3 ML-2237	159261960
WVU 83	23	080S	210E	4304720205	12436	Federal	GW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0809	UT-0969
WVU 97	11	080S	210E	4304730014	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0806	UT-0969
WVU 103	14	080S	210E	4304730021	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 104	15	080S	210E	4304730022	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 105	10	080S	210E	4304730023	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0806	UT-0969
WVU 109	15	080S	210E	4304730045	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 110	14	080S	210E	4304730046	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 112	15	080S	210E	4304730048	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 124	15	080S	210E	4304730745	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0806	
WVU 126	21	080S	210E	4304730796	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0804	UT-0969
WVU 128	10	080S	210E	4304730798	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0806	UT-0969
WVU 132	15	080S	210E	4304730822	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 136	21	080S	210E	4304731047	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0804	UT-0969
WVU 134	16	080S	210E	4304731118	5265	State	OW	P	WONSITS VALLEY	710	S	UINTAH	3 ML-2237	159261960
WVU 137	11	080S	210E	4304731523	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0806	UT-0969
WVU 28-2	11	080S	210E	4304731524	99990	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0806	UT-0969
WVU 141	16	080S	210E	4304731609	5265	State	OW	P	WONSITS VALLEY	710	S	UINTAH	3 ML-2237	159261960
WVU 127	16	080S	210E	4304731611	5265	State	OW	P	WONSITS VALLEY	710	S	UINTAH	3 ML-2237	159261960
WVU 142	16	080S	210E	4304731612	5265	State	OW	P	WONSITS VALLEY	710	S	UINTAH	3 ML-2237	159261960
WVU 133	15	080S	210E	4304731706	5265	Federal	OW	P	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 140	15	080S	210E	4304731707	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0807	UT-0969
WVU 40-2	10	080S	210E	4304731798	5265	Federal	WI	A	WONSITS VALLEY	710	S	UINTAH	1 U-0806	UT-0969

## SEI (N4235) to QEP (N2460) WONSITS VALLEY UNIT

well_name	Sec	T	R	api	Entity	Lease Type	type	stat		unit_name	field		county	type	lease #	bond #
WVU 144	10	080S	210E	4304731807	5265	Federal	OW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVU 143	10	080S	210E	4304731808	5265	Federal	WI	A		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVU 145	18	080S	220E	4304731820	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WVU 121	14	080S	210E	4304731873	5265	Federal	OW	S		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVU 135-2	21	080S	210E	4304732016	5265	Federal	OW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0804	UT-0969
WVU 130	22	080S	210E	4304732307	5265	Federal	OW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0804	UT-0969
WVU 71-2	15	080S	210E	4304732449	5265	Federal	WI	A		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVU 119	21	080S	210E	4304732461	5265	Federal	OW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0804	UT-0969
WVU 120	22	080S	210E	4304732462	5265	Federal	WI	A		WONSITS VALLEY	710	S	UINTAH	1	U-0804	UT-0969
WVU 54 WG	07	080S	220E	4304732821	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-22158	UT-0969
WVU 69 WG	18	080S	220E	4304732829	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WVU 38 WG	08	080S	220E	4304732831	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVU 49 WG	08	080S	220E	4304732832	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVU 138 WG	18	080S	220E	4304733054	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WVU 14 WG	12	080S	210E	4304733070	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-806	UT-0969
WVU 11 WG	12	080S	210E	4304733085	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVU 81 WG	24	080S	210E	4304733086	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0810	UT-0969
WVU 146 WG	19	080S	220E	4304733128	12436	Federal	GW	P		WONSITS VALLEY	630	S	UINTAH	1	U-057	UT-0969
WVU 1W-14-8-21	14	080S	210E	4304733220	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVU 5W-13-8-21	13	080S	210E	4304733221	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVU 9W-13-8-21	13	080S	210E	4304733223	12436	State	GW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-3084A	159261960
WVU 46 WG	07	080S	220E	4304733241	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVU 2W-16-8-21	16	080S	210E	4304733246	12436	State	GW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WVU 2G-16-8-21	16	080S	210E	4304733247	5265	State	OW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WVU 9W-14-8-21	14	080S	210E	4304733269	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVU 7W-13-8-21	13	080S	210E	4304733270	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVU 1W-18-8-22	18	080S	220E	4304733294	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WVU 11W-8-8-22	08	080S	220E	4304733295	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVU 3W-8-8-22	08	080S	220E	4304733493	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVU 5W-7-8-22	07	080S	220E	4304733494	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVU 11W-7-8-22	07	080S	220E	4304733495	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVU 13W-7-8-22	07	080S	220E	4304733496	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVU 1W-7-8-22	07	080S	220E	4304733501	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVU 3W-7-8-22	07	080S	220E	4304733502	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WV 7WRG-7-8-22	07	080S	220E	4304733503	5265	Federal	OW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	UT-0969
WVU 6W-16-8-21	16	080S	210E	4304733527	12436	State	GW	P	C	WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WVU 16W-9-8-21	09	080S	210E	4304733529	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0805	UT-0969
WVU 1W-12-8-21	12	080S	210E	4304733531	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVU 1W-13-8-21	13	080S	210E	4304733532	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVU 3W-18-8-22	18	080S	220E	4304733533	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WVU 9W-12-8-21	12	080S	210E	4304733534	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVU 11W-12-8-21	12	080S	210E	4304733535	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVU 11W-13-8-21	13	080S	210E	4304733536	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVU 13W-12-8-21	12	080S	210E	4304733537	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVU 13W-18-8-22	18	080S	220E	4304733538	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969

## SEI (N4235) to QEP (N2460) WONSITS VALLEY UNIT

well_name	Sec	T	R	api	Entity	Lease Type	type	stat		unit_name	field		county	type	lease #	bond #
WVFU 6G-16-8-21	16	080S	210E	4304733564	5265	State	OW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WVFU 16G-9-8-21	09	080S	210E	4304733565	5265	Federal	OW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0805	UT-0969
WVFU 1W-21-8-21	21	080S	210E	4304733602	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-68217	UT-0969
WVFU 3W-13-8-21	13	080S	210E	4304733603	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 3W-22-8-21	22	080S	210E	4304733604	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0804	UT-0969
WVFU 3W-24-8-21	24	080S	210E	4304733605	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0810	UT-0969
WVFU 13W-13-8-21	13	080S	210E	4304733606	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 13W-14-8-21	14	080S	210E	4304733607	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVFU 15W-13-8-21	13	080S	210E	4304733608	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 1W-24-8-21	24	080S	210E	4304733613	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0810	UT-0969
WVFU 11W-18-8-22	18	080S	220E	4304733626	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WVFU 16W-2-8-21	02	080S	210E	4304733645	5265	State	OW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2785	159261960
WVFU 9W-2-8-21	02	080S	210E	4304733648	12436	State	GW	P		WONSITS VALLEY	2	S	UINTAH	3	ML-2785	159261960
WVFU 12W-16-8-21	16	080S	210E	4304733649	12436	State	GW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WVFU 12G-16-8-21	16	080S	210E	4304733650	5265	State	OW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WVFU 2W-10-8-21	10	080S	210E	4304733655	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 4W-11-8-21	11	080S	210E	4304733657	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 12W-10-8-21	10	080S	210E	4304733659	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 12G-10-8-21	10	080S	210E	4304733660	5265	Federal	OW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 15W-9-8-21	09	080S	210E	4304733661	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0805	UT-0969
WVFU 15G-9-8-21	09	080S	210E	4304733662	5265	Federal	OW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0805	UT-0969
WVFU 2W-13-8-21	13	080S	210E	4304733791	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 6W-13-8-21	13	080S	210E	4304733792	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 8W-13-8-21	13	080S	210E	4304733793	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 10W-1-8-21	01	080S	210E	4304733794	12436	Federal	GW	S		WONSITS VALLEY	710	S	UINTAH	1	U-0802	UT-0969
WVFU 10W-13-8-21	13	080S	210E	4304733795	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 16W-13-8-21	13	080S	210E	4304733796	12436	State	GW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-3084	159261960
WVFU 12W-7-8-22	07	080S	220E	4304733808	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVFU 6W-8-8-22	08	080S	220E	4304733811	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVFU 7W-8-8-22	08	080S	220E	4304733812	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVFU 10W-7-8-22	07	080S	220E	4304733813	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVFU 10W-8-8-22	08	080S	220E	4304733814	13450	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVFU 12W-8-8-22	08	080S	220E	4304733815	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVFU 14W-7-8-22	07	080S	220E	4304733816	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVFU 16W-7-8-22	07	080S	220E	4304733817	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVFU 6W-7-8-22	07	080S	220E	4304733828	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-022158	UT-0969
WVFU 6W-18-8-22	18	080S	220E	4304733842	12436	Federal	GW	P	C	WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WVFU 6WC-18-8-22	18	080S	220E	4304733843	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WVFU 6WD-18-8-22	18	080S	220E	4304733844	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WVFU 5W-23-8-21	23	080S	210E	4304733860	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0809	UT-0969
WVFU 7W-23-8-21	23	080S	210E	4304733861	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0809	UT-0969
WVFU 8W-12-8-21	12	080S	210E	4304733862	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 10W-12-8-21	12	080S	210E	4304733863	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 14W-12-8-21	12	080S	210E	4304733864	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 16W-12-8-21	12	080S	210E	4304733865	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969

## SEI (N4235) to QEP (N2460) WONSITS VALLEY UNIT

well_name	Sec	T	R	api	Entity	Lease Type	type	stat		unit_name	field		county	type	lease #	bond #
WVFU 1W-15-8-21	15	080S	210E	4304733902	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVFU 1W-22-8-21	22	080S	210E	4304733903	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-06304	UT-0969
WVFU 1W-23-8-21	23	080S	210E	4304733904	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0809	UT-0969
WVFU 6W-11-8-21	11	080S	210E	4304733906	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WV 7W-22-8-21	22	080S	210E	4304733907	13230	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0804	UT-0969
WVFU 7W-24-8-21	24	080S	210E	4304733908	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0810	UT-0969
WVFU 10W-11-8-21	11	080S	210E	4304733910	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 11W-15-8-21	15	080S	210E	4304733911	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVFU 11W-17-8-21	17	080S	210E	4304733912	13228	Federal	GW	P		WONSITS VALLEY	2	S	UINTAH	1	UTU-68219	UT-0969
WVFU 13W-11-8-21	11	080S	210E	4304733913	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 13W-15-8-21	15	080S	210E	4304733914	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVFU 15W-10-8-21	10	080S	210E	4304733916	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 15W-15-8-21	15	080S	210E	4304733917	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVFU 5W-14-8-21	14	080S	210E	4304733953	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVFU 7W-14-8-21	14	080S	210E	4304733955	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVFU 8W-11-8-21	11	080S	210E	4304733957	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 8W-14-8-21	14	080S	210E	4304733958	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVFU 9W-15-8-21	15	080S	210E	4304733959	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVFU 12W-13-8-21	13	080S	210E	4304733961	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WVFU 14W-13-8-21	13	080S	210E	4304733962	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WVFU 15W-14-8-21	14	080S	210E	4304733963	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WVFU 2W-18-8-22	18	080S	220E	4304733986	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WV 8W-18-8-22	18	080S	220E	4304733989	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-9617	UT-0969
WVFU 10W-18-8-22	18	080S	220E	4304733991	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WVFU 12W-18-8-22	18	080S	220E	4304733993	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WV 14W-18-8-22	18	080S	220E	4304733995	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-057	UT-0969
WVFU 6W-1-8-21	01	080S	210E	4304734008		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	U-0802	UT-0969
WVFU 8W-1-8-21	01	080S	210E	4304734009	12436	Federal	GW	DRL	C	WONSITS VALLEY	710	S	UINTAH	1	U-0802	UT-0969
WV 10G-2-8-21	02	080S	210E	4304734035	5265	State	OW	P		WONSITS VALLEY	2	S	UINTAH	3	ML-2785	159261960
WV 14G-2-8-21	02	080S	210E	4304734036	5265	State	OW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2785	159261960
WV 4W-17-8-22	17	080S	220E	4304734038	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-055	UT-0969
WV 16W-1-8-21	01	080S	210E	4304734047		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	U-0802	UT-0969
WV 13G-2-8-21	02	080S	210E	4304734068	5265	State	OW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2785-A	159261960
WV 5G-16-8-21	16	080S	210E	4304734107	5265	State	OW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WV 12G-1-8-21	01	080S	210E	4304734108	5265	Federal	OW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0802	UT-0969
WV 2W-14-8-21	14	080S	210E	4304734140	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	U-0969
GH 2W-21-8-21	21	080S	210E	4304734141	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0804	U-0969
WV 2W-23-8-21	23	080S	210E	4304734142	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0809	U-0969
GH 3W-21-8-21	21	080S	210E	4304734143	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0804	U-0969
WV 4W-13-8-21	13	080S	210E	4304734144	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
GH 4W-21-8-21	21	080S	210E	4304734145	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0804	UT-0969
WV 4W-22-8-21	22	080S	210E	4304734146	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0804	U-0969
WV 16W-11-8-21	11	080S	210E	4304734155	12436	Federal	GW	S		WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 3W-19-8-22	19	080S	220E	4304734187	12436	Federal	GW	P		WONSITS VALLEY	630	S	UINTAH	1	UTU-057	UT-0969
WV 4W-23-8-21	23	080S	210E	4304734188	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-809	UT-0969

## SEI (N4235) to QEP (N2460) WONSITS VALLEY UNIT

well_name	Sec	T	R	api	Entity	Lease Type	type	stat		unit_name	field		county	type	lease #	bond #
WV 6W-23-8-21	23	080S	210E	4304734189	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-809	UT-0969
WV 11W-16-8-21	16	080S	210E	4304734190	12436	State	GW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WV 13W-16-8-21	16	080S	210E	4304734191	12436	State	GW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237A	159261960
WV 14W-16-8-21	16	080S	210E	4304734192	12436	State	GW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WV 15W-16-8-21	16	080S	210E	4304734224	12436	State	GW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WV 16W-16-8-21	16	080S	210E	4304734225	12436	State	GW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237A	159261960
WV 2W-15-8-21	15	080S	210E	4304734242	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 2W-22-8-21	22	080S	210E	4304734243	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0804	UT-0969
WV 4W-14-8-21	14	080S	210E	4304734244	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WV 6W-12-8-21	12	080S	210E	4304734245	12436	Federal	GW	TA		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WV 7W-15-8-21	15	080S	210E	4304734246	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	U-0807	UT-0969
WV 8W-15-8-21	15	080S	210E	4304734247	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 12W-12-8-21	12	080S	210E	4304734248	12436	Federal	GW	TA		WONSITS VALLEY	710	S	UINTAH	1	U-0806	UT-0969
WV 14W-15-8-21	15	080S	210E	4304734249	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 16W-10-8-21	10	080S	210E	4304734250	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 16W-15-8-21	15	080S	210E	4304734251	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 1W-11-8-21	11	080S	210E	4304734263		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 2W-11-8-21	11	080S	210E	4304734264		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 2W-12-8-21	12	080S	210E	4304734265	12436	Federal	GW	DRL	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 3W-11-8-21	11	080S	210E	4304734266		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 3W-12-8-21	12	080S	210E	4304734267		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 4W-12-8-21	12	080S	210E	4304734268		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 5W-11-8-21	11	080S	210E	4304734269		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 5W-12-8-21	12	080S	210E	4304734270	12436	Federal	GW	DRL	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 6W-14-8-21	14	080S	210E	4304734271	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 9W-11-8-21	11	080S	210E	4304734274		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 10W-14-8-21	14	080S	210E	4304734275	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 11W-11-8-21	11	080S	210E	4304734276		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 11W-14-8-21	14	080S	210E	4304734277	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 12W-11-8-21	11	080S	210E	4304734278		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 12W-14-8-21	14	080S	210E	4304734279	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 14W-11-8-21	11	080S	210E	4304734280		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 14W-14-8-21	14	080S	210E	4304734281	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 15W-11-8-21	11	080S	210E	4304734282		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0806	UT-0969
WV 16W-14-8-21	14	080S	210E	4304734283	5265	Federal	OW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 1W-16-8-21	16	080S	210E	4304734288		State	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WV 3W-15-8-21	15	080S	210E	4304734289		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 3W-16-8-21	16	080S	210E	4304734290		State	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WV 4W-15-8-21	15	080S	210E	4304734291		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 4W-16-8-21	16	080S	210E	4304734292		State	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WV 5W-15-8-21	15	080S	210E	4304734293		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 6W-15-8-21	15	080S	210E	4304734294	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WV 10W-15-8-21	15	080S	210E	4304734295	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0807	UT-0969
WVU 5W-16-8-21	16	080S	210E	4304734321	12436	State	GW	DRL		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	04127294
WV 7W-16-8-21	16	080S	210E	4304734322	12436	State	GW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960



## SEI (N4235) to QEP (N2460) WONSITS VALLEY UNIT

well_name	Sec	T	R	api	Entity	Lease Type	type	stat		unit_name	field		county	type	lease #	bond #
WV 8W-16-8-21	16	080S	210E	4304734323		State	GW	APD		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WV 9W-16-8-21	16	080S	210E	4304734325	12436	State	GW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WV 10W-16-8-21	16	080S	210E	4304734326	12436	State	GW	P		WONSITS VALLEY	710	S	UINTAH	3	ML-2237	159261960
WVU 4W-24-8-21	24	080S	210E	4304734330	12436	Federal	GW	P		WONSITS VALLEY	710	S	UINTAH	1	UTU-0810	U-0969
WVU 2W-24-8-21	24	080S	210E	4304734337		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0810	UT-0969
WVU 6W-24-8-21	24	080S	210E	4304734338		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0810	UT-0969
WVU 8W-23-8-21	23	080S	210E	4304734339		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0809	UT-0969
WVU 8W-24-8-21	24	080S	210E	4304734340	12436	Federal	GW	P	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0810	UT-0969
WV 2G-7-8-22	07	080S	220E	4304734355		Federal	OW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	UT-0969
WV 2W-7-8-22	07	080S	220E	4304734356		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	UT-0969
WV 4G-8-8-22	08	080S	220E	4304734357		Federal	OW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	UT-0969
WV 4WA-18-8-22	18	080S	220E	4304734358		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-057	UT-0969
WV 4WD-18-8-22	18	080S	220E	4304734359		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-057	UT-0969
WV 13WA-18-8-22	18	080S	220E	4304734361		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-057	UT-0969
WV 13WD-18-8-22	18	080S	220E	4304734362		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-057	UT-0969
WV 2WA-18-8-22	18	080S	220E	4304734426		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-057	UT-0969
WV 2WD-18-8-22	18	080S	220E	4304734427		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-057	UT-0969
WV 3WA-18-8-22	18	080S	220E	4304734428		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-057	UT-0969
WV 3WD-18-8-22	18	080S	220E	4304734429		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-057	UT-0969
WV 4W-8-8-22	08	080S	220E	4304734457		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	UT-0969
WV 1W-8-8-22	08	080S	220E	4304734467		Federal	GW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	UT-0969
WV 2W-8-8-22	08	080S	220E	4304734468	12436	Federal	GW	P	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	UT-0969
WV 8W-7-8-22	07	080S	220E	4304734469	12436	Federal	GW	DRL	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	UT-0969
WV 8W-22-8-21	22	080S	210E	4304734564	12436	Federal	GW	P	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-0804	U-0969
WV 3G-8-8-22	08	080S	220E	4304734596	5265	Federal	OW	TA	C	WONSITS VALLEY	710	S	UINTAH	1	U-022158	U-0969
WONSITS VALLEY 1G-7-8-22	07	080S	220E	4304734597		Federal	OW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	U-022158	U-0969
WONSITS VALLEY 5G-8-8-22	08	080S	220E	4304734612		Federal	OW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	U-0969
WONSITS VALLEY 7G-8-8-22	08	080S	220E	4304734613		Federal	OW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-76508	U-0969
WV 11G-8-8-22	08	080S	220E	4304734614		Federal	OW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	U-0969
WV 13G-8-8-22	08	080S	220E	4304734615		Federal	OW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	U-0969
WV 15G-7-8-22	07	080S	220E	4304734626		Federal	OW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	U-0969
WV 11G-7-8-22	07	080S	220E	4304734627		Federal	OW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	U-0969
WONSITS VALLEY 7G-7-8-22	07	080S	220E	4304734628		Federal	OW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	U-0969
WONSITS VALLEY 9G-7-8-22	07	080S	220E	4304734629		Federal	OW	APD	C	WONSITS VALLEY	710	S	UINTAH	1	UTU-02215	U-0969
WV EXT 2W-17-8-21	17	080S	210E	4304734928	12436	Federal	GW	DRL	C	WONSITS VALLEY	610	S	UINTAH	1	UTU-68219	UT-1237



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir  
Use "APPLICATION FOR PERMIT--" for such proposals

***SUBMIT IN TRIPLICATE***

1. Type of Well

Oil Gas  
☐ Well ☒ Well ☐ Other

2. Name of Operator

**QEP UINTA BASIN, INC.**

3. Address and Telephone No.

**11002 E. 17500 S. VERNAL, UT 84078-8526**

Contact: **dahn.caldwell@questar.com**  
**435.781.4342 Fax 435.781.4357**

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

**NWNW, Sec 12, T8S, R21E**  
**356' FNL, 475' FWL**

5. Lease Designation and Serial No.

**UTU-0806**

6. If Indian, Allottee or Tribe Name

**Ute Tribe**

7. If Unit or CA, Agreement Designation

**Wonsits Valley**

8. Well Name and No.

**WV 4W 12 8 21**

9. API Well No.

**43-047-34268**

10. Field and Pool, or Exploratory Area

**WONSITS VALLEY**

11. County or Parish, State

**UINTAH COUNTY, UTAH**

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent  
☒ Subsequent Report  
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment  
☐ Recompletion  
☐ Plugging Back  
☐ Casing Repair  
☐ Altering Casing  
☒ Other **Spud**  
☐ Change of Plans  
☐ New Construction  
☐ Non-Routine Fracturing  
☐ Water Shut-Off  
☐ Conversion to Injection  
☐ Dispose Water

(Note) Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

14. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)

**This well was spud on 9/26/03. Drilled 40' 26" hole. Set 40' 20" conductor pipe. Cement w/ 2.2 yards ready mix cement.**

RECEIVED

OCT 03 2003

DIV. OF OIL, GAS & MINING

3 - BLM, 2 - Utah OG&M, 1 - Denver, 1 - file Word file-server

14. I hereby certify that the foregoing is true and correct.  
Signed [Signature]

Title **Authorized Representative**

Date **10/01/03**

(This space for Federal or State office use)

Approved by:

Title

Date

Conditions of approval, if any

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**CONFIDENTIAL**

ENTITY ACTION FORM - FORM 6

OPERATOR: QEP, Uinta Basin, Inc.  
ADDRESS: 11002 East 17500 South  
Vernal, Utah 84078-8526

OPERATOR ACCT. No. N-2460

(435)781-4300

Action Code	Current Entity No.	New Entity No.	API Number	Well Name	QQ	SC	TP	RG	County	Spud Date	Effective Date
B	99999	12436	43-047-34268	WV 4W 12 8 21	NWNW	12	8S	21E	Uintah	9/26/03	10/9/03

WELL 1 COMMENTS: *WSTC*

WELL 2 COMMENTS:

WELL 3 COMMENTS:

WELL 4 COMMENTS:


WELL 5 COMMENTS:

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)


NOTE: Use COMMENT section to explain why each Action Code was selected

(3/89)

  
Signature

Clerk Specialist 10/01/03  
Title Date

Phone No. (435) 781-4342



CONFIDENTIAL



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, UT 84145-0155



IN REPLY REFER TO  
3180  
UT-922

June 28, 2005

QEP Uinta Basin, Inc.  
Attn: Angela Page  
1050 Seventeenth Street, Suite 500  
Denver, Colorado 80265

Re: Initial Consolidated  
Wasatch-Mesaverde-Mancos Formation PA  
Wonsits Valley Unit  
Uintah County, Utah

Gentlemen:

The Initial Consolidated Wasatch-Mesaverde-Mancos Formation PA, Wonsits Valley Unit, CRS No. UTU63043D, AFS No. 891008482D is hereby approved effective as of March 10, 2004, pursuant to Section 11 of the Wonsits Valley Unit Agreement, Uintah County, Utah.

The Initial Consolidated Wasatch-Mesaverde-Mancos Formation PA results in an Initial Participating Area of 8,022.50 acres. Copies of the approved request are being distributed to the appropriate agencies and one copy is returned herewith. Please advise all interested parties of the establishment of the Initial Consolidated Wasatch-Mesaverde-Mancos Formation PA, Wonsits Valley Unit, and the effective date.

Sincerely,

/s/ Terry Catlin

Terry Catlin  
Acting Chief, Branch of Fluid Minerals

Enclosure

bcc: Division of Oil, Gas & Mining  
SITLA  
Wonsits Valley Unit w/enclosure  
Field Manager - Vernal w/enclosure  
Agr. Sec. Chron.  
Reading File  
Central Files

UT922:TATHOMPSON:tt:6/28/05

RECEIVED  
JUL 0 / 2005  
DIV. OF OIL, GAS & MINING

WONSITS VALLEY WASATCH/MESAVERDE/MANCOS PARTICIPATING AREA  
Effective 3/10/2004 per BLM

Entity Eff Date	From Entity to PA Entity	Well	API	Sec	Twsp	Rng	Q/Q	Unit
8/30/2005	12436 to 14864	WV 10W-1-8-21	4304733794	01	080S	210E	NWSE	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 8W-1-8-21	4304734009	01	080S	210E	SENE	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 9W-2-8-21	4304733648	02	080S	210E	NESE	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 16W-9-8-21	4304733529	09	080S	210E	SESE	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 15W-9-8-21	4304733661	09	080S	210E	SWSE	Wonsits Valley
8/30/2005	12436 to 14864	WV 2W-10-8-21	4304733655	10	080S	210E	NWNE	Wonsits Valley
8/30/2005	12436 to 14864	WV 12W-10-8-21	4304733659	10	080S	210E	NWSW	Wonsits Valley
8/30/2005	12436 to 14864	WV 15W-10-8-21	4304733916	10	080S	210E	SWSE	Wonsits Valley
8/30/2005	12436 to 14864	WV 16W-10-8-21	4304734250	10	080S	210E	SESE	Wonsits Valley
8/30/2005	12436 to 14864	WV 14MU-10-8-21	4304735879	10	080S	210E	SESW	Wonsits Valley
8/30/2005	14487 to 14864	WV 14MU-10-8-21	4304735879	10	080S	210E	SESW	Wonsits Valley
8/30/2005	12436 to 14864	WV 4W-11-8-21	4304733657	11	080S	210E	NWNW	Wonsits Valley
8/30/2005	12436 to 14864	WV 6W-11-8-21	4304733906	11	080S	210E	SENE	Wonsits Valley
8/30/2005	12436 to 14864	WV 10W-11-8-21	4304733910	11	080S	210E	NWSE	Wonsits Valley
8/30/2005	12436 to 14864	WV 13W-11-8-21	4304733913	11	080S	210E	SWSW	Wonsits Valley
8/30/2005	12436 to 14864	WV 8W-11-8-21	4304733957	11	080S	210E	SENE	Wonsits Valley
8/30/2005	12436 to 14864	WV 16W-11-8-21	4304734155	11	080S	210E	SESE	Wonsits Valley
8/30/2005	12436 to 14864	WV 9W-11-8-21	4304734274	11	080S	210E	NESE	Wonsits Valley
8/30/2005	14437 to 14864	WV 14M-11-8-21	4304734280	11	080S	210E	SESW	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 14 WG	4304733070	12	080S	210E	SWSE	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 11 WG	4304733085	12	080S	210E	SWNE	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 1W-12-8-21	4304733531	12	080S	210E	NENE	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 9W-12-8-21	4304733534	12	080S	210E	NESE	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 11W-12-8-21	4304733535	12	080S	210E	NESW	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 13W-12-8-21	4304733537	12	080S	210E	SWSW	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 8W-12-8-21	4304733862	12	080S	210E	SENE	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 10W-12-8-21	4304733863	12	080S	210E	NWSE	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 14W-12-8-21	4304733864	12	080S	210E	SESW	Wonsits Valley
8/30/2005	12436 to 14864	WVFU 16W-12-8-21	4304733865	12	080S	210E	SESE	Wonsits Valley
8/30/2005	12436 to 14864	WV 12W-12-8-21	4304734248	12	080S	210E	NWSW	Wonsits Valley
8/30/2005	12436 to 14864	WV 2W-12-8-21	4304734265	12	080S	210E	NWNE	Wonsits Valley
8/30/2005	12436 to 14864	WV 3W-12-8-21	4304734267	12	080S	210E	NENW	Wonsits Valley
8/30/2005	12436 to 14864	WV 4W-12-8-21	4304734268	12	080S	210E	NWNW	Wonsits Valley
8/30/2005	12436 to 14864	WV 5W-12-8-21	4304734270	12	080S	210E	SWNW	Wonsits Valley

CONFIDENTIAL

CONFIDENTIAL

Division of Oil, Gas and Mining  
**OPERATOR CHANGE WORKSHEET**

**ROUTING**

1. DJJ
2. CDW

Change of Operator (Well Sold)

**X - Operator Name Change/Merger**

The operator of the well(s) listed below has changed, effective:

**1/1/2007**

**FROM: (Old Operator):**  
 N2460-QEP Uinta Basin, Inc.  
 1050 17th St, Suite 500  
 Denver, CO 80265

Phone: 1 (303) 672-6900

**TO: ( New Operator):**  
 N5085-Questar E&P Company  
 1050 17th St, Suite 500  
 Denver, CO 80265

Phone: 1 (303) 672-6900

CA No.				Unit:	WONSITS VALLEY UNIT				
WELL NAME			SEC TWN RNG		API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
SEE ATTACHED LISTS					*				

**OPERATOR CHANGES DOCUMENTATION**

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 4/19/2007
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 4/16/2007
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 1/31/2005
- Is the new operator registered in the State of Utah: Business Number: 764611-0143
- (R649-9-2) Waste Management Plan has been received on: IN PLACE
- Inspections of LA PA state/fee well sites complete on: n/a
- Reports current for Production/Disposition & Sundries on: n/a
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 4/23/2007 BIA
- Federal and Indian Units:**  
 The BLM or BIA has approved the successor of unit operator for wells listed on: 4/23/2007
- Federal and Indian Communization Agreements ("CA"):**  
 The BLM or BIA has approved the operator for all wells listed within a CA on: \_\_\_\_\_
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: \_\_\_\_\_

**DATA ENTRY:**

- Changes entered in the **Oil and Gas Database** on: 4/30/2007 and 5/15/2007
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 4/30/2007 and 5/15/2007
- Bond information entered in RBDMS on: 4/30/2007 and 5/15/2007
- Fee/State wells attached to bond in RBDMS on: 4/30/2007 and 5/15/2007
- Injection Projects to new operator in RBDMS on: 4/30/2007 and 5/15/2007
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a

**BOND VERIFICATION:**

- Federal well(s) covered by Bond Number: ESB000024
- Indian well(s) covered by Bond Number: 799446
- (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number 965003033
- The **FORMER** operator has requested a release of liability from their bond on: n/a

**LEASE INTEREST OWNER NOTIFICATION:**

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

**COMMENTS: THIS IS A COMPANY NAME CHANGE.**

**SOME WELL NAMES HAVE BEEN CHANGED AS REQUESTED**

QEP Uinta Basin (N2460) to QUESTAR E and P (N5085)  
WONSITS VALLEY UNIT

4/30/2007 and 5/15/2007

Original Well Name	Well Name & No.	Q/Q	SEC	TWP	RNG	API	Entity	Lease	Well Type	Status
WVU 16	WV 16	NENE	15	080S	210E	4304715447	5265	Federal	WI	A
WVU 31	WV 31	NENW	14	080S	210E	4304715460	5265	Federal	WI	A
WVU 35	WV 35	NESW	14	080S	210E	4304715463	5265	Federal	WI	A
WV 36	WV 36	NESW	10	080S	210E	4304715464	5265	Federal	WI	A
WVU 41	WV 41	NENW	15	080S	210E	4304715469	5265	Federal	WI	A
WV 43	WV 43	SWSW	11	080S	210E	4304715471	5265	Federal	OW	P
WV 48	WV 48	SWNE	10	080S	210E	4304715476	5265	Federal	OW	P
WVU 50	WV 50	SWNE	15	080S	210E	4304715477	5265	Federal	WI	A
WV 53	WV 53	SWSE	10	080S	210E	4304720003	5265	Federal	OW	P
WVU 55	WV 55	SWNE	14	080S	210E	4304720005	5265	Federal	OW	P
WVU 59	WV 59	SWNW	14	080S	210E	4304720018	5265	Federal	WI	A
WVU 60	WV 60	SWSE	15	080S	210E	4304720019	5265	Federal	WI	A
WV 62	WV 62	SWSW	10	080S	210E	4304720024	5265	Federal	OW	P
WVU 65	WV 65	SWNW	15	080S	210E	4304720041	5265	Federal	OW	P
WVU 67	WV 67	NESW	15	080S	210E	4304720043	5265	Federal	WI	A
WVU 68	WV 68	NESE	15	080S	210E	4304720047	5265	Federal	WI	A
WVU 83	WV 83 WG	NENW	23	080S	210E	4304720205	14864	Federal	GW	S
WV 97	WV 97	NWSW	11	080S	210E	4304730014	5265	Federal	WI	A
WVU 103	WV 103	NWNW	14	080S	210E	4304730021	5265	Federal	OW	P
WVU 104	WV 104	NWNE	15	080S	210E	4304730022	5265	Federal	OW	P
WV 105	WV 105	SESE	10	080S	210E	4304730023	5265	Federal	OW	P
WVU 109	WV 109	SENE	15	080S	210E	4304730045	5265	Federal	OW	P
WVU 110	WV 110	SENE	14	080S	210E	4304730046	5265	Federal	OW	P
WVU 112	WV 112	SENE	15	080S	210E	4304730048	5265	Federal	OW	P
WVU 124	WV 124	NWSE	15	080S	210E	4304730745	5265	Federal	OW	P
WVU 126	WV 126	NWNE	21	080S	210E	4304730796	5265	Federal	WI	A
WV 128	WV 128	SESW	10	080S	210E	4304730798	5265	Federal	OW	P
WVU 132	WV 132	NWSW	15	080S	210E	4304730822	5265	Federal	OW	P
WVU 136	WV 136	NENW	21	080S	210E	4304731047	5265	Federal	OW	S
WV 137	WV 137	SENE	11	080S	210E	4304731523	5265	Federal	OW	P
WV 28-2	WV 28-2	NESW	11	080S	210E	4304731524	99990	Federal	WI	A
WVU 133	WV 133	SESW	15	080S	210E	4304731706	5265	Federal	OW	P
WVU 140	WV 140	NWNW	15	080S	210E	4304731707	5265	Federal	WI	A
WV 40-2	WV 40-2	NESE	10	080S	210E	4304731798	5265	Federal	WI	A
WVU 144	WV 144	SENE	10	080S	210E	4304731807	5265	Federal	OW	P
WV 143	WV 143	NWSE	10	080S	210E	4304731808	5265	Federal	WI	A
WVU 145	WV 145	NWNW	18	080S	220E	4304731820	14864	Federal	GW	P
WVU 121	WV 121	NWSW	14	080S	210E	4304731873	5265	Federal	OW	TA
WVU 135-2	WV 135-2	NENE	21	080S	210E	4304732016	5265	Federal	OW	P
WVU 130	WV 130	NWNW	22	080S	210E	4304732307	5265	Federal	OW	P
WVU 71-2	WV 71-2	SWSW	15	080S	210E	4304732449	5265	Federal	WI	A

QEP Uinta Basin (N2460) to QUESTAR E and P (N5085)  
WONSITS VALLEY UNIT

4/30/2007 and 5/15/2007

Original Well Name	Well Name & No.	Q/Q	SEC	TWP	RNG	API	Entity	Lease	Well Type	Status
WVUFU 119	WV 119	NWNW	21	080S	210E	4304732461	5265	Federal	OW	P
WVUFU 120	WV 120	NENW	22	080S	210E	4304732462	5265	Federal	WI	A
WVUFU 54 WG	WV 54 WG	SWSE	07	080S	220E	4304732821	14864	Federal	GW	P
WVUFU 69 WG	WV 69 WG	SWNE	18	080S	220E	4304732829	14864	Federal	GW	P
WVUFU 38 WG	WV 38 WG	SWNW	08	080S	220E	4304732831	14864	Federal	GW	P
WVUFU 49 WG	WV 49 WG	SWSW	08	080S	220E	4304732832	14864	Federal	GW	P
WVUFU 138 WG	WV 138 WG	SWNW	18	080S	220E	4304733054	14864	Federal	GW	P
WVUFU 14 WG	WV 14 WG	SWSE	12	080S	210E	4304733070	14864	Federal	GW	P
WVUFU 11 WG	WV 11 WG	SWNE	12	080S	210E	4304733085	14864	Federal	GW	P
WVUFU 81 WG	WV 81 WG	SWNW	24	080S	210E	4304733086	14864	Federal	GW	P
WVUFU 146 WG	WV 146 WG	NWNW	19	080S	220E	4304733128	14864	Federal	GW	P
WVUFU 1W-14-8-21	WV 1W-14-8-21	NENE	14	080S	210E	4304733220	14864	Federal	GW	P
WVUFU 5W-13-8-21	WV 5W-13-8-21	SWNW	13	080S	210E	4304733221	14864	Federal	GW	P
WVUFU 46 WG	WVUFU 46 WG	NESE	07	080S	220E	4304733241	14864	Federal	GW	P
WVUFU 9W-14-8-21	WV 9W-14-8-21	NESE	14	080S	210E	4304733269	14864	Federal	GW	P
WVUFU 7W-13-8-21	WV 7W-13-8-21	SWNE	13	080S	210E	4304733270	14864	Federal	GW	P
WVUFU 1W-18-8-22	WV 1W-18-8-22	NENE	18	080S	220E	4304733294	14864	Federal	GW	P
WVUFU 11W-8-8-22	WV 11W-8-8-22	NESW	08	080S	220E	4304733295	14864	Federal	GW	P
WVUFU 3W-8-8-22	WV 3W-8-8-22	NENW	08	080S	220E	4304733493	14864	Federal	GW	S
WVUFU 5W-7-8-22	WV 5W-7-8-22	SWNW	07	080S	220E	4304733494	14864	Federal	GW	P
WVUFU 11W-7-8-22	WV 11W-7-8-22	NESW	07	080S	220E	4304733495	14864	Federal	GW	P
WVUFU 13W-7-8-22	WV 13W-7-8-22	SWSW	07	080S	220E	4304733496	14864	Federal	GW	P
WVUFU 1W-7-8-22	WV 1W-7-8-22	NENE	07	080S	220E	4304733501	14864	Federal	GW	P
WVUFU 3W-7-8-22	WV 3W-7-8-22	NENW	07	080S	220E	4304733502	14864	Federal	GW	P
WV 7WRG-7-8-22	WV 7WRG-7-8-22	SWNE	07	080S	220E	4304733503	5265	Federal	OW	P
WVUFU 16W-9-8-21	WV 16W-9-8-21	SESE	09	080S	210E	4304733529	14864	Federal	GW	P
WVUFU 1W-12-8-21	WV 1W-12-8-21	NENE	12	080S	210E	4304733531	14864	Federal	GW	P
WVUFU 1W-13-8-21	WV 1W-13-8-21	NENE	13	080S	210E	4304733532	14864	Federal	GW	P
WVUFU 3W-18-8-22	WV 3W-18-8-22	NENW	18	080S	220E	4304733533	14864	Federal	GW	P
WVUFU 9W-12-8-21	WV 9W-12-8-21	NESE	12	080S	210E	4304733534	14864	Federal	GW	P
WVUFU 11W-12-8-21	WV 11W-12-8-21	NESW	12	080S	210E	4304733535	14864	Federal	GW	P
WVUFU 11W-13-8-21	WV 11W-13-8-21	NESW	13	080S	210E	4304733536	14864	Federal	GW	P
WVUFU 13W-12-8-21	WV 13W-12-8-21	SWSW	12	080S	210E	4304733537	14864	Federal	GW	S
WVUFU 13W-18-8-22	WV 13W-18-8-22	SWSW	18	080S	220E	4304733538	14864	Federal	GW	P
WVUFU 16G-9-8-21	WV 16G-9-8-21	SESE	09	080S	210E	4304733565	5265	Federal	OW	P
WVUFU 1W-21-8-21	WV 1W-21-8-21	NENE	21	080S	210E	4304733602	14864	Federal	GW	P
WVUFU 3W-13-8-21	WV 3W-13-8-21	NENW	13	080S	210E	4304733603	14864	Federal	GW	S
WVUFU 3W-22-8-21	WV 3W-22-8-21	NENW	22	080S	210E	4304733604	14864	Federal	GW	P
WVUFU 3W-24-8-21	WV 3W-24-8-21	NENW	24	080S	210E	4304733605	14864	Federal	GW	P
WVUFU 13W-13-8-21	WV 13W-13-8-21	SWSW	13	080S	210E	4304733606	14864	Federal	GW	S
WVUFU 13W-14-8-21	WV 13W-14-8-21	SWSW	14	080S	210E	4304733607	14864	Federal	GW	P

QEP Uinta Basin (N2460) to QUESTAR E and P (N5085)  
WONSITS VALLEY UNIT

4/30/2007 and 5/15/2007

Original Well Name	Well Name & N	Q/Q	SEC	TWP	RNG	API	Entity	Lease	Well Type	Status
WVFU 15W-13-8-21	WV 15W-13-8-21	SWSE	13	080S	210E	4304733608	14864	Federal	GW	S
WVFU 1W-24-8-21	WV 1W-24-8-21	NENE	24	080S	210E	4304733613	14864	Federal	GW	P
WVFU 11W-18-8-22	WV 11W-18-8-22	NESW	18	080S	220E	4304733626	14864	Federal	GW	P
WV 2W-10-8-21	WV 2W-10-8-21	NWNE	10	080S	210E	4304733655	14864	Federal	GW	P
WV 4W-11-8-21	WV 4W-11-8-21	NWNW	11	080S	210E	4304733657	14864	Federal	GW	P
WV 12W-10-8-21	WV 12W-10-8-21	NWSW	10	080S	210E	4304733659	14864	Federal	GW	S
WV 12G-10-8-21	WV 12G-10-8-21	NWSW	10	080S	210E	4304733660	5265	Federal	OW	P
WVFU 15W-9-8-21	WV 15W-9-8-21	SWSE	09	080S	210E	4304733661	14864	Federal	GW	P
WVFU 15G-9-8-21	WV 15G-9-8-21	SWSE	09	080S	210E	4304733662	5265	Federal	OW	P
WVFU 2W-13-8-21	WV 2W-13-8-21	NWNE	13	080S	210E	4304733791	14864	Federal	GW	P
WVFU 6W-13-8-21	WV 6W-13-8-21	SENW	13	080S	210E	4304733792	14864	Federal	GW	P
WVFU 8W-13-8-21	WV 8W-13-8-21	SENE	13	080S	210E	4304733793	14864	Federal	GW	P
WV 10W-1-8-21	WV 10W-1-8-21	NWSE	01	080S	210E	4304733794	14864	Federal	GW	TA
WVFU 10W-13-8-21	WV 10W-13-8-21	NWSE	13	080S	210E	4304733795	14864	Federal	GW	P
WVFU 12W-7-8-22	WV 12W-7-8-22	NWSW	07	080S	220E	4304733808	14864	Federal	GW	P
WVFU 6W-8-8-22	WV 6W-8-8-22	SENW	08	080S	220E	4304733811	14864	Federal	GW	P
WVFU 7W-8-8-22	WV 7W-8-8-22	SWNE	08	080S	220E	4304733812	14864	Federal	GW	S
WVFU 10W-7-8-22	WV 10W-7-8-22	NWSE	07	080S	220E	4304733813	14864	Federal	GW	P
WVFU 12W-8-8-22	WV 12W-8-8-22	NWSW	08	080S	220E	4304733815	14864	Federal	GW	P
WVFU 14W-7-8-22	WV 14W-7-8-22	SESW	07	080S	220E	4304733816	14864	Federal	GW	P
WVFU 16W-7-8-22	WV 16W-7-8-22	SESE	07	080S	220E	4304733817	14864	Federal	GW	P
WVFU 6W-7-8-22	WV 6W-7-8-22	SENW	07	080S	220E	4304733828	14864	Federal	GW	P
WVFU 6W-18-8-22	WV 6W-18-8-22	SENW	18	080S	220E	4304733842	14864	Federal	GW	P
WVFU 6WC-18-8-22	WV 6WC-18-8-22	SENW	18	080S	220E	4304733843	14864	Federal	GW	P
WVFU 6WD-18-8-22	WV 6WD-18-8-22	SENW	18	080S	220E	4304733844	14864	Federal	GW	P
WVFU 5W-23-8-21	WV 5W-23-8-21	SWNW	23	080S	210E	4304733860	14864	Federal	GW	P
WVFU 7W-23-8-21	WV 7W-23-8-21	SWNE	23	080S	210E	4304733861	14864	Federal	GW	P
WVFU 8W-12-8-21	WV 8W-12-8-21	SENE	12	080S	210E	4304733862	14864	Federal	GW	P
WVFU 10W-12-8-21	WV 10W-12-8-21	NWSE	12	080S	210E	4304733863	14864	Federal	GW	P
WVFU 14W-12-8-21	WV 14W-12-8-21	SESW	12	080S	210E	4304733864	14864	Federal	GW	P
WVFU 16W-12-8-21	WV 16W-12-8-21	SESE	12	080S	210E	4304733865	14864	Federal	GW	P
WVFU 1W-15-8-21	WV 1W-15-8-21	NENE	15	080S	210E	4304733902	14864	Federal	GW	S
WVFU 1W-22-8-21	WV 1W-22-8-21	NENE	22	080S	210E	4304733903	14864	Federal	GW	P
WVFU 1W-23-8-21	WV 1W-23-8-21	NENE	23	080S	210E	4304733904	14864	Federal	GW	P
WV 6W-11-8-21	WV 6W-11-8-21	SENW	11	080S	210E	4304733906	14864	Federal	GW	P
WVFU 7W-24-8-21	WV 7W-24-8-21	SWNE	24	080S	210E	4304733908	14864	Federal	GW	P
WV 10W-11-8-21	WV 10W-11-8-21	NWSE	11	080S	210E	4304733910	14864	Federal	GW	P
WVFU 11W-15-8-21	WV 11W-15-8-21	NESW	15	080S	210E	4304733911	14864	Federal	GW	P
WV 13W-11-8-21	WV 13W-11-8-21	SWSW	11	080S	210E	4304733913	14864	Federal	GW	S
WVFU 13W-15-8-21	WV 13W-15-8-21	SWSW	15	080S	210E	4304733914	14864	Federal	GW	P
WV 15W-10-8-21	WV 15W-10-8-21	SWSE	10	080S	210E	4304733916	14864	Federal	GW	P



QEP Uinta Basin (N2460) to QUESTAR E and P (N5085)  
WONSITS VALLEY UNIT

4/30/2007 and 5/15/2007

Original Well Name	Well Name & No.	Q/Q	SEC	TWP	RNG	API	Entity	Lease	Well Type	Status
WVFU 15W-15-8-21	WV 15W-15-8-21	SWSE	15	080S	210E	4304733917	14864	Federal	GW	P
WVFU 5W-14-8-21	WV 5W-14-8-21	SWNW	14	080S	210E	4304733953	14864	Federal	GW	P
WVFU 7W-14-8-21	WV 7W-14-8-21	SWNE	14	080S	210E	4304733955	14864	Federal	GW	P
WV 8W-11-8-21	WV 8W-11-8-21	SENE	11	080S	210E	4304733957	14864	Federal	GW	S
WVFU 8W-14-8-21	WV 8W-14-8-21	SENE	14	080S	210E	4304733958	14864	Federal	GW	P
WVFU 9W-15-8-21	WV 9W-15-8-21	NESE	15	080S	210E	4304733959	14864	Federal	GW	P
WVFU 12W-13-8-21	WV 12W-13-8-21	NWSW	13	080S	210E	4304733961	14864	Federal	GW	P
WVFU 14W-13-8-21	WV 14W-13-8-21	SESW	13	080S	210E	4304733962	14864	Federal	GW	P
WVFU 15W-14-8-21	WV 15W-14-8-21	SWSE	14	080S	210E	4304733963	14864	Federal	GW	P
WVFU 2W-18-8-22	WV 2W-18-8-22	NWNE	18	080S	220E	4304733986	14864	Federal	GW	P
WV 8W-18-8-22	WV 8W-18-8-22	SENE	18	080S	220E	4304733989	14864	Federal	GW	P
WVFU 10W-18-8-22	WV 10W-18-8-22	NWSE	18	080S	220E	4304733991	14864	Federal	GW	P
WVFU 12W-18-8-22	WV 12W-18-8-22	NWSW	18	080S	220E	4304733993	14864	Federal	GW	P
WV 14W-18-8-22	WV 14W-18-8-22	SESW	18	080S	220E	4304733995	14864	Federal	GW	P
WVFU 8W-1-8-21	WV 8W-1-8-21	SENE	01	080S	210E	4304734009	14864	Federal	GW	DRL
WV 4W-17-8-22	WV 4W-17-8-22	NWNW	17	080S	220E	4304734038	14864	Federal	GW	P
WV 12G-1-8-21	WV 12G-1-8-21	NWSW	01	080S	210E	4304734108	5265	Federal	OW	TA
WV 2W-14-8-21	WV 2W-14-8-21	NWNE	14	080S	210E	4304734140	14864	Federal	GW	P
GH 2W-21-8-21	GH 2W-21-8-21	NWNE	21	080S	210E	4304734141	14864	Federal	GW	P
WV 2W-23-8-21	WV 2W-23-8-21	NWNE	23	080S	210E	4304734142	14864	Federal	GW	P
GH 3W-21-8-21	WV 3W-21-8-21	NENW	21	080S	210E	4304734143	14864	Federal	GW	P
WV 4W-13-8-21	WV 4W-13-8-21	NWNW	13	080S	210E	4304734144	14864	Federal	GW	P
GH 4W-21-8-21	WV 4W-21-8-21	NWNW	21	080S	210E	4304734145	14864	Federal	GW	P
WV 4W-22-8-21	WV 4W-22-8-21	NWNW	22	080S	210E	4304734146	14864	Federal	GW	P
WV 16W-11-8-21	WV 16W-11-8-21	SESE	11	080S	210E	4304734155	14864	Federal	GW	TA
WV 3W-19-8-22	WV 3W-19-8-22	NENW	19	080S	220E	4304734187	14864	Federal	GW	P
WV 4W-23-8-21	WV 4W-23-8-21	NWNW	23	080S	210E	4304734188	14864	Federal	GW	P
WV 6W-23-8-21	WV 6W-23-8-21	SENE	23	080S	210E	4304734189	14864	Federal	GW	P
WV 2W-15-8-21	WV 2W-15-8-21	NWNE	15	080S	210E	4304734242	14864	Federal	GW	P
WV 2W-22-8-21	WV 2W-22-8-21	NWNE	22	080S	210E	4304734243	14864	Federal	GW	P
WV 4W-14-8-21	WV 4W-14-8-21	NWNW	14	080S	210E	4304734244	14864	Federal	GW	P
WV 6W-12-8-21	WV 6W-12-8-21	SENE	12	080S	210E	4304734245	5265	Federal	GW	S
WV 7W-15-8-21	WV 7W-15-8-21	SWNE	15	080S	210E	4304734246	14864	Federal	GW	P
WV 8W-15-8-21	WV 8W-15-8-21	SENE	15	080S	210E	4304734247	14864	Federal	GW	P
WV 12W-12-8-21	WV 12W-12-8-21	NWSW	12	080S	210E	4304734248	14864	Federal	GW	S
WV 14W-15-8-21	WV 14W-15-8-21	SESW	15	080S	210E	4304734249	14864	Federal	GW	P
WV 16W-10-8-21	WV 16W-10-8-21	SESE	10	080S	210E	4304734250	14864	Federal	GW	P
WV 16W-15-8-21	WV 16W-15-8-21	SESE	15	080S	210E	4304734251	14864	Federal	GW	P
WV 2W-12-8-21	WV 2W-12-8-21	NWNE	12	080S	210E	4304734265	14864	Federal	GW	OPS
WV 3W-12-8-21	WV 3W-12-8-21	NENW	12	080S	210E	4304734267	14864	Federal	GW	OPS
WV 4W-12-8-21	WV 4D-12-8-21	NWNW	12	080S	210E	4304734268	12436	Federal	GW	DRL

QEP Uinta Basin (N2460) to QUESTAR E and P (N5085)  
WONSITS VALLEY UNIT

4/30/2007 and 5/15/2007

Original Well Name	Well Name & No.	Q/Q	SEC	TWP	RNG	API	Entity	Lease	Well Type	Status
WV 5W-12-8-21	WV 5W-12-8-21	SWNW	12	080S	210E	4304734270	14864	Federal	GW	OPS
WV 6W-14-8-21	WV 6W-14-8-21	SENE	14	080S	210E	4304734271	14864	Federal	GW	P
WV 9W-11-8-21	WV 9W-11-8-21	NESE	11	080S	210E	4304734274	14864	Federal	GW	DRL
WV 10W-14-8-21	WV 10W-14-8-21	NWSE	14	080S	210E	4304734275	14864	Federal	GW	S
WV 11W-14-8-21	WV 11W-14-8-21	NESW	14	080S	210E	4304734277	14864	Federal	GW	P
WV 12W-14-8-21	WV 12W-14-8-21	NWSW	14	080S	210E	4304734279	14864	Federal	GW	S
WV 14M-11-8-21	WV 14M-11-8-21	SESW	11	080S	210E	4304734280	14864	Federal	GW	P
WV 14W-14-8-21	WV 14W-14-8-21	SESW	14	080S	210E	4304734281	14864	Federal	GW	P
WV 16W-14-8-21	WV 16G-14-8-21	SESE	14	080S	210E	4304734283	5265	Federal	OW	S
WV 3MU-15-8-21	WV 3MU-15-8-21	NENW	15	080S	210E	4304734289	14864	Federal	GW	P
WV 4MU-15-8-21	WV 4MU-15-8-21	NWNW	15	080S	210E	4304734291	14864	Federal	GW	P
WV 5MU-15-8-21	WV 5MU-15-8-21	SWNW	15	080S	210E	4304734293	14864	Federal	GW	P
WV 6W-15-8-21	WV 6W-15-8-21	SENE	15	080S	210E	4304734294	14864	Federal	GW	P
WV 10W-15-8-21	WV 10W-15-8-21	NWSE	15	080S	210E	4304734295	14864	Federal	GW	P
WVU 4W-24-8-21	WV 4W-24-8-21	NWNW	24	080S	210E	4304734330	14864	Federal	GW	P
WV 8M-23-8-21	WV 8M-23-8-21	SENE	23	080S	210E	4304734339	14864	Federal	GW	P
WVU 8W-24-8-21	WV 8W-24-8-21	SENE	24	080S	210E	4304734340	14864	Federal	GW	P
WV 2W-8-8-22	WV 2W-8-8-22	NWNE	08	080S	220E	4304734468	14864	Federal	GW	P
WV 8W-7-8-22	WV 8W-7-8-22	SENE	07	080S	220E	4304734469	14864	Federal	GW	S
WV 8W-22-8-21	WV 8W-22-8-21	SENE	22	080S	210E	4304734564	14864	Federal	GW	P
WV 3G-8-8-22	WV 3G-8-8-22	NENW	08	080S	220E	4304734596	5265	Federal	OW	TA
WV 14MU-10-8-21	WV 14MU-10-8-21	SESW	10	080S	210E	4304735879	14864	Federal	GW	P
WV 13MU-10-8-21	WV 13MU-10-8-21	SWSW	10	080S	210E	4304736305	14864	Federal	GW	P
WV 3DML-13-8-21	WV 3D-13-8-21	SENE	13	080S	210E	4304737923	14864	Federal	GW	DRL
WV 14DML-12-8-21	WV 14DML-12-8-21	SESW	12	080S	210E	4304737924	14864	Federal	GW	DRL
WV 15AML-12-8-21	WV 15AML-12-8-21	NWSE	12	080S	210E	4304737925		Federal	GW	APD
WV 13DML-10-8-21	WV 13DML-10-8-21	SWSW	10	080S	210E	4304737926	14864	Federal	GW	P
WV 4DML-15-8-21	WV 4DML-15-8-21	NWNW	15	080S	210E	4304737927	14864	Federal	GW	DRL
WV 13AD-8-8-22	WV 13AD-8-8-22	SWSW	08	080S	220E	4304737945		Federal	GW	APD
WV 11AML-14-8-21	WV 11AD-14-8-21	NWSE	14	080S	210E	4304738049	15899	Federal	GW	APD
WV 11DML-14-8-21	WV 11DML-14-8-21	SESW	14	080S	210E	4304738050		Federal	GW	APD
WV 4AML-19-8-22	WV 4AML-19-8-22	NWNW	19	080S	220E	4304738051		Federal	GW	APD
WV 13CML-8-8-22	WV 13CML-8-8-22	SWSW	08	080S	220E	4304738431		Federal	GW	APD
WV 13BML-18-8-22	WV 13BML-18-8-22	SWSW	18	080S	220E	4304738432		Federal	GW	APD
WV 8BML-18-8-22	WV 8BML-18-8-22	E/NE	18	080S	220E	4304738433		Federal	GW	APD
WV 6ML-24-8-21	WV 6-24-8-21	SENE	24	080S	210E	4304738663		Federal	GW	APD
WV 2ML-24-8-21	WV 2ML-24-8-21	NWNE	24	080S	210E	4304738664		Federal	GW	APD
WV 1DML-13-8-21	WV 1DML-13-8-21	NENE	13	080S	210E	4304738733		Federal	GW	APD
WV 4DML-13-8-21	WV 4DML-13-8-21	NWNW	13	080S	210E	4304738734		Federal	GW	APD
WV 3AML-14-8-21	WV 3AML-14-8-21	NENW	14	080S	210E	4304738736		Federal	GW	APD
WV 16CML-14-8-21	WV 16C-14-8-21	SESE	14	080S	210E	4304738737		Federal	GW	APD

QEP Uinta Basin (N2460) to QUESTAR E and P (N5085)  
WONSITS VALLEY UNIT

4/30/2007 and 5/15/2007

Original Well Name	Well Name & No.	Q/Q	SEC	TWP	RNG	API	Entity	Lease	Well Type	Status
WVU 21	WV 21	NENE	16	080S	210E	4304715452	99990	State	WI	A
WVU 32	WV 32	NENW	16	080S	210E	4304716513	5265	State	OW	P
WVU 72	WV 72	SWSW	16	080S	210E	4304720058	99990	State	WI	A
WVU 73	WV 73	NESE	16	080S	210E	4304720066	5265	State	WI	A
WVU 74	WV 74	SWSE	16	080S	210E	4304720078	5265	State	OW	P
WVU 75	WV 75	SWNE	16	080S	210E	4304720085	5265	State	OW	P
WVU 78	WV 78	NESW	16	080S	210E	4304720115	99990	State	WI	A
WVU 134	WV 134	SESE	16	080S	210E	4304731118	5265	State	OW	P
WVU 141	WV 141	NWSE	16	080S	210E	4304731609	5265	State	OW	P
WVU 127	WV 127	SENE	16	080S	210E	4304731611	5265	State	OW	P
WVU 142	WV 142	SESW	16	080S	210E	4304731612	5265	State	OW	P
WVUFU 9W-13-8-21	WV 9W-13-8-21	NESE	13	080S	210E	4304733223	14864	State	GW	S
WVUFU 2W-16-8-21	WV 2W-16-8-21	NWNE	16	080S	210E	4304733246	14864	State	GW	P
WVUFU 2G-16-8-21	WV 2G-16-8-21	NWNE	16	080S	210E	4304733247	5265	State	OW	P
WVUFU 6W-16-8-21	WV 6W-16-8-21	SENW	16	080S	210E	4304733527	14864	State	GW	P
WVUFU 6G-16-8-21	WV 6G-16-8-21	SENW	16	080S	210E	4304733564	5265	State	OW	P
WVUFU 16W-2-8-21	WV 16W-2-8-21	SESE	02	080S	210E	4304733645	5265	State	OW	S
WVUFU 9W-2-8-21	WV 9W-2-8-21	NESE	02	080S	210E	4304733648	14864	State	GW	P
WVUFU 12W-16-8-21	WV 12W-16-8-21	NWSW	16	080S	210E	4304733649	14864	State	GW	P
WVUFU 12G-16-8-21	WV 12G-16-8-21	NWSW	16	080S	210E	4304733650	5265	State	OW	P
WVUFU 16W-13-8-21	WV 16W-13-8-21	SESE	13	080S	210E	4304733796	14864	State	GW	P
WV 10G-2-8-21	WV 10G-2-8-21	NWSE	02	080S	210E	4304734035	5265	State	OW	P
WV 14G-2-8-21	WV 14G-2-8-21	SESW	02	080S	210E	4304734036	5265	State	OW	P
WV 13G-2-8-21	WV 13G-2-8-21	SWSW	02	080S	210E	4304734068	5265	State	OW	P
WV 5G-16-8-21	WV 5G-16-8-21	SWNW	16	080S	210E	4304734107	5265	State	OW	P
WV 11W-16-8-21	WV 11W-16-8-21	NESW	16	080S	210E	4304734190	14864	State	GW	P
WV 13W-16-8-21	WV 13W-16-8-21	SWSW	16	080S	210E	4304734191	14864	State	GW	P
WV 14W-16-8-21	WV 14W-16-8-21	SESW	16	080S	210E	4304734192	14864	State	GW	P
WV 15W-16-8-21	WV 15W-16-8-21	SWSE	16	080S	210E	4304734224	14864	State	GW	P
WV 16W-16-8-21	WV 16W-16-8-21	SESE	16	080S	210E	4304734225	14864	State	GW	P
WV 1MU-16-8-21	WV 1MU-16-8-21	NENE	16	080S	210E	4304734288	14864	State	GW	P
WV 3W-16-8-21	WV 3W-16-8-21	NENW	16	080S	210E	4304734290		State	GW	LA
WV 4W-16-8-21	WV 4W-16-8-21	NWNW	16	080S	210E	4304734292	12436	State	D	PA
WVU 5W-16-8-21	WV 5W-16-8-21	SWNW	16	080S	210E	4304734321	14864	State	GW	P
WV 7W-16-8-21	WV 7W-16-8-21	SWNE	16	080S	210E	4304734322	14864	State	GW	P
WV 8ML-16-8-21	WV 8ML-16-8-21	SENE	16	080S	210E	4304734323	14864	State	GW	P
WV 9W-16-8-21	WV 9W-16-8-21	NESE	16	080S	210E	4304734325	14864	State	GW	P
WV 10W-16-8-21	WV 10W-16-8-21	NWSE	16	080S	210E	4304734326	14864	State	GW	P
WV 12BML-16-8-21	WV 12BML-16-8-21	SWNW	16	080S	210E	4304737824	14864	State	GW	P
WV 12DML-16-8-21	WV 12D-16-8-21	NWSW	16	080S	210E	4304737870		State	GW	APD
WV 15CML-16-8-21	WV 15CML-16-8-21	SESW	16	080S	210E	4304737871	14864	State	GW	P

QEP Uinta Basin (N2460) to QUESTAR E and P (N5085)  
WONSITS VALLEY UNIT

4/30/2007 and 5/15/2007

Original Well Name	Well Name & No.	Q/Q	SEC	TWP	RNG	API	Entity	Lease	Well Type	Status
WV 15DML-16-8-21	WV 15DML-16-8-21	SWSE	16	080S	210E	4304737872		State	GW	APD
WV 16DML-13-8-21	WV 16DML-13-8-21	SESE	13	080S	210E	4304738735		State	GW	APD



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: see attached
2. NAME OF OPERATOR: QUESTAR EXPLORATION AND PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: see attached
3. ADDRESS OF OPERATOR: 1050 17th Street Suite 500 CITY Denver STATE CO ZIP 80265		7. UNIT or CA AGREEMENT NAME: see attached
PHONE NUMBER: (303) 308-3068		8. WELL NAME and NUMBER: see attached
4. LOCATION OF WELL FOOTAGES AT SURFACE: attached		9. API NUMBER: attached
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		10. FIELD AND POOL, OR WILDCAT:

COUNTY: Uintah

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 1/1/2007	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Operator Name Change
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective January 1, 2007 operator of record, QEP Uinta Basin, Inc., will hereafter be known as QUESTAR EXPLORATION AND PRODUCTION COMPANY. This name change involves only an internal corporate name change and no third party change of operator is involved. The same employees will continue to be responsible for operations of the properties described on the attached list. All operations will continue to be covered by bond numbers:

Federal Bond Number: 965002976 (BLM Reference No. ESB000024)

Utah State Bond Number: 965003033


Fee Land Bond Number: 965003033

Current operator of record, QEP UINTA BASIN, INC., hereby resigns as operator of the properties as described on the attached list.

Jay B. Neese, Executive Vice President, QEP Uinta Basin, Inc.

Successor operator of record, QUESTAR EXPLORATION AND PRODUCTION COMPANY, hereby assumes all rights, duties and obligations as operator of the properties as described on the attached list

Jay B. Neese, Executive Vice President  
Questar Exploration and Production Company

NAME (PLEASE PRINT) Debra K. Stanberry	TITLE Supervisor, Regulatory Affairs
SIGNATURE 	DATE 3/16/2007

(This space for State use only)

RECEIVED

APR 19 2007

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL ☐ GAS WELL ☐ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:

QUESTAR EXPLORATION AND PRODUCTION COMPANY

3. ADDRESS OF OPERATOR:

1050 17th Street Suite 500 City: Denver

STATE: CO ZIP: 80265

PHONE NUMBER:

(303) 308-3068

4. LOCATION OF WELL:

FOOTAGES AT SURFACE: attached

COUNTY: Uintah

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE:

UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:  
see attached

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:  
see attached

7. UNIT or CA AGREEMENT NAME:  
see attached

8. WELL NAME and NUMBER:  
see attached

9. API NUMBER:  
attached

10. FIELD AND POOL, OR WILDCAT:

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ NOTICE OF INTENT  
(Submit in Duplicate)

Approximate date work will start:

1/1/2007

☐ SUBSEQUENT REPORT  
(Submit Original Form Only)

Date of work completion:

TYPE OF ACTION

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☐ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☒ OTHER: Well Name Changes

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

PER THE ATTACHED LIST OF WELLS, QUESTAR EXPLORATION AND PRODUCTION COMPANY REQUESTS THAT THE INDIVIDUAL WELL NAMES BE UPDATED IN YOUR RECORDS.

NAME (PLEASE PRINT) Debra K. Stanberry

TITLE Supervisor, Regulatory Affairs

SIGNATURE

DATE 4/17/2007

(This space for State use only)

RECEIVED

APR 19 2007

DIV. OF OIL, GAS & MINING



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, UT 84145-0155



IN REPLY REFER TO  
3180  
UT-922

April 23, 2007

Questar Exploration and Production Company  
1050 17th Street, Suite 500  
Denver, Colorado 80265

Re: Wonsits Valley Unit  
Uintah County, Utah

Gentlemen:

On April 12, 2007, we received an indenture dated April 6, 2007, whereby QEP Uinta Basin, Inc. resigned as Unit Operator and Questar Exploration and Production Company was designated as Successor Unit Operator for the Wonsits Valley Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective April 23, 2007. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the Wonsits Valley Unit Agreement.

Your nationwide oil and gas bond No. ESB000024 will be used to cover all federal operations within the Wonsits Valley Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Greg J. Noble

Greg J. Noble  
Acting Chief, Branch of Fluid Minerals

Enclosure

bcc: Field Manager - Vernal (w/enclosure)  
SITLA  
Division of Oil, Gas & Mining  
File - Wonsits Valley Unit (w/enclosure)  
Agr. Sec. Chron  
Reading File  
Central Files

UT922:TAThompson:tt:4/23/07

RECEIVED  
APR 30 2007  
DIV. OF OIL, GAS & MINING

**CONFIDENTIAL**

**CONFIDENTIAL**

Form 3160-5  
(November 1994)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**SUNDRY NOTICES AND REPORTS ON WELLS**

**Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.**

FORM APPROVED  
OMB No. 1004-0135  
Expires July 31, 1996

5. Lease Serial No.

**UTU-0806**

6. If Indian, Allottee or Tribe Name

**UTE TRIBE**

7. If Unit or CA/Agreement, Name and/or No.

**WONSITS VALLEY**

8. Well Name and No.

**WV 4W-12-8-21**

9. API Well No.

**43-047-34268**

10. Field and Pool, or Exploratory Area

**WONSITS VALLEY**

11. County or Parish, State

**Uintah**

**SUBMIT IN TRIPLICATE - Other Instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

**QEP Uinta Basin, Inc.**

**Contact: Jan Nelson**

3a. Address

**1571 East 1700 South, Vernal, UT 84078**

3b. Phone No. (include area code)

**435-781-4032**

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

**356' FNL 475' FWL, NWNW, SECTION 12, T8S, R21E**

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once Testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

**QEP Uinta Basin, Inc set Conductor on 9/16/03. This location is on Questar's future drilling schedule.**

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

**Laura Bills**

Title

**Regulatory Assistant**

Signature



Date

**February 6, 2007**

**THIS SPACE FOR FEDERAL OR STATE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**RECEIVED**

(Instructions on reverse)

**FEB 09 2007**

DIV. OF OIL, GAS & MINING



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**CONFIDENTIAL**

FORM APPROVED  
OMB No. 1004-0137  
Expires: March 31, 2007

**SUNDRY NOTICES AND REPORTS ON WELLS**

*Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.*

**SUBMIT IN TRIPLICATE- Other instructions on reverse side.**

1. Type of Well  
☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator **Questar Exploration and Production Inc.**

3a. Address  
**1050 17th Street, Suite 500 Denver, CO 80265**

3b. Phone No. (include area code)  
**303 308-3068**

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
**2167' FNL, 586' FWL, SWNW, Sec 12-T8S-R21E**

5. Lease Serial No.  
**UTU 0806**

6. If Indian, Allottee or Tribe Name  
**Ute Tribe**

7. If Unit or CA/Agreement, Name and/or No.  
**Wonsits Valley**

8. Well Name and No.  
**WV 4D 12 8 21**

9. API Well No.  
**43-047-34268**

10. Field and Pool, or Exploratory Area  
**Wonsits Valley**

11. County or Parish, State  
**Uintah County, Utah**

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>well status</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleation in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Questar Exploration and Production Company's (QEP) records show that this well was spud on 9/26/03 and has set 40' of 20" conductor. QEP plans to drill this well in 2008 and QEP is currently evaluating the feasibility of drilling the surface casing with a small rig then coming in with a large drilling rig to drill the rest of the well bore. Based on current data and geologic evaluation, this well will be drilled to a deeper depth and drilling operations to total depth will require a larger drilling rig. This well site has recently be on-sited with the Tribe and paperwork requesting your approval will be submitted to your office in the near future providing details of QEP's revised drilling plans for this well.

This sundry is being submitted per the August 23, 2007 written order of the authorized officer received from your office by QEP on August 27, 2007 requesting a time line be provided for when this well will be drilled and completed.

14. I hereby certify that the foregoing is true and correct  
Name (Printed/Typed)

**Debra K. Stanberry**

Title **Supervisor, Regulatory Affairs**

Signature

Date

**10/16/2007**

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

**RECEIVED**

**OCT 25 2007**

**DIV. OF OIL, GAS & MINING**

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**SUNDRY NOTICES AND REPORTS ON WELLS**

**Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.**

FORM APPROVED  
OMB No. 1004-0135  
Expires July 31, 1996

5. Lease Serial No.

**UTU-0806**

6. If Indian, Allottee or Tribe Name

**UTE INDIAN TRIBE**

7. If Unit or CA/Agreement, Name and/or No.

**WONSITS VALLEY**

8. Well Name and No.

**WV 4W-12-8-21**

9. API Well No.

**43-047-34268**

10. Field and Pool, or Exploratory Area

**WONSITS VALLEY**

11. County or Parish, State

**UINTAH**

**SUBMIT IN TRIPLICATE - Other Instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

**QUESTAR EXPLORATION & PRODUCTION, CO.**

3a. Address

**11002 E. 17500 S. VERNAL, UT 84078**

3b. Phone No. (include area code)

**435-781-4331**

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

**356' FNL 475' FWL, NWNW, SEC. 12, T8S, R21E**

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input checked="" type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	<b>NAME CHANGE</b>
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once Testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

QUESTAR EXPLORATION AND PRODUCTION COMPANY (QEP) REQUEST PERMISSION TO CHANGE THE DRILLING PLANS FOR THIS WELL AND TO USE OIL BASE MUD FOR THE DRILLING OF THE FINAL SECTION OF THIS WELL TO IMPROVE DRILLING EFFICIENCY, WELLBORE STABILITY AND TO PROMOTE A GOOD CEMENT JOB OF THE PRODUCTION CASING. ATTACHED IS A DRILLING PLAN, WELLBORE DIAGRAM, DRILLING FLUID PROPOSAL AND A PROPOSAL FOR PROCESSING AND DISPOSAL OF THE OIL BASE MUD.

QUESTAR EXPLORATION AND PRODUCTION COMPANY (QEP) IS REQUESTING TO CHANGE THE WELL NAME FROM WV 4W-12-8-21 TO WV 4D-12-8-21.

QUESTAR EXPLORATION & PRODUCTION COMPANY (QEP) WILL PROVIDE THE PROPER PAPER WORK TO THE BUREAU OF INDIAN AFFAIRS AND UTE TRIBE.

FOR TECHNICAL QUESTIONS, PLEASE CONTACT JIM  
(303) 308-3090.

GINEER FOR QEP, AT

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

**Jan Nelson**

Signature

**November 6, 2007**

**NOV 08 2007**

**THIS SPACE FOR FEDERAL OR STATE USE**

Approved by

Title

**Accepted by the  
Utah Division of  
Oil, Gas and Mining**

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

**FOR RECORD ONLY**

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**SUNDRY NOTICES AND REPORTS ON WELLS**

**Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.**

FORM APPROVED  
OMB No. 1004-0135  
Expires July 31, 1996

5. Lease Serial No.

UTU-0806

6. If Indian, Allottee or Tribe Name

UTE INDIAN TRIBE

7. If Unit or C/A Agreement, Name and/or No.

WONSITS VALLEY

8. Well Name and No.

WV 4W-12-8-21

9. API Well No.

43-047-34268

10. Field and Pool, or Exploratory Area

WONSITS VALLEY

11. County or Parish, State

UINTAH

**SUBMIT IN TRIPLICATE - Other Instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

QUESTAR EXPLORATION & PRODUCTION, CO.

3a. Address

11002 E. 17500 S. VERNAL, UT 84078

3b. Phone No. (include area code)

435-781-4331

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

356' FNL 475' FWL, NWNW, SEC. 12, T8S, R21E

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input checked="" type="checkbox"/> Other <u>NAME CHANGE</u>
	<input checked="" type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandon <input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input type="checkbox"/> Water Disposal

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomple horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once Testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

QUESTAR EXPLORATION AND PRODUCTION COMPANY (QEP) REQUEST PERMISSION TO CHANGE THE DRILLING PLANS FOR THIS WELL AND TO USE OIL BASE MUD FOR THE DRILLING OF THE FINAL SECTION OF THIS WELL TO IMPROVE DRILLING EFFICIENCY, WELLBORE STABILITY AND TO PROMOTE A GOOD CEMENT JOB OF THE PRODUCTION CASING. ATTACHED IS A DRILLING PLAN, WELLBORE DIAGRAM, DRILLING FLUID PROPOSAL AND A PROPOSAL FOR PROCESSING AND DISPOSAL OF THE OIL BASE MUD.

QUESTAR EXPLORATION AND PRODUCTION COMPANY (QEP) IS REQUESTING TO CHANGE THE WELL NAME FROM WV 4W-12-8-21 TO WV 4D-12-8-21.

QUESTAR EXPLORATION & PRODUCTION COMPANY (QEP) WILL PROVIDE THE PROPER PAPER WORK TO THE BUREAU OF INDIAN AFFAIRS AND UTE TRIBE.

FOR TECHNICAL QUESTIONS, PLEASE CONTACT JIM DAVIDSON, CHIEF DRILLING ENGINEER FOR QEP, AT (303) 308-3090.

14. I hereby certify that the foregoing is true and correct

RECEIVED

Name (Printed/Typed)

Jan Nelson

Signature

Title

Regulatory Affairs

Date

November 6, 2007

NOV 08 2007

DIV. OF OIL, GAS & MINING

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Accepted by the  
Utah Division of  
Oil, Gas and Mining

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

FOR RECORD ONLY

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

CONFIDENTIAL

DRILLING PROGRAM

ONSHORE OIL & GAS ORDER NO. 1  
Approval of Operations on Onshore  
Federal Oil and Gas Leases

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas No. 1, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

**1. Formation Tops**

The estimated tops of important geologic markers are as follows:

<u>Formation</u>	<u>Depth</u>
Uinta	Surface
Green River	3,025'
Wasatch	6,425'
Mesaverde	9,325'
Sego	11,775'
Castlegate	11,925'
Blackhawk	12,253'
Mancos Shale	12,709'
Mancos B	13,133'
Frontier	15,839'
Dakota Silt	16,731'
Dakota	16,933'
TD	17,500'

**2. Anticipated Depths of Oil Gas Water and Other Mineral Bearing Zones**

The estimated depths at which the top and bottom of the anticipated water, oil, gas. Or other mineral bearing formations are expected to be encountered are as follows:

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
Gas	Wasatch	6,425'
Gas	Mesaverde	9,325'
Gas	Blackhawk	12,253'
Gas	Mancos Shale	12,709'
Gas	Mancos B	13,133'
Gas	Dakota	16,933'

All fresh water and prospectively valuable minerals encountered during drilling will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

DRILLING PROGRAM

All water shows and water-bearing sands will be reported to the BLM in Vernal, Utah. Copies of State of Utah form OGC-8-X are acceptable. If flows are detected, samples will be submitted to the BLM along with any water analyses conducted. Fresh water will be obtained from Wonsits Valley water right # A36125 (which was filed on May 7, 1964,) or Red Wash water right # 49-2153 (which was filed on March 25, 1960). It was determined by the Fish and Wildlife Service that any water right number filed before 1989 is not depleting to the Upper Colorado River System, to supply fresh water for drilling purposes. All water resulting from drilling operations will be disposed of at Red Wash Central Battery Disposal Site; SWSE, Section 27, T7S, R23E or Wonsits Valley Disposal Site; SWNW, Section 12, T8S, R21E.

**3. Operator's Specification for Pressure Control Equipment:**

- A. 13-5/8" 5000 psi double gate, 5,000 psi annular BOP (schematic included) from surface hole to 9-5/8" casing point. A 13-5/8" 10,000 psi double and single gate may be substituted based on contractor availability and substructure height of the drilling rig.
- B. 11" or 13-5/8" 10,000 psi double gate, 10,000 psi single gate, 10,000 psi annular BOP (schematic included) from 9-5/8" casing point to total depth. The choice of BOP stacks is based on the drilling contractor's availability.
- C. Functional test daily
- D. All casing strings shall be pressure tested (0.2 psi/foot or 1500 psi, whichever is greater) prior to drilling the plug after cementing; test pressure shall not exceed the internal yield pressure of the casing.
- E. Ram type preventers and associated equipment shall be tested to approved stack working pressure if isolated by test plug or to 50 percent of internal yield pressure of casing whichever is less. BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc..., for a 10M system and individual components shall be operable as designed.



## DRILLING PROGRAM

### 4. Casing Design:

Hole Size	Csg. Size	Top (MD)	Bottom (MD)	Wt.	Grade	Thread	Cond.
26"	20"	sfc	40-60'	Steel	Cond.	None	Used
17-1/2"	13-3/8	sfc	500'	54.5	K-55	STC	New
11"	9-5/8"	sfc	6300'	47	HCP-110	Flush Jnt **	New
8-1/2"	7"	8000'	12,750'	29* SDrift	HCP-110	LTC	New
6-1/8"	4-1/2"	sfc	13,700'	15.1	P-110	LTC	New
6-1/8"	4-1/2"	13,700'	17,500'	15.1	Q-125	LTC	New

Casing Strengths:				Collapse	Burst	Tensile (minimum)
13-3/8"	54.5 lb.	K-55	STC	1,130 psi	2,730 psi	547,000 lb.
9-5/8"	47 lb.	HCP-110	LTC	7,100 psi	9,440 psi	1,213,000 lb.
7"	29 lb.*	HCP-110	LTC	9,200 psi	11,220 psi	797,000 lb.
4-1/2"	15.1 lb.	P-110	LTC	14,350 psi	14,420 psi	406,000 lb.
4-1/2"	15.1 lb.	Q-125	LTC	15,840 psi	16,380 psi	438,000 lb.

\* Special Drift

\*\* Flush Jnt – VAM SLIJ II

### MINIMUM DESIGN FACTORS:

COLLAPSE: 1.125

BURST: 1.10

TENSION: 1.80

Area Fracture Gradient: 0.9 psi/foot

Maximum anticipated mud weight: 15.4 ppg

Maximum surface treating pressure: 12,500 psi

DRILLING PROGRAM

**5. Auxiliary Equipment**

- A. Kelly Cock – yes
- B. Float at the bit – yes
- C. Monitoring equipment on the mud system – visually and/or PVT/Flow Show
- D. Full opening safety valve on the rig floor – yes
- E. Rotating Head – yes  
If drilling with air the following will be used:
  - 1. The blooie line shall be at least 6” in diameter and extend at least 100’ from the well bore into the reserve/blooie pit.
  - 2. Blooie line ignition shall be provided by a continuous pilot (ignited when drilling below 500’).
  - 3. Compressor shall be tied directly to the blooie line through a manifold.
  - 4. A mister with a continuous stream of water shall be installed near the end of the blooie lines for dust suppression.

Surface hole will be drilled with air, air/mist, foam, or mud depending on hole conditions. Drilling below surface casing will be with water based drilling fluids consisting primarily of fresh water, bentonite, lignite, caustic, lime, soda ash and polymers. No chromates will be used. Oil based mud will be used to drill the final section of the hole. The water based and oil based drilling system specifics are attached to this APD. Maximum anticipated mud weight is 15.4 ppg.

No minimum quantity of weight material will be required to be kept on location.

PVT/Flow Show will be used from base of surface casing to TD.

Gas detector will be used from surface casing depth to TD.

**6. Testing, logging and coring program**

- A. Cores – none anticipated
- B. DST – none anticipated
- C. Logging – Mud logging – 4500’ to TD  
GR-SP-Induction, Neutron Density, FMI

## DRILLING PROGRAM

- D. Formation and Completion Interval: Mancos interval, final determination of completion will be made by analysis of logs.  
Stimulation – Stimulation will be designed for the particular area of interest as encountered.

### 7. **Cementing Program**

#### **20" Conductor:**

Cement to surface with construction cement.

#### **13-3/8" Surface Casing: sfc – 500' (MD)**

**Slurry:** 0' – 500'. 610 sks (731 cu ft) Premium cement + 0.25 lbs/sk Flocele + 2% CaCl<sub>2</sub>  
Slurry wt: 15.6 ppg, slurry yield: 1.20 ft<sup>3</sup>/sk, slurry volume: 17-1/2" hole + 100% excess.

#### **9-5/8" Intermediate Casing: sfc – 6,300' (MD)**

**Lead Slurry:** 0' – 5,900'. 894 sks (1315 cu. ft) Foamed Lead 50/50 Poz cement + 0.1 % FDP-C766-05 (Low Fluid Loss Control) + 5 #/sx Silicate Compacted + 20 % SSA-1 + 0.1 % Versaset + 1.5 % Zonesealant 2000 (Foamer) Slurry wt: 14.3 ppg, (unfoamed) or 11.0 ppg. (foamed) Slurry yield: 1.47 ft<sup>3</sup>/sk (unfoamed), Slurry volume: 11" hole + 35 % excess.

**Tail Slurry:** 5,900' – 6,300'. 57 sks (15 bbls) Tail 50/50 Poz cement + 0.1 % FDP-C766-05 (Low Fluid Loss Control) + 5 #/sx Silicate Compacted + 20 % SSA-1 + 0.1 % Versaset Slurry wt: 14.3 ppg, Slurry yield: 1.47 ft<sup>3</sup>/sk, Slurry volume: 11" hole + 35% excess.

#### **7" Intermediate Casing: 5,800 - 12,750' (MD)**

**Foamed Lead Slurry 2:** 5,800' – 12,750'. 693 sks (1102 cu ft) 50/50 Poz Premium + 20% SSA-1 + 3 % silicalite compacted + 3% Silicalite Compacted + 0.5% Halad 344 + 0.2% Halad 413 + 0.1% HR-12 + 0.7% Super CBL + 0.2% Suspend Slurry wt: 14.0 ppg,, Slurry yield: 1.59 ft<sup>3</sup>/sk, Slurry volume: 8-1/2" hole + 25% excess.

#### **4-1/2" Production Casing: sfc – 17,500' (MD)**

**Lead/Tail Slurry:** 6,500 - 17,500'. 939 sks (1399 cu ft) Premium Cement + 17.5% SSA-1, + 4% Microbond HT, + 0.2% Halad 344 + 0.5% Halad 413, + 0.3% CFR-3, + 0.9% HR-12, + 0.2% Super CBL, + 0.2% Suspend HT, 17.5% SSA-2. Slurry wt: 16.2 ppg, Slurry yield: 1.49 ft<sup>3</sup>/sk, Slurry volume: 6-1/8" hole + 35% in open hole section.

\*Final cement volumes to be calculated from caliper log with an attempt to be made to circulate cement to the surface on the intermediate string and 6,500' on the production string. A bond log will be run across the zone of interest and across zones as required by the authorized officer to insure protection of natural resources.

DRILLING PROGRAM

**8. Anticipated Abnormal Pressures and Temperatures, Other Potential Hazards**

No abnormal temperatures or pressures are anticipated. No H<sub>2</sub>S has been encountered in or known to exist from previous wells drilled to similar depths in the general area. Maximum anticipated bottom hole pressure equals approximately 12,300 psi. Maximum anticipated bottom hole temperature is 315° F.

**9. ADDITIONAL INFORMATION FOR OIL BASE MUD:**

- A. See attached diagram of well pad layout. A reserve pit will be constructed for this location. This pit will be constructed so that a minimum of two vertical feet of freeboard exists above the top of the pit at all times and at least one-half of the holding capacity will be below ground level. The pit will be lined with a synthetic reinforced liner, 30 millimeters thick, with sufficient bedding used to cover any rocks prior to putting any fluids into the pit. The pad will be designed so that runoff from adjacent slopes does not flow into the reserve pit. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. At the beginning of drilling operations this reserve pit will have an open-ended dike placed in the pit that allows the fluids to migrate from one side of the pit to the other during the drilling of the surface and intermediate hole using water based mud. At the time that operations begin to drill the production hole with oil base mud, this dike will be extended, dividing the pit into two distinct, isolated halves allowing no migration of fluids from one side to the other. At that time all fluids will be removed from the end of the pit to be used as a cuttings pit. This cuttings pit will be used for oil based cuttings generated during drilling of the production hole.
- B. Oil-base mud will be mixed in the closed circulating system and transferred to four 500-bbl tanks on location for storage prior to and after drilling operations. Drip pans will be installed below the rotary beams on the substructure and can be viewed on site from the cellar area. As the production section of the hole is drilled, the cuttings transported to the surface with the drilling fluid will be mechanically separated from the drilling fluid as waste by two shale-shakers and then cleaned/dried via a mud cleaner and/or centrifuge. These separated cuttings will be collected in a steel catch tank once they leave the closed circulating system and transported and placed into the cuttings half of the reserve pit.


DRILLING PROGRAM

- C. Plastic material will underlay the rig, oil base mud/diesel storage tanks and mud pits. All tanks on location will be placed inside of berms. Any oily waste fluids and sediments generated at the work site during drilling operations or when cleaning the fluid containment system after drilling will also be placed into the cuttings half of the pit.
- D. All rig ditches will be lined and directed to a lined sump for fluid recovery. A drip pan will be installed on the BOP stack, a mud bucket will be utilized as needed on connections and a vacuum system will be used on the rig floor for fluid recovery in those areas.
- E. Once all waste has been placed in the cuttings portion of the pit and all necessary approvals obtained, the oilfield waste management consultant Soli-Bond or a similar company will mobilize equipment and personnel to the site to perform the cement based solidification/stabilization process in-situ for encapsulation. Soil will be backfilled over the processed material used on the cuttings side of the pit and that portion of the pit area will be returned to the existing grade bordering the pit. Please see the attached Soli-Bond Proposal for Processing and Disposal of Drilling Waste for specific details. The half of the reserve pit containing water base materials will be left to evaporate and will be closed and reclaimed at the time that portion of the pit is dry.




## DRILLING PROGRAM

**BOP Requirements:**




# Attachment I Diagrams of Choke Manifold Equipment



1-4 10M and 15M Choke Manifold Equipment -- Configuration of chokes may vary


[34 FR 39528, Sept. 27, 1969]

Revised as March 25, 1992 by John D. Corbett



② SM CHOKER MANIFOLD EQUIPMENT — CONFIGURATION OF CHOKES MAY VARY

## WV 4D-12-8-21





**Questar  
Exploration &  
Production Company**

***WV 4D-12-8-21***

***Sec 12-T8S-R21E  
Uintah County, Utah***

***Drilling Fluids Program***

***410 17<sup>th</sup> Street, Suite 460 Denver, CO 80202  
(303) 623-2205 (720) 904-7970 Fax***





## Newpark Drilling Fluids, LP

410 17<sup>th</sup> Street, Suite 460

■ Denver, Colorado 80202

■ (303) 623-2205

■ FAX (720) 904-7970

November 2, 2007

Mr. Jim Davidson  
Chief Drilling Engineer  
Questar Exploration & Production  
1331 17th Street, Suite 800  
Denver, Colorado 80202

RE: WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah Co, Utah

Mr. Davidson:

Newpark Drilling Fluids, LP is pleased to present the enclosed revised recommended drilling fluids program for the WV 4D-12-8-21 well to be drilled in Uintah County, Utah. This program is for drilling with Air/Water in the 1st intermediate T.D. at 6300 ft, then to +/- 8000 ft depending on hole conditions.

The Surface Interval will be drilled with air to a depth of 500 ft.

For the Intermediate Interval, an Air/Mist drilling program is recommended. Offset wells in the area have drilled with air to a depth of 1500-1700 ft +/- or until water intrusions were noted. After changing to Air/Water, due to hole stability problems on offset wells, it is recommended to add KCL to the water for 3% KCL and maintain a Potassium Silicate concentration in the water for 0.25-0.50 % Silicate. (Approximately 3 sks per 100 ft drilled).

Brine kill pills may be needed for trips, logs, and casing operations, depending on pressure encountered while drilling. Trona water flows in this area may require a mud weight of 9.5 ppg to control. Mud weight at interval T.D. at 6,300' is expected to be in the 8.8-9.0 ppg range.

In the Liner interval, drill out with the Air/Water from the previous interval, continuing additions of KCL, and maintaining 3% through the Wasatch. At 7,500' - 8,000' depending upon hole conditions, begin a mud-up for a KCL/Polymer mud system for properties as outlined in the following program. After drilling into the Mesa Verde, allow the KCL to deplete through dilution allowing the system to convert to a NewPPHA/Polymer system. Mud weight in this interval is expected to be in the 11.2-11.4 ppg range at the 13,000 ft liner interval T.D.

In the Production interval, displace to a 12.0-12.5 ppg OptiDrill OBM system. Maintain fluid density as low as possible to increase penetration rates and reduce the possibility of lost circulation. Use high weight pills for well control during trips, logs, and casing operations. Mud weight at T.D. is expected to be at +/-15.5 ppg.

The projected drilling time for this project is 65-70 days with an estimated material and engineering cost of \$500,000.00 assuming no unusual delays or problems are encountered. The estimate is based on minimal losses and a 15.0 ppg mud weight at TD. Costs will increase dramatically if severe losses are encountered.

All sack material and bulk barite will be furnished from our Grand Junction, Colorado facility, with OBM supplied from Newpark's Boulder, WY facility. If you have any questions following your review of this proposal, please call.

Regards,

Estes Ward  
Operations Manager  
Newpark Drilling Fluids, LP

# Project Summary

**Questar**  
**Exploration & Production**  
**WV 4D-12-8-21**  
**Sec 12-T8S-R21E**  
**Uintah, County Utah**

	Depth (ft)	Formations	Interval Comments	Mud Weight (ppg)	Mud Properties
	500'	Uinta  Surface T.D.	Hole size: 17 1/2" / Casing: 13 3/8"  AIR DRILLED	NA	NA
	3,025'	Green River Mahogeny	Air/KCL Water Hole size: 11.0" / Casing: 9 5/8" Flush Joint  Drill out with Air, maintaining 2100 +/- cfm. When water is encountered reduce air to +/- 1400 cfm and load the hole with KCL brine at 2-3% KCL. For increased hole stability mix Potassium Silicate for 0.2-0.5%. (approximately 3 sks/100 ft.)  Pump pre-hydrated NewGel or Flowzan sweeps for increased hole cleaning and for any tight hole and/or torque.  For trips, spot heavy brine if needed for trona flow, and at intermediate T.D. check hole conditions and spot high viscosity mud if needed.	Air  8.8	Vis (sec/qt): Water  PV (cp): NA  YP (#s/100ft <sup>2</sup> ): NA  FL (ml/30 min): NC  LGS %: < 1%  pH: 10.5-10.8
	6,300'	Intermediate T.D.	Mud weight at T.D. is expected to be in the 8.8-9.0 ppg range	8.8	Cl (mg/l): 11-15K KCL %: 2.5-3.0
	6,425' 9,325'	Wasatch Mesa Verde	Air/KCL Water Hole size: 8.5" / Liner: 7" Drill out with the fluid from the previous interval, maintaining 2-3% KCL without Silicate additions.	8.8	Vis (sec/qt): 40-45  PV (cp) : 12-20
	10,500' 11,775'	Sego Bucktongue	NewPHPA/Polymer (7500'-8000') Mud up as hole conditions dictate to a NewPHPA/Polymer system. Maintain properties as outlined increasing the PHPA concentration to 1 ppb.	10.0	YP (#s/100ft <sup>2</sup> ) : 10-12  FL (ml/30 min): 6-8
	11,925' 12,253'	Castlegate Blackhawk	Lost circulation may be a problem in this interval. If lost circulation is encountered, pump LCM pills as needed. If LCM pills will not control losses, by-pass the shakers and increase the LCM concentration in the system as needed.	11.0	LGS %: 3-5  pH: 10.0-10.5
	12,709'	Mancos Shale	If severe lost circulation is encountered, consider a DynaPlug squeeze.	11.2	Cl (mg/l): 11-15K
	12,750' +/-	Liner T.D.	Hole instability may be encountered in the Mesa Verde. Monitor torque, pump pressure, connection fill, and trip conditions for indications of hole instability and consider adding Asphalt if hole conditions dictate.	11.2	KCL %: 0
	13,133'	Mancos B	OptiDrill OBM Hole size: 7.0" / Casing: 4-1/2"  Drill out with the OptiDrill system, treating cement contamination as needed with OptiWet to prevent shaker blinding.	11.2	PV (cp): 15-25  YP (lbs/100ft <sup>2</sup> ): 8-10  HPHT (mls/30 min.): <20
	15,839' 16,731' 16,933'	Frontier equiv. Dakota Silt Dakota	Maintain hole cleaning during high ROP's with high viscosity sweeps. Use a 1:1 ratio of OptiVis RM and OptiVis.		O/W : 80:20 - 85:15  ES: 500+
	17,500'	Total Depth	CO2 in the gas stream while drilling under balanced will require additional Lime, emulsifiers and wetting agent.  Maintain mud weight as needed for well control. Spot high weight ECD pills for trips, logs, and casing operations.	15.5	Lime: 2-4 ppb LGS %: < 6



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
 Denver, CO. 80202  
 (303) 623-2205 FAX (720) 904-7970

# Project Summary

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

## DRILLING FLUID PROPERTIES

### Surface Hole: Air Drilled

Hole Size (in)	TVD (ft)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	API Fluid Loss (ml/30min)	Total Solids (%)
17 1/2 "	0-500'	NA	NA	NA	NA	NA

### Intermediate Hole: Air/KCL-Silicate Water

Hole Size (in)	MD (ft)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	API Fluid Loss (ml/30min)	KCL (%)	LGS Solids (%)
11"	500-6,300'	8.5-8.6	NA	NA	NA	2-3	< 1%

### Liner Interval: NewPHPA

Hole Size (in)	MD (ft)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	API Fluid Loss (ml/30min)	KCL (%)	LGS Solids (%)
8 1/2"	6,300'-8,000'	8.5-8.8	NA	NA	NC	3.0	< 1%
8 1/2 "	8,000'-12,750'	11.2-11.4	12-18	12-15	6-8	0	3-6

### Production Interval: OptiDrill OBM

Hole Size (in)	MD (ft)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	O/W Ratio (%)	HPHT Fluid Loss (ml/30min)	CaCL (mg/l) X 10,000	Electrical Stability (mv)	LGS Solids (%)
7.0 "	12,750'-17,500'	15.0-15.5	20-30	8-10	85/15	12-15	250-350	500 +	3-6

- Drilling fluid properties are guidelines only.
- Mud weights for guidelines only, allow hole conditions to dictate actual mud weights.
- Hole conditions should be closely monitored and product mix adjusted accordingly.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# Intermediate Interval

## 11" Hole (500' - 6,300')

**Questar**  
**Exploration & Production**  
**WV 4D-12-8-21**  
**Sec 12-T8S-R21E**  
**Uintah, County Utah**

Intermediate Interval Drilling Fluid Properties									
Depth Interval (TVD)	Mud Weight (ppg)	Viscosity (sec/qt)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	pH	API Fluid Loss (ml/30min)	Hardness Mg/l)	Low Gravity Solids	KCL %
500'-1,800' +/-	AIR	NA	NA	NA	NA	NA	NA	NA	2.0-3.0
1,800'+/-6,300'	8.6-8.8	27-28	NA	NA	10.5-10.8	NA	<100	< 1.0	2.0-3.0

- Drill out with Air/Mist maintaining 3% KCL and 1% Potassium Silicate in the mist water.
- When water is encountered, load the hole with 3% KCL water and begin aerated water drilling.
- While drilling with aerated water begin additions FlexFirm ka (Potassium Silicate) for 0.2-0.5% (mix at 3 sks per 100 ft)
- Pump pre-hydrated NewGel sweeps for increased hole cleaning, and LCM sweeps for seepage (Paper LCM while drilling with water)
- If water flows are encountered, spot heavy brine pills for trips, logs and casing operations.
- Offset information indicates the 1st major loss zone to be at +/- 3600 ft.

Challenges:	Strategies:
Gravel/Unconsolidated formation	If encountered, pump sweeps of pre-hydrated NewGel with a viscosity of 150 –300 sec/qt.
Water Flows (Trona)	If water flows become excessive, mud up and increase mud weight as needed for control. Treat carbonate contamination with <b>Lime/ Calcium Chloride</b> as needed.
Lost Circulation	While drilling with water, pump LCM sweeps consisting of paper. If drilling with mud, pump mixed LCM pills in the 20-30% LCM range.
Hole Cleaning	Pump sweeps on a regular basis and for any indications of insufficient hole cleaning. Circulate and pump sweeps before connections and for any anticipated down time.
Increase ROP with PDC Bits	Pump 20-40 bbl. Sweeps with NewEase 203, New100N, DynaDet, and SAPP. (FlexDrill Sweeps)
Hole Instability/Sloughing Shale	Maintain KCL at 3% and Potassium Silicate at 0.2-0.5%



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
 Denver, CO. 80202  
 (303) 623-2205 FAX (720) 904-7970

## Intermediate Interval

### 11" Hole (500' - 6,300')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

---

---

#### Offset Data:

- Wells in this area have encountered major losses at +/- 3600 ft.
- Gravel/unconsolidated formation has been encountered at 1380 ft.

#### Fluid Recommendations:

- Drill out cement, float collar and new formation. Test the integrity of the casing seat and squeeze if necessary.
- Drill out with Air/KCL Mist pumping +/- 2400 cfm air.
- When water is encountered, close in pits and begin Aerated water drilling. Bring KCL content to 3% and maintain 0.2-0.5% Potassium Silicate. (Mix 3 sks per 100 ft drilled.)
- If a Trona Water flow is encountered additions of **Lime** and/or **Calcium Chloride** should be used to adjust alkalinities as needed.
- The use of a premix tank is highly recommended. Pre-Hydrate **NewGel** for use as sweeps and for viscosity when a mud up is needed. Fill premix tank with fresh water. Treat out hardness with **SodaAsh** as needed. Add 0.25-0.5 ppb **Caustic Soda** for a 10.0-10.5 pH. Begin additions of 20-25 ppb **NewGel** allow sufficient circulating time for maximum hydration. Add 1.0-2.0 ppb **CFL II**. Then mix additional **NewGel** (30-40 ppb total) or a 120+ funnel viscosity. The pre-hydrated bentonite can be pumped from the premix to the pill tank and pumped downhole for sweeps or can be added slowly to the 3% KCL water for viscosity and rheology control.
- If penetration rates slow sweeps with **New 100N**, **NewEase 203**, **SAPP**, and **DynaDet** should be considered. (1% **New 100N**, 1% **NewEase 203**, 0.5-0.75 ppb **SAPP**, 0.2 % **DynaDet**). "**Flex Sweeps**"
- For trips, an increase in mud weight may be necessary to kill water flows. 9.8-10.0 ppg brine should be considered for this operation.
- Seepage and/or lost circulation may become a problem. For seepage while drilling with water, pump 20-30 bbl pills containing Paper LCM.
- If losses become severe, consider a mud up and LCM sweeps of **Cedar Fiber** and **FiberSeal** should be pumped and incorporated into the system as needed. If losses continue, increase coarse LCM in active system to 15-20%. If losses continue the use of a **DynaPlug** Squeeze is strongly recommended.
- At TD increase funnel viscosity for logs and casing operations as hole conditions dictate. Suggest funnel viscosity be increased to 45-50 sec/qt, before logging operations be attempted.
- At 6,300' ( intermediate T.D.) short trip, check hole conditions. If hole conditions dictate, add pre-hydrated **New-Gel** from the premix tank to the active system to increase funnel viscosity to 45-50 sec/qt and spot in the open hole for logs and casing operations

**DRILL STRING PACK-OFF:** Rapid penetration rate during fast drilling often deteriorates to pack-off, a situation which can lead to lost circulation and/or stuck pipe. Pack-off is typically self-induced by exceeding the maximum rate of penetration for a given annular flow rate. The solution to this is to control the penetration rate to a level that the pumps can adequately clean the hole while maintaining rheological properties in line with existing hydraulic parameters.

**SOLIDS CONTROL:** It is of the utmost importance that the shale shakers and flow line cleaners be equipped with the finest screens possible, and yet handle the flow rate. The desander and desilter units should be evaluated periodically and serviced to maximize performance.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970



# Liner Interval

8 1/2" Hole (6,300'- 12,750')

Questar  
Exploration & Production  
WV 4D-12-8-21  
**Sec 12-T8S-R21E**  
Uintah, County Utah

Liner Interval Drilling Fluid Properties								
Depth Interval (TVD)	Mud Weight (ppg)	Viscosity (sec/qt)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	pH	API Fluid Loss (ml/30min)	Hardness Mg/l)	Low Gravity Solids
6,300'-8,000'	8.8-9.0	27-28	NA	NA	10.0-10.5	NA	<40	< 1%
8,000'-12,750'	11.2-11.4	45-50	10-18	12-14	10.0-10.5	6-8	100+	4-6

- Drill out with aerated water continuing additions of KCL until mud-up at 7500'-8000'. After mud-up , allow the system to revert to a fresh water polymer system.
- As mud weight is increased, seepage losses can become severe. Treat with LCM pills as needed. If pill treatments will not contain the losses at reasonable levels, by-pass the shakers, retaining the pills and allowing the LCM concentration to increase as needed.
- Hole instability can occur in the Mesa Verde in this area. If encountered, consider adding Asphalt, building to a 4-6 ppb concentration.
- High pressure may be encountered in the Castlegate/Blackhawk. Monitor closely for increased pressure while drilling and use caution on trips to minimize possible swabbing.
- Mud weight at Liner Interval T.D. is expected to be in the 11.2-11.4 ppg range.

Challenges:	Strategies:
Hole Instability/Sloughing Shale	Consider 4-6 ppb Asphalt
Increase in Formation pressure	Monitor well conditions and increase density as needed with <b>NewBar</b> as needed.
Seepage/Lost Circulation	As mud weight is increased (10.0ppg +) seepage and losses may become a problem. For seepage pump 50 bbl sweeps with 5-10 ppb <b>DynaFiber</b> and 10-20 ppb <b>NewCarb</b> as needed. For partial or total losses pump sweeps with 10-15 ppb <b>FiberSeal</b> and <b>Cedar Fiber</b> . Severity of losses will determine size and quantity of LCM added. If losses are not controlled with sweeps consider 10-15% LCM in active system. For severe losses the use of a <b>DynaPlug</b> squeeze should be considered.
Differential Sticking	Maintain mud weight as low as possible. Control Low Gravity Solids below 6%, and control fluid loss at 8-10 mls/30 min.
Increase ROP with PDC Bits	Pump 20-40 bbl. Sweeps with NewEase 203, New100N, DynaDet, and SAPP. (FlexDrill Sweeps)



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# Liner Interval

8 1/2" Hole (6,300'-12,750')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

---

---

## Offset Data:

Wells in this area have experienced losses as mud weights are increased to control formation pressure. LCM sweeps are strongly recommended for this reason. Mud weights should be kept as low as practical but increases to 11.2 ppg may be required by Liner TD at 12,750'.

- Loss zones on offset wells were at 9200 ft and 9500 ft.

## Fluid Recommendations:

- Drill out cement, float collar and new formation with the system from the previous interval. Test the integrity of the casing seat and squeeze if necessary.
- Continue drilling with the aerated water from the previous interval until mud up at +/- 7500 ft or as hole conditions dictate. After mud-up allow the KCL to naturally dissipate by dilution with fresh water. Begin additions of 0.5-1.0 ppb **NewPHPA** and maintain throughout the interval.
- Maintain viscosity with PreHydrated **NewGel** until chlorides have dropped below 5000-7000 mg/l. After chlorides have dropped **NewGel** will not need to be pre-hydrated and can be added directly to the system.
- Begin additions of **NewPHPA**. Concentration of **NewPHPA** should be maintained at 0.5-1.0 ppb throughout the interval. As mud weight increases additions of **PHPA** should be switched from **NewPHPA DLMW** to the shorter chain **NewPHPA DSL**.
- If hole conditions dictate, consider 4-6 ppb Asphalt.
- If penetration rates slow sweeps with **New 100N**, **NewEase 203**, **SAPP**, and **DynaDet** should be considered. (1% **New 100N**, 1% **NewEase 203**, 0.5-0.75 ppb **SAPP**, 0.2 % **DynaDet**). "**Flex Sweeps**"
- Increase mud weight as needed to control formation pressures as needed. Mud weights should be maintained as low as practical to reduce chance of losses and differential sticking. Increase mud weight as needed with **NewBar**.
- As density increases additions of **NewEdge** and/or **DrillThin** should be added for rheology control.
- As bottom hole temperatures increase and additional fluid loss control is desired supplement the **NewPAC** with **DynaPlex** for fluid loss control. Lower API filtrate to 6-8 cc's with additions of **NewPAC** and **DynaPlex**.
- As mud weight is increased seepage and/or lost circulation may become a problem. For seepage pump 20-30 bbl pills containing a combination of **NewCarb** and **DynaFiber** mixed at a 2:1 ratio. If partial or total returns are encountered, LCM sweeps with a varied size distribution including **Cedar Fiber** and **Fiber Seal**, **PhenoSeal** and other assorted sizes should be considered and incorporated into the system as needed. 20-25% LCM in the active system may be required. The type, size and quantity of LCM used will depend on the severity of losses. If losses are severe a **DynaPlug** squeeze should be considered.
- At TD increase funnel viscosity for logs and casing operations as hole conditions dictate. Suggest funnel viscosity be increased to 50-55 sec/qt, before logging or casing operations be attempted.
- While circulating casing it is recommended to reduce Yield Points for cementing operations.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# Production Interval

## 6 1/8" Hole (12,750'-17,500')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

### Production Interval Drilling Fluid Properties

Depth Interval (TVD)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	O/W Ratio %	HTHP Fluid Loss (ml/30min)	Excess Lime (PPB)	Electrical Stability (MV)	Low Gravity Solids	CaCl Mg/l Water
13,000'-17,725'	15.0-15.5	25-35	8-10	85:15	12-15	2-4	500+	< 6	300K

### Drilling Fluid Recommendations: (12,750'-17,500')

- Displace to a OptiDrill OBM after finishing the liner job at 12,750'.
- After displacement, maintain the OptiDrill system within the parameters outlined above.
- Offsets in the area have encountered high rates of seepage in this interval. If indications of seepage are observed, sweeps of NewCarb C, Dynafiber C & M, NewSeal, and CyberSeal are recommended. Mixing ratios are recommended to be at 5:1 NewCarb M to DynaFiber, NewSeal, and CyberSeal. If losses continue to be a problem, consider trying different sizes and combinations until seepage is slowed.
- Maintain rheology low to reduce ECD values and reduce surge and swab during connections and trips.
- Drill as underbalanced as possible to help prevent losses and increase penetration rates.
- For pressure control, spot high weight pills with an equivalent mud weight to drilling ECD's. On trips in, stage these pills out and divert to storage for further use. High weight pills in excess of the drilling ECD should be avoided due to possible lost circulation.

Challenges	Strategies
Displacement	<ul style="list-style-type: none"> <li>• Have 1200-1300 bbls of OBM volume on location along with a pump capable of keeping up with displacement rates.</li> <li>• Pump a 10-20 bbl viscosified OBM spacer ahead of the OptiDrill (enough for 500 ft + separation)</li> <li>• A steady pump rate for either turbulent or plug flow should be used. Reciprocate and rotate to assist in minimizing channeling.</li> <li>• Do not shut down once displacement commences.</li> <li>• Should any contamination occur, isolate the contaminated fluid for reconditioning.</li> </ul>
Seepage/lost Circulation.	Pump LCM sweeps when seepage and/or losses are indicated. Sweeps should be a mixture of, NewCarb, DynaFiber, NewSeal, and CyberSeal. If lost returns are encountered, consider a Diaseal M or cross linked polymer squeeze.
Maintaining Oil wet solids	For every 1.0 ppg mud weight increase, mix 0.02 gal/bbl OptiWet
Pressure control	<ul style="list-style-type: none"> <li>• Spot weighted pills calculated to give a bottom hole pressure equal to drilling ECD.</li> <li>• Do not exceed drilling bottom hole pressure with the ECD pill. Lost circulation has been a problem on offset wells.</li> <li>• Stage weighted pills out of the hole and recover for future use.</li> </ul>



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# Production Interval

## 6 1/8" Hole (12,750'-17,500')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

---

---

### Maintenance Procedure:

**HPHT** - Maintain HPHT values within programmed parameters. Additions of **OptiMul** and **OptiPlus**, at recommended concentrations should maintain the HTHP at recommended levels. If hole conditions indicate a need for lower HPHT values, **Opti G** at 2-4 ppb is recommended.

**Electrical Stability**— Electrical stability should be used as a guide not as an absolute in determining maintenance requirements. Actual values are not critical but should be observed for trends or changes. Decreases in electrical stability should be noted along with other mud properties to determine treatments. To increase electrical stability add emulsifiers and wetting agents **OptiMul** and **OptiPlus** or decrease water content.

**Oil/Water Ratio** - Maintain the oil/water ratio in the 90:10-80:20 range depending on mud weight and condition.. Higher water content will decrease the amount of **OptiVis** needed for rheology.

**Mud weight** - Maintain minimum fluid densities with solids equipment. Monitor hole conditions and all drilling parameters closely for indications of increases in formation pressures and adjust fluid densities accordingly. Drilling with a minimum amount of overbalance will reduce the possibility of losing returns and/or of differentially sticking the drill string. Mud weight on offset wells was in the 15.0-15.5 ppg range at T.D.

**Rheology** - Maintain solids as low as possible. Increase rheology as needed for hole cleaning with a combination of **OptiVis (Bentone 910)** and **Opti Vis RM** or **Opti Vis PS** and water content.

**Lime** - Maintain the excess Lime at 2-3 ppb excess.

**Hole cleaning** - Calculate rheology requirements based on ROP, pump rates and hole conditions. Adjust as needed .

**Mud losses downhole**—Monitor ECD's with Hy-Calc, maintaining the lowest values possible. If losses are encountered; sweeps containing **NewCarb**, **DynaFiber**, **Opti-G**, and **NewSeal** should be circulated to aid in the prevention of losses. If seepage losses continue and/or become severe, consider spotting a pill with **Magma Fiber (Fine & Regular)** and the above formulation. Keep the hole full at all times, and avoid excessive swabbing and/or surge actions when tripping.

**Solids Control** - Maintain low gravity solids at 4-6 % by volume. The high performance shakers should be equipped with the finest mesh screens that will handle the circulating volume and not cut barite out.

**Water Contamination**— Keep all water sources off the mud pits. If contamination occurs, treat with emulsifiers and Calcium Chloride as needed.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# Production Interval

6 1/8" Hole (12,750'-17,500')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

**Recommended materials for relaxed filtrate OptiDrill system :**  
**( 85:15 Oil/Water Ratio)**

Product	Function	Concentration
<b>NewBar</b>	Weighting material	As needed
<b>OptiVis</b>	Organophilic Clay / Viscosifier	2-4 ppb
<b>OptiMul</b>	Primary Emulsifier	2.0 ppb
<b>OptiPlus</b>	Secondary Emulsifier	4.0 gal/bbl.
<b>OptiVis RM</b>	Low End Rheology Modifier	0.1-0.2 ppb
<b>Calcium Chloride Water</b>	Internal Phase	10.0%-20.0 % by volume
<b>Calcium Chloride</b>	Salinity/Activity	300,000 - 350,000 mg/l
<b>OptiG</b>	Fluid Loss control Additive	1.0-4.0 ppb
<b>Lime</b>	Alkalinity Additive	5 ppb
<b>NewCarb M</b>	Loss Circulation Material	10.0 ppb
<b>NewCarb F</b>	Loss Circulation Material	As required
<b>DynaFiber</b>	Loss Circulation Material	As required



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970



**OILFIELD WASTE MANAGEMENT PROPOSAL**

For

**Questar Market Resources**

**SOLI-BOND® Processing and Disposal of Drilling Waste**

**Batch Treatment**

**Wells: WV 4D-12-8-21**

**SWSE Section 12**

**T8S – R21E**

**Uintah County, Utah**

Prepared For: Jon Gent  
Region Drilling Manager  
Questar Market Resources  
1050 17<sup>th</sup> Street, Suite 500  
Denver, Colorado 80265  
(303) 672-6927

Prepared By: Robert J. Wilson  
Technical Sales Representative  
Soli-Bond, Inc.  
(303) 579-9800

**CONFIDENTIALITY NOTICE:**

Unless otherwise indicated or obvious from the Proposal, the information contained in this Proposal is privileged and confidential, intended for the use of the individual or entity named above. Dissemination, distribution or copying of this document is strictly prohibited.

SOLI-BOND® Processing and Disposal of Drilling Waste  
BATCH TREATMENT  
QUESTAR • WV 4D-12-8-21  
Uintah County, Utah

**OVERVIEW**

Soli-Bond, Inc. (SBI) proposes to utilize the SOLI-BOND® Process for the treatment of **Drilling Waste** on the **WV 4D-12-8-21** in Uintah County, Utah, which will be followed by onsite disposal of the processed material.

This proposal will serve to delineate the specifications and criteria for achieving the project objectives as required by **Questar Market Resources** (Client) and the appropriate regulatory entities.

**GENERAL DESCRIPTION OF THE SOLI-BOND® PROCESS**

The SOLI-BOND® Process involves the controlled addition of a non-toxic, chemically reactive, portland-cement-based reagent or reagents to a waste, followed by the mixing of the reagent with the waste to form homogeneous slurry similar to viscous mortar. Oily substances that may be present in the waste are broken up into small droplets or particles and dispersed throughout the reagent/waste mixture during the mixing phase of the process. After the mixing phase, an irreversible chemical reaction begins to occur between the reagent and water present (or added) in the waste, ultimately causing the reagent/waste mixture to be transformed into a solid granular material with a “soil-like” consistency, typically within 48 hours after processing. Any dispersed particles of oily substances within the processed material are *physically* locked in place or “micro-encapsulated” in their isolated state inside the reacted cementitious matrix, preventing them from re-coalescing and suddenly being released to the environment at significant rates. The same irreversible reaction *chemically* stabilizes various metals that may be present in the waste, primarily by transforming them into less soluble metal hydroxides and other chemical species, thus greatly reducing their mobility and availability to the surrounding environment as well. In summary The SOLI-BOND® Process reduces the leaching rate of target constituents of concern from a waste form to such a degree that they can no longer cause harm to health or the environment. The SOLI-BOND® Process is a waste treatment method more generally known as Solidification/Stabilization (S/S). S/S has been recognized and prescribed by the United States Environmental Protection Agency for many years as an effective technology for the treatment of waste containing various metals as well as non-volatile and semi-volatile organic substances.

**INNOCUOUS WASTE APPLICATIONS**

The SOLI-BOND® Process can also be applied to solidify innocuous oilfield wastes such as spent water based drilling fluids and physically unstable water based drill cuttings to avoid the increased difficulties typically associated with the disposal of liquid or semi-solid wastes. Irreversibly transforming the *physical* properties of an innocuous waste, from a liquid or semi-solid state that’s structurally unstable, into a solid, granular material with load bearing capability, can be the sole reason for using The SOLI-BOND® Process. In addition, the chemically driven transformation into a dry solid occurs quickly, with minimal volume addition and the process can accommodate waste with high fluid content. For oilfield waste pit applications, the process provides more rapid solidification of the pit contents, more room for the prescribed depth of soil cover and can greatly reduce the waiting period for the pit contents to dry sufficiently for pit closure as opposed to that required for conventional closure methods.



SOLI-BOND® Processing and Disposal of Drilling Waste  
BATCH TREATMENT  
QUESTAR • WV 4D-12-8-21  
Uintah County, Utah

**SITE AND APPLICATION DESCRIPTION**

The subject work site is an area constructed for the drilling and production of the gas well covered in this proposal. The well plan contemplates the use of an oilbase drilling fluid during the drilling of the production section of the well. As this section of the well is drilled, cuttings will be generated, transported to the surface within the drilling fluid, then mechanically separated from the drilling fluid as waste. These separated cuttings are expected to contain elevated levels of adhered/absorbed hydrocarbons due to their prior contact with the oilbase drilling fluid. These “oilbase cuttings” will be collected in steel catch tanks provided by the Client as drilling progresses and then placed in the separate oil base cuttings pit.

In addition to the “oilbase cuttings” described above, oily waste fluids and sediments may be generated at the work site during drilling operations and after drilling is completed the drilling fluid containment system will be cleaned thus generating some oily cleaning waste as well. It is these oilbase cuttings, waste fluids and sediments and cleaning waste that comprise all the waste to be treated and disposed of under this proposal.

Based on Client information and allowing for well bore washout, decompression/expansion of the drilled cuttings and the adhered/absorbed drilling fluids (“WEF”), the total volume of waste to treat was estimated as follows:

**WV 4D-12-8-21**

<b>4,750 feet of 6.125 inch diameter hole x WEF factor of 3:</b>	<b>519</b>
<b>Estimated additional sediments and cleaning waste:</b>	<b><u>10,500</u></b>
<b>Total Estimated Barrels of Waste to Treat:</b>	<b>11,019</b>

SBI proposes to apply the SOLI-BOND® Process to the oilbase cuttings and other indicated waste from the well during drilling operations to achieve the following objectives:

- Permanently reduce the leaching rate of target constituents of concern from the treated material to within prescribed limits.
- Irreversibly solidify the physically unstable waste to allow onsite disposal and support of soil cover without subsidence.
- Accomplish treatment with minimal volume addition to minimize disposal cell size and facilitate required minimum space for soil cover.
- Achieve rapid solidification of the waste to allow prompt final disposal.

**PRELIMINARY ACTIVITIES**

SBI personnel collected a sample of waste similar in characteristics to the waste to be generated on the subject project. The waste sample was used to conduct bench scale SOLI-BOND® processing, which has been carried out to determine effective reagent formulations, reagent/waste mix ratios, pricing and other aspects of this proposal.

**OPERATIONAL PLAN**

SBI jobsite operations will be conducted as follows:

SOLI-BOND® Processing and Disposal of Drilling Waste  
BATCH TREATMENT  
QUESTAR • WV 4D-12-8-21  
Uintah County, Utah

- After drilling the oilbase section of the well, SBI will install the SOLI-BOND® Waste Processing System at the well site. The “oilbase cuttings” will be treated “in-situ” in the existing lined pit.
- SBI will mobilize personnel to the jobsite to process the waste that has accumulated in the lined oil base cuttings pit.
- Upon arrival at the jobsite, the SBI Site Foreman will conduct a Jobsite Safety Assessment with SBI crew, discussing all potential jobsite safety hazards, required personal safety gear and accident avoidance and conduct safety meetings with SBI crew prior to each day’s work throughout the project.
- SBI and Client Representative will verify the volume of waste to treat in each batch prior to process operations.
- SBI crew will then process the waste with the SOLI-BOND® Waste Processing System.
- Waste processing will be preformed during eight (8) hour daylight shifts. After daily onsite process operations are completed SBI personnel will prepare a SBI field ticket for Client Representative signature, indicating the volume of waste processed (in barrels).
- Components of The SOLI-BOND® Waste Processing System may remain at the jobsite until all waste to treat has been processed.
- After all waste is processed from the well, a composite sample of the processed material will be collected for laboratory analysis to verify that it complies with criteria under the section herein entitled “Performance Criteria.”
- SBI will utilize the existing lined pit as an on-site disposal cell sized to accommodate the processed oilbase cuttings and four (4) feet of soil cover after final reclamation of the drill site. Client has provided a plastic liner for the disposal cell, including installation. After achievement of performance criteria is verified, SBI will backfill the cell to the adjacent surface elevation thus constituting final disposal of the processed material. SBI will then demobilize equipment and personnel thus concluding SBI’s onsite operations.
- A SBI Waste Treatment and Disposal Report suitable for submittal to the appropriate regulatory agencies will then be prepared documenting all pertinent aspects of the project and will be submitted to the Client.

**PERFORMANCE CRITERIA**

The treated waste will comply with the following criteria:

1. Leachable Oil and Grease less than 10 mg/L.
2. Leachable Total Dissolved Solids to be less than 5000 mg/L and/or leachable salts below acceptable site-specific guidelines.

Compliance with the performance criteria will be certified by an accredited testing laboratory utilizing the appropriate tests as prescribed and will be documented in a final report submitted to Client and the appropriate regulatory agencies as required.

**SCHEDULE** (All time/days are estimates and may change due to jobsite conditions)

SOLI-BOND® Processing and Disposal of Drilling Waste  
**BATCH TREATMENT**  
QUESTAR • WV 4D-12-8-21  
Uintah County, Utah

<b>ITEM / SERVICE</b> (Based on estimated 11,019 total barrels of waste to process)	<b>ESTIMATED DAYS</b>
Mobilization And Setup	1
Estimated SOLI-BOND® PWD Waste Processing System Rental Days	15
Process Material, Backfill Cell	12
Takedown and Demobilization	1

**ITEMS FURNISHED with SOLI-BOND® PWD Waste Processing System**

**Equipment**

- SB-2-7 Processor
- SOLI-BOND® Reagent Storage Silo w/ Discharge Auger
- Back Hoe Loader
- Ancillary Equipment
- First Aid and Safety Equipment
- SBI Crew Transportation

**Personnel**

- *SBI Site Foreman*
- *SBI Operator Material*
- Fuel necessary to operate Soli-Bond's motorized equipment.

**Miscellaneous**

- SBI Equipment Cleaning.
- One Laboratory Analysis of Processed Material. (for parameters indicated herein)
- SBI Waste Treatment and Disposal Report.

**CLIENT RESPONSIBILITY**

- Client will provide SBI with a written work order or other Client recognized document to contract SBI to perform the work as described herein.
- Client will provide SBI with a list of any Client requirements related to performing and being compensated for the work described herein.
- Client will provide "all weather" ingress and egress to the site.
- Client will provide process add-mix water.
- Client agrees that delays or interruptions in SBI's work described herein caused by "Acts of Nature" or events under the responsibility of the Client or Client contractors (excluding SBI and it's contractors) may result in additional charges to Client.

# QUESTAR EXPL. & PROD.

WV #4D-12-8-21

LOCATED IN UINTAH COUNTY, UTAH  
SECTION 12, T8S, R21E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY




PHOTO: VIEW FROM EXISTING ROAD ACCESS

CAMERA ANGLE: SOUTHEASTERLY



**UELS** Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

8  
MONTH

15  
DAY

01  
YEAR

PHOTO

TAKEN BY: D.A.

DRAWN BY: K.G.

REV: 09-26-07 Z.L.


*T8S, R21E, S.L.B.&M.*

**QUESTAR EXPLR. & PROD.**

Well location, WV #4D-12-8-21, located as shown in the NW 1/4 NW 1/4 of Section 12, T8S, R21E, S.L.B.&M. Uintah County, Utah.

## BASIS OF ELEVATION

BENCH MARK (45 EAM) LOCATED IN THE N 1/2 OF SECTION 5, T8S, R21E, S.L.B.&M. TAKEN FROM THE BRENNAN BASIN QUADRANGLE, UTAH, UINTAH COUNTY 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4689 FEET.



**CERTIFICATE**

THIS IS TO CERTIFY THAT THE ABOVE RECORDED AND INDEXED FROM  
FIELD NOTES OF ACTUAL SURVEY PREPARED BY ME OR UNDER MY  
SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE  
BEST OF MY KNOWLEDGE AND BELIEF. 161319

REGISTERED LAND SURVEYOR  
REGISTRATION NO. 181319

REVISED: 09-27-07 S.L.

**UNTAE ENGINEERING & LAND SURVEYING**  
**85 SOUTH 200 EAST - VERNAL, UTAH 84078**  
**(435) 789-1017**

SCALE 1" = 1000'		DATE SURVEYED: 8-6-01	DATE DRAWN: 8-13-01
PARTY D.A. J.A. D.COX		REFERENCES G.L.O. PLAT	
WEATHER WARM		FILE QUESTAR EXPLR. & PROD.	

1950 Brass Cap  
0.7" High. Steel  
Post ▲

***N88°52'20"E - 2660.26' (Meas.)***

N89°13'47"E - 2722.46' (Meas.)

**▲ Brass Cap**

**Bronze Cap  
1.5' High,  
Set Stone,  
2 Stones**

WV #4D-12-8-21

*Elev. Ungraded Ground = 5008'*

**N01°35'58"W - 2704.43' (Meas.)**

**N01°37'35"W - 2692.36' (Meas.)**

N00°46'12"W - 2714.78' (Meds.)

**N0101'28"W - 2696.12' (Meas.)**

### Brass Cap

12

**Brass Cap**

BASIS OF BEARINGS IS THE EAST LINE OF THE NE 1/4  
OF SECTION 13, T8S, R21E, S.L.B.&M. WHICH IS ASSUMED  
FROM G.L.O. INFORMATION TO BEAR NO'49'W.

Brass Cap  $589^{\circ}09'48''W - 2658.73'$  (Meas.)

N89°15'16"E - 2656.54' (Meas.)

**LEGEND:**

L = 90° SYMBOL

● = PROPOSED WELL HEAD.

▲ = SECTION CORNERS LOCATED.

(AUTONOMOUS NAD 83)

LATITUDE = 40°08'41.23" (40.144786)

LONGITUDE = 109°30'39.54" (109.510983)  
(AUTONOMOUS NAV. OF)

(AUTONOMOUS NAD 27)

LATITUDE = 40°08'41.36" (40.144822)

LONGITUDE = 109°30'37.06" (109.510294)

# QUESTAR EXPLR. & PROD.

## LOCATION LAYOUT FOR


WV #4D-12-8-21  
SECTION 12, T8S, R21E, S.L.B.&M.  
356' FNL 475' FWL

FIGURE #1

SCALE: 1" = 60'  
DATE: 09-28-07  
Drawn By: S.L.


Existing Access Road

EXISTING ROAD



### NOTE:

Flare Pit is to be located a min. of 100' from the Well Head.



### NOTES:

Elev. Ungraded Ground At Loc. Stake = 5008.0'

FINISHED GRADE ELEV. AT LOC. STAKE = 5008.0'

UINTAH ENGINEERING & LAND SURVEYING

85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

# QUESTAR EXPLR. & PROD.





## TYPICAL CROSS SECTIONS FOR

WV #40-12-8-21  
SECTION 12, T8S, R21E, S.L.B.&M.  
356' FNL 475' FWL

FIGURE #2

1" = 20'  
X-Section  
Scale  
1" = 50'

DATE: 09-28-07  
Drawn By: S.L.



### NOTE:

Topsil should not be Stripped Below Finished Grade on Substructure Area.

### APPROXIMATE ACREAGES

WELL SITE DISTURBANCE = ± 3.557 ACRES  
ACCESS ROAD DISTURBANCE = ± 0.131 ACRES  
TOTAL = ± 3.688 ACRES

### \* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION

### APPROXIMATE YARDAGES

#### CUT

(6") Topsoil Stripping = 1,560 Cu. Yds.  
Remaining Location = 18,040 Cu. Yds.

TOTAL CUT = 19,600 CU.YDS.

FILL = 4,020 CU.YDS.

EXCESS MATERIAL = 15,580 Cu. Yds.

Topsoil & Pit Backfill = 5,550 Cu. Yds.  
(1/2 Pit Vol.)

EXCESS UNBALANCE = 10,030 Cu. Yds.  
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017







SCALE: 1" = 60'  
DATE: 09-28-07  
Drawn By: S.L.

**QUESTAR EXPLR. & PROD.**  
**INTERIM RECLAMATION PLAN FOR**  
WV #4D-12-8-21  
SECTION 12, T8S, R21E, S.L.B.&M.  
356' FNL 475' FWL

**FIGURE #3**

Access Road


EXISTING ROAD



 INTERIM RECLAMATION

**UINTAH ENGINEERING & LAND SURVEYING**  
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017





# LEGEND:

● PROPOSED LOCATION

## QUESTAR EXPL. & PROD.

WV #4D-12-8-21  
SECTION 12, T8S, R21E, S.L.B.&M.  
356' FNL 475' FWL



Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813



TOPOGRAPHIC  
MAP

8 1501  
MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: K.G. REV: 09-26-07 Z.L.
















APPROXIMATE TOTAL PIPELINE DISTANCE = 6,085' +/-

# LEGEND:

- EXISTING PIPELINE
- PROPOSED PIPELINE
- PROPOSED ACCESS



## QUESTAR EXPL. & PROD.

WV #4D-12-8-21  
SECTION 12, T8S, R21E, S.L.B.&M.  
356' FNL 475' FWL

TOPOGRAPHIC  
MAP

8 15 01  
MONTH DAY YEAR

D  
TOPO

SCALE: 1" = 1000' DRAWN BY: K.G. REV: 09-26-07 Z.L.



Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813



Well:		API Number:	Commenced:
WV 5W-36-7-21	drlg rpts/wcr	4304734099	05/29/2003
WV 4D-12-8-21	drlg rpts/wcr	4304734268	09/26/2003
WV 9W-11-8-21	drlg rpts/wcr	4304734274	09/26/2003
Brennan 1	wcr	4304715417	07/19/2003
WV 8W-1-8-21	drlg rpts/wcr	4304734009	06/16/2003
OU SG 4W-11-8-22	drlg rpts/wcr	4304735071	06/11/2005
OU SG 5W-11-8-22	drlg rpts/wcr	4304735072	06/11/2005
OU SG 14W-11-8-22	drlg rpts/wcr	4304735114	06/16/2005
OU SG 13W-11-8-22	drlg rpts/wcr	4304735377	06/16/2005
GH 16W-19-8-21	drlg rpts/wcr	4304735325	06/27/2005
OU GB 8MU 10-8-22	drlg rpts/wcr	4304735422	03/22/2006
WV 3DML-13-8-21	drlg rpts/wcr	4304737923	09/27/2006
GB 12SG-29-8-22	drlg rpts/wcr	4304738766	04/25/2007
GB 4SG-36-8-21	drlg rpts/wcr	4304738764	05/03/2007
BZ 10D-16-8-24	drlg rpts/wcr	4304737671	05/09/2007
RW 34-34AD	drlg rpts/wcr	4304736351	06/07/2007
RWS 14D-6-9-24	drlg rpts/wcr	4304737414	07/20/2007

## NOTICE

Utah Oil and Gas Conservation General Rule R649-3-21 states that,

- A well is considered completed when the well has been adequately worked to be capable of producing oil or gas or when well testing as required by the division is concluded.
- Within 30 days after the completion or plugging of a well, the following shall be filed:
  - Form 8, Well Completion or Recompletion Report and Log
  - A copy of electric and radioactivity logs, if run
  - A copy of drillstem test reports,
  - A copy of formation water analyses, porosity, permeability or fluid saturation determinations
  - A copy of core analyses, and lithologic logs or sample descriptions if compiled
  - A copy of directional, deviation, and/or measurement-while-drilling survey for each horizontal well

Failure to submit reports in a timely manner will result in the issuance of a Notice of Violation by the Division of Oil, Gas and Mining, and may result in the Division pursuing enforcement action as outlined in Rule R649-10, Administrative Procedures, and Section 40-6-11 of the Utah Code.

---

As of the mailing of this notice, the division has not received the required reports for

Operator: Questar Exploration & Production Co Today's Date: 11/27/2007

Well: API Number: Drilling Commenced:

See Attachment

To avoid compliance action, required reports should be mailed within 7 business days to:

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

If you have questions or concerns regarding this matter, please call (801) 538-5284.

cc: Well File  
Compliance File



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0137  
Expires: March 31, 2007

**SUNDRY NOTICES AND REPORTS ON WELLS**

**Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.**

**SUBMIT IN TRIPLICATE- Other instructions on reverse side.**

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. <b>UTU 0806</b>
2. Name of Operator <b>Questar Exploration and Production Inc.</b>		6. If Indian, Allottee or Tribe Name <b>Ute Tribe</b>
3a. Address <b>1050 17th Street, Suite 500 Denver, CO 80265</b>	3b. Phone No. (include area code) <b>303 308-3068</b>	7. If Unit or CA/Agreement, Name and/or No. <b>Wonsits Valley</b>
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) <b>2167' FNL, 586' FWL, SWNW, Sec 12-T8S-R21E</b>		8. Well Name and No. <b>WV 4D 12 8 21</b>
		9. API Well No. <b>43-047-34268</b>
		10. Field and Pool, or Exploratory Area <b>Wonsits Valley</b>
		11. County or Parish, State <b>Utah County, Utah</b>

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other well status
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Questar Exploration and Production Company's (QEP) records show that this well was spud on 9/26/03 and has set 40' of 20" conductor. QEP plans to drill this well in 2008 and QEP is currently evaluating the feasibility of drilling the surface casing with a small rig then coming in with a large drilling rig to drill the rest of the well bore. Based on current data and geologic evaluation, this well will be drilled to a deeper depth and drilling operations to total depth will require a larger drilling rig. This well site has recently be on-sited with the Tribe and paperwork requesting your approval will be submitted to your office in the near future providing details of QEP's revised drilling plans for this well.

This sundry is being submitted per the August 23, 2007 written order of the authorized officer received from your office by QEP on August 27, 2007 requesting a time line be provided for when this well will be drilled and completed.

14. I hereby certify that the foregoing is true and correct Name (Printed/Typed) <b>Debra K. Stanberry</b>		Title <b>Supervisor, Regulatory Affairs</b>
Signature		Date <b>10/16/2007</b>

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by _____ Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Title _____ Office _____	Date _____
--	-----------------------------	------------

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

**RECEIVED**

**DEC 11 2007**

DIV. OF OIL, GAS & MINING

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**SUNDRY NOTICES AND REPORTS ON WELLS**

**Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.**

FORM APPROVED  
OMB No. 1004-0135  
Expires July 31, 1996

5. Lease Serial No.

UTU-0806

6. If Indian, Allottee or Tribe Name

UTE INDIAN TRIBE

7. If Unit or CA/Agreement, Name and/or No.

WONSITS VALLEY UNIT

8. Well Name and No.

WV 4D-12-8-21

9. API Well No.

43-047-34268

10. Field and Pool, or Exploratory Area

WONSITS VALLEY

11. County or Parish, State

UINTAH

**SUBMIT IN TRIPLICATE - Other Instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

QUESTAR EXPLORATION & PRODUCTION, CO.

Contact: Jan Nelson

3a. Address

11002 E. 17500 S. VERNAL, UT 84078

3b. Phone No. (include area code)

435-781-4331

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

356' FNL 475' FWL, NWNW, SECTION 12, T8S, R21E

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input checked="" type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

QUESTAR EXPLORATION AND PRODUCTION COMPANY (QEP) REQUEST PERMISSION TO CHANGE THE CASING PROGRAM, CEMENT PROGRAM, BOP AND DRILLING FLUID IN ORDER TO HAVE A SAFER OPERATION, ENHANCE DRILLING EFFICIENCY AND CAPTURE COST SAVINGS.  
PLEASE NOTE THAT THE DRILLING FLUID IN THE INTERVAL 500' TO 5,900' WILL BE AIR/MIST AERATED SALT WATER.

ATTACHED IS A REVISED DRILLING PLAN. CEMENT, BOP DIAGRAM, DRILLING FLUIDS PROGRAM AND WELLBORE DIAGRAM.

FOR TECHNICAL QUESTIONS, PLEASE CONTACT JIM DAVIDSON, CHIEF DRILLING ENGINEER FOR QEP AT (303) 308-3090.

Accepted by the  
Utah Division of  
Oil, Gas and Mining

JAN 25 2008

FOR RECORD ONLY

DIV OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

Laura Bills

Signature

*Laura Bills*

Title

Regulatory Affairs

Date

January 22, 2008

**THIS SPACE FOR FEDERAL OR STATE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

**CONFIDENTIAL**

DRILLING PROGRAM

ONSHORE OIL & GAS ORDER NO. 1  
Approval of Operations on Onshore  
Federal Oil and Gas Leases

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas No. 1, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

**1. Formation Tops**

The estimated tops of important geologic markers are as follows:

<u>Formation</u>	<u>Depth</u>
Uinta	Surface
Green River	3,025'
Wasatch	6,425'
Mesaverde	9,325'
Sego	11,775'
Castlegate	11,925'
Blackhawk	12,253'
Mancos Shale	12,709'
Mancos B	13,133'
Frontier	15,839'
Dakota Silt	16,731'
Dakota	16,933'
TD	17,500'

**2. Anticipated Depths of Oil Gas Water and Other Mineral Bearing Zones**

The estimated depths at which the top and bottom of the anticipated water, oil, gas. Or other mineral bearing formations are expected to be encountered are as follows:

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
Gas	Wasatch	6,425'
Gas	Mesaverde	9,325'
Gas	Blackhawk	12,253'
Gas	Mancos Shale	12,709'
Gas	Mancos B	13,133'
Gas	Dakota	16,933'

All fresh water and prospectively valuable minerals encountered during drilling will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

DRILLING PROGRAM

All water shows and water-bearing sands will be reported to the BLM in Vernal, Utah. Copies of State of Utah form OGC-8-X are acceptable. If flows are detected, samples will be submitted to the BLM along with any water analyses conducted. Fresh water will be obtained from Wonsits Valley water right # A36125 (which was filed on May 7, 1964,) or Red Wash water right # 49-2153 (which was filed on March 25, 1960). It was determined by the Fish and Wildlife Service that any water right number filed before 1989 is not depleting to the Upper Colorado River System, to supply fresh water for drilling purposes. All water resulting from drilling operations will be disposed of at Red Wash Central Battery Disposal Site; SWSE, Section 27, T7S, R23E or Wonsits Valley Disposal Site; SWNW, Section 12, T8S, R21E.

**3. Operator's Specification for Pressure Control Equipment:**

- A. 13-5/8" 2000 psi annular BOP (schematic included) from surface casing seat to 9-5/8" casing point.
- B. 11" or 13-5/8" 10,000 psi double gate, 10,000 psi single gate, 10,000 psi annular BOP (schematic included) from 9-5/8" casing point to total depth. The choice of BOP stacks is based on the drilling contractor's availability.
- C. Functional test daily
- D. All casing strings shall be pressure tested (0.2 psi/foot or 1500 psi, whichever is greater) prior to drilling the plug after cementing; test pressure shall not exceed the internal yield pressure of the casing.
- E. Ram type preventers and associated equipment shall be tested to approved stack working pressure if isolated by test plug or to 50 percent of internal yield pressure of casing whichever is less. BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc..., for a 10M system and individual components shall be operable as designed.

DRILLING PROGRAM

4. **Casing Design:**

Hole Size	Csg. Size	Top (MD)	Bottom (MD)	Wt.	Grade	Thread	Cond.
26"	20"	sfc	40-60'	Steel	Cond.	None	Used
17-1/2"	13-3/8	sfc	500'	54.5	K-55	STC	New
12-1/4"	9-5/8"	sfc	6300'	47	HCP-110	Flush Jnt **	New
8-1/2"	7"	sfc	9,000'	26 SDrift	HCP-110	LTC	New
8-1/2"	7"	9000'	12,750'	29* SDrift	HCP-110	LTC	New
6-1/8"	4-1/2"	sfc	13,000'	15.1	P-110	LTC	New
6-1/8"	4-1/2"	13,000'	15,000'	15.1	Q-125	LTC	New
6-1/8"	4-1/2"	15,000'	17,500'	17.1	Q-125	LTC	New

Casing Strengths:				Collapse	Burst	Tensile (minimum)
13-3/8"	54.5 lb.	K-55	STC	1,130 psi	2,730 psi	547,000 lb.
9-5/8"	47 lb.	HCP-110	LTC	7,100 psi	9,440 psi	1,213,000 lb.
7"	29 lb.*	HCP-110	LTC	9,200 psi	11,220 psi	797,000 lb.
4-1/2"	15.1 lb.	P-110	LTC	14,350 psi***	14,420 psi	406,000 lb.
4-1/2"	15.1 lb.	Q-125	LTC	15,840 psi***	16,380 psi	438,000 lb.
4-1/2"	17.1 lb.	Q-125	LTC	19,010 psi	18,180 psi	493,000 lb.

\* Special Drift

\*\* Flush Jnt – VAM SLIJ II or LT&C based on availability

**MINIMUM DESIGN FACTORS:**

COLLAPSE: 1.125-1.3\*\*\*

BURST: 1.10

TENSION: 1.80

DRILLING PROGRAM

Area Fracture Gradient: 0.9 psi/foot  
Maximum anticipated mud weight: 15.4 ppg  
Maximum surface treating pressure: 12,500 psi

**5. Auxiliary Equipment**

- A. Kelly Cock – yes
- B. Float at the bit – yes
- C. Monitoring equipment on the mud system – visually and/or PVT/Flow Show
- D. Full opening safety valve on the rig floor – yes
- E. Rotating Head – yes  
If drilling with air the following will be used:
  - 1. The blooie line shall be at least 6” in diameter and extend at least 100’ from the well bore into the reserve/blooie pit.
  - 2. Blooie line ignition shall be provided by a continuous pilot (ignited when drilling below 500’).
  - 3. Compressor shall be tied directly to the blooie line through a manifold.
  - 4. A mister with a continuous stream of water shall be installed near the end of the blooie lines for dust suppression.

Surface hole and the first intermediate hole section (12-1/4” hole) will be drilled with air, air/mist, foam, or mud depending on hole conditions. Drilling below the first intermediate casing will be with water based drilling fluids consisting primarily of fresh water, bentonite, lignite, caustic, lime, soda ash and polymers. No chromates will be used. It is intended to use oil base mud in the production hole. Maximum anticipated mud weight is 15.4 ppg. The high mud density is required more for hole stability and not necessarily pore pressure.

No minimum quantity of weight material will be required to be kept on location.

PVT/Flow Show will be used from base of surface casing to TD.

Gas detector will be used from surface casing depth to TD.

DRILLING PROGRAM

6. **Testing, logging and coring program**

- A. Cores – none anticipated
- B. DST – none anticipated
- C. Logging – Mud logging – 4500' to TD  
GR-SP-Induction, Neutron Density, FMI
- D. Formation and Completion Interval: Mancos interval, final determination of completion will be made by analysis of logs.  
Stimulation – Stimulation will be designed for the particular area of interest as encountered.

7. **Cementing Program**

**20" Conductor:**

Cement to surface with construction cement.

**13-3/8" Surface Casing: sfc – 500' (MD)**

**Slurry:** 0' – 500'. 610 sxs (731 cu ft) Premium cement + 0.25 lbs/sk Flocele + 2%  $\text{CaCl}_2$   
Slurry wt: 15.6 ppg, slurry yield: 1.20 ft<sup>3</sup>/sx, slurry volume: 17-1/2" hole + 100% excess.

**9-5/8" Intermediate Casing: sfc – 5,900' (MD)**

**Lead Slurry:** 0' – 5,500'. 1582 sks (2325 cu. ft) Foamed Lead 50/50 Poz cement + 0.1 % FDP-C766-05 (Low Fluid Loss Control) + 5 #/sx Silicate Compacted + 20 % SSA-1 + 0.1 % Versaset + 1.5 % Zonesealant 2000 (Foamer) Slurry wt: 14.3 ppg, (unfoamed) or 11.0 ppg. (foamed) Slurry yield: 1.47 ft<sup>3</sup>/sk (unfoamed), Slurry volume: 12-1/4" hole + 35 % excess.

**Tail Slurry:** 5,500' – 5,900'. 57 sks (15 bbls) Tail 50/50 Poz cement + 0.1 % FDP-C766-05 (Low Fluid Loss Control) + 5 #/sx Silicate Compacted + 20 % SSA-1 + 0.1 % Versaset Slurry wt: 14.3 ppg, Slurry yield: 1.47 ft<sup>3</sup>/sk, Slurry volume: 12-1/4" hole + 35% excess.

**7" Intermediate Casing: sfc - 12,750' (MD)**

**Foamed Lead Slurry 2:** sfc – 12,750'. 1271 sks (2021 cu ft) 50/50 Poz Premium + 20% SSA-1 + 3 % silicalite compacted + 3% Silicalite Compacted + 0.5% Halad 344 + 0.2% Halad 413 + 0.1% HR-12 + 0.7% Super CBL + 0.2% Suspend Slurry wt: 14.0 ppg,, Slurry yield: 1.59 ft<sup>3</sup>/sk, Slurry volume: 8-1/2" hole + 25% excess.



DRILLING PROGRAM

**4-1/2" Production Casing: sfc – 17,500' (MD)**

**Lead/Tail Slurry:** 6,500 - 17,500'. 939 sks (1399 cu ft) Premium Cement + 17.5% SSA-1, + 4% Microbond HT, + 0.2% Halad 344 + 0.5% Halad 413, + 0.3% CFR-3, + 0.9% HR-12, + 0.2% Super CBL, + 0.2% Suspend HT, 17.5% SSA-2. Slurry wt: 16.2 ppg, Slurry yield: 1.49 ft<sup>3</sup>/sk, Slurry volume: 6-1/8" hole + 35% in open hole section.

\*Final cement volumes to be calculated from caliper log with an attempt to be made to circulate cement to the surface on the intermediate string and 6,500' on the production string. A bond log will be run across the zone of interest and across zones as required by the authorized officer to insure protection of natural resources.

**8. Anticipated Abnormal Pressures and Temperatures, Other Potential Hazards**

No H<sub>2</sub>S has been encountered in or known to exist from previous wells drilled to similar depths in the general area. Maximum anticipated bottom hole pressure equals approximately 10,000 psi to 11,000 psi based on pressure transient work on the GB 9D-27-8-21. Maximum anticipated bottom hole temperature is 300° - 310° F.


**9. ADDITIONAL INFORMATION FOR OIL BASE MUD:**

A. See attached diagram of well pad layout. A reserve pit will be constructed for this location. This pit will be constructed so that a minimum of two vertical feet of freeboard exists above the top of the pit at all times and at least one-half of the holding capacity will be below ground level. The pit will be lined with a synthetic reinforced liner, 30 millimeters thick, with sufficient bedding used to cover any rocks prior to putting any fluids into the pit. The pad will be designed so that runoff from adjacent slopes does not flow into the reserve pit. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. At the beginning of drilling operations this reserve pit will have an open-ended dike placed in the pit that allows the fluids to migrate from one side of the pit to the other during the drilling of the surface and intermediate hole using water based mud. At the time that operations begin to drill the production hole with oil base mud, this dike will be extended, dividing the pit into two distinct, isolated halves allowing no migration of fluids from one side to the other. At that time all fluids will be removed from the end of the pit to be used as a cuttings pit. This cuttings pit will be used for oil based cuttings generated during drilling of the production hole.


## DRILLING PROGRAM


- B.** Oil-base mud will be mixed in the closed circulating system and transferred to four 500-bbl tanks on location for storage prior to and after drilling operations. Drip pans will be installed below the rotary beams on the substructure and can be viewed on site from the cellar area. As the production section of the hole is drilled, the cuttings transported to the surface with the drilling fluid will be mechanically separated from the drilling fluid as waste by two shale-shakers and then cleaned/dried via a mud cleaner and/or centrifuge. These separated cuttings will be collected in a steel catch tank once they leave the closed circulating system and transported and placed into the cuttings half of the reserve pit.
- C.** Plastic material will underlay the rig, oil base mud/diesel storage tanks and mud pits. All tanks on location will be placed inside of berms. Any oily waste fluids and sediments generated at the work site during drilling operations or when cleaning the fluid containment system after drilling will also be placed into the cuttings half of the pit.
- D.** All rig ditches will be lined and directed to a lined sump for fluid recovery. A drip pan will be installed on the BOP stack, a mud bucket will be utilized as needed on connections and a vacuum system will be used on the rig floor for fluid recovery in those areas.
- E.** Once all waste has been placed in the cuttings portion of the pit and all necessary approvals obtained, the oilfield waste management consultant Soli-Bond or a similar company will mobilize equipment and personnel to the site to perform the cement based solidification/stabilization process in-situ for encapsulation. Soil will be backfilled over the processed material used on the cuttings side of the pit and that portion of the pit area will be returned to the existing grade bordering the pit. Please see the attached Soli-Bond Proposal for Processing and Disposal of Drilling Waste for specific details. The half of the reserve pit containing water base materials will be left to evaporate and will be closed and reclaimed at the time that portion of the pit is dry.

## DRILLING PROGRAM




DRILLING PROGRAM





Choke Manifold (Typical)

# Attachment I. Diagrams of Choke Manifold Equipment



1-4 10M and 15M Choke Manifold Equipment -- Configuration of chokes may vary

[34 FR 39528, Sept. 27, 1989]

Last Updated March 25, 1997 by John Broderick



**Questar  
Exploration &  
Production Company**

***WV 4D-12-8-21***

***Sec 12-T8S-R21E  
Uintah County, Utah***

***Drilling Fluids Program***

***410 17<sup>th</sup> Street, Suite 460 Denver, CO 80202  
(303) 623-2205 (720) 904-7970 Fax***





## Newpark Drilling Fluids, LP

410 17<sup>th</sup> Street, Suite 460

■ Denver, Colorado 80202

■ (303) 623-2205

■ FAX (720) 904-7970

January 18, 2008

Mr. Jim Davidson  
Chief Drilling Engineer  
Questar Exploration & Production  
1331 17th Street, Suite 800  
Denver, Colorado 80202

RE: WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah Co, Utah

Mr. Davidson:

Newpark Drilling Fluids, LP is pleased to present the enclosed revised recommended drilling fluids program for the WV 4D-12-8-21 well to be drilled in Uintah County, Utah. This program is for drilling with Aerated Saltwater in the 1st intermediate to 5900 ft, a polymer fluid system in the 2nd intermediate interval to 12,750 ft, then to T.D. at 17,500 ft with OBM.

The Surface Interval will be pre-set at a depth of 500 ft.

For the 1st intermediate Interval, an aerated saltwater drilling fluid is planned.

Brine kill pills may be needed for trips, logs, and casing operations, depending on pressure encountered while drilling. Trona water flows in this area may require a mud weight of 9.5-9.8 ppg to control. Mud weight at interval T.D. at 5,900 is expected to be in the 8.8-9.0 ppg range.

In the 2nd intermediate interval, drill out with fresh water or mud-up before drilling out, as hole conditions dictate. When a mud-up is needed, mud-up to a NewPHPA/Polymer system. Mud weight in this interval is expected to be in the 11.2-11.4 ppg range at the 13,000 ft liner interval T.D.

In the Production interval, displace to a 12.0-12.5 ppg OptiDrill OBM system. Maintain fluid density as low as possible to increase penetration rates and reduce the possibility of lost circulation. Use high weight pills for well control during; trips, logs, and casing operations. Mud weight at T.D. is expected to be at +/-15.5 ppg.

The projected drilling time for this project is 65-70 days with an estimated material and engineering cost of \$500,000.00 assuming no unusual delays or problems are encountered. The estimate is based on minimal losses and a 15.0 ppg mud weight at TD. Costs will increase dramatically if severe losses are encountered.

All sack material and bulk barite will be furnished from our Grand Junction, Colorado facility, with OBM supplied from Newpark's Boulder, WY facility.

If you have any questions following your review of this proposal, please call.

Regards,

Estes Ward  
Operations Manager  
Newpark Drilling Fluids, LP

# Project Summary

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

Depth (ft)	Formations	Interval Comments	Mud Weight (ppg)	Mud Properties
500'	Uinta Surface T.D.	Hole size: 17 1/2" / Casing: 13 3/8"  AIR DRILLED	NA	NA
3,025'	Green River Mahogeny	<b>Aerated Salt Water</b> Hole size: 11.0" / Casing: 9 5/8" Flush Joint  Drill out with saltwater aerating as needed to maintain circulation. When water is encountered reduce air as needed to control the flow. Pump pre-hydrated NewGel or Flowzan /SaltGelsweeps for increased hole cleaning and for any tight hole and/or torque. For trips, spot heavy brine if needed for trona flow, and at intermediate T.D. check hole conditions and spot high viscosity mud if needed. If hole conditions dictate a mud-up, base the system on the chloride content of the fluid.	9.5-10.0	Vis (sec/qt): Water PV (cp): NA YP (#s/100ft <sup>2</sup> ): NA FL (ml/30 min): NC LGS %: < 1 % pH: 10.5-10.8 Cl (mg/l): 150-200K
5,900'	1st Intermediate T.D.	Mud weight required at T.D. is expected to be in the 8.8-9.0 ppg range	9.5-10.0	
6,425'	Wasatch Mesa Verde	<b>NewPHPA/Polymer</b> Hole size: 8.5" / Liner: 7"  Mud up as hole conditions dictate to a NewPHPA/ Polymer system. Maintain properties as outlined in-creasing the PHPA concentration to 1 ppb.	8.8	Vis (sec/qt): 40-45 PV (cp) : 12-20
10,500'	Sego	Lost circulation may be a problem in this interval. If lost circulation is encountered, pump LCM pills as needed.	10.0	YP (#s/100ft <sup>2</sup> ) : 10-12 FL (ml/30 min): 6-8
11,775'	Bucktongue	If LCM pills will not control losses, by-pass the shakers and increase the LCM concentration in the system as needed.		LGS %: 3-5
11,925'	Castlegate	If severe lost circulation is encountered, consider a DynaPlug squeeze.	11.0	pH: 10.0-10.5
12,253'	Blackhawk	Hole instability may be encountered in the Mesa Verde.	11.2	Cl (mg/l): 11-15K
12,709'	Mancos Shale	Monitor torque, pump pressure, connection fill, and trip conditions for indications of hole instability and consider adding Asphalt if hole conditions dictate.	11.2	PHPA: 1.0 ppb
12,750' +/-	2nd Intermediate T.D.			
13,133'	Mancos B	<b>OptiDrill OBM</b> Hole size: 6-1/8" / Casing: 4-1/2"  Drill out with the OptiDrill system, treating cement contamination as needed with OptiWet to prevent shaker blinding.	11.2	PV (cp): 15-25 YP (lbs/100ft <sup>2</sup> ): 8-10 HPHT (mls/30 min.): <20 O/W : 80:20 - 85:15 ES: 500+
15,839'	Frontier equiv.	Maintain hole cleaning during high ROP's with high viscosity sweeps. Use a 1:1 ratio of OptiVis RM and OptiVis.		Lime: 2-4 ppb
16,731'	Dakota Silt	CO2 in the gas stream while drilling under balanced will require additional Lime, emulsifiers and wetting agent.		LGS %: < 6
16,933'	Dakota	Maintain mud weight as needed for well control. Spot high weight ECD pills for trips, logs, and casing operations.	15.5	
17,500'	Total Depth			



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# Project Summary

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

## DRILLING FLUID PROPERTIES

### Surface Hole: Air Drilled

Hole Size (in)	TVD (ft)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	API Fluid Loss (ml/30min)	Total Solids (%)
17 1/2 "	0-500'	NA	NA	NA	NA	NA

### 1st Intermediate Hole: Aerated Saltwater

Hole Size (in)	MD (ft)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	API Fluid Loss (ml/30min)	Chloride Mg/l (x1000)	LGS Solids (%)
11"	500'-5,900'	9.5-10.0	NA	NA	NA	150-200	< 1%

### 2nd Intermediate Interval: NewPHPA/Polymer

Hole Size (in)	MD (ft)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	API Fluid Loss (ml/30min)	pH	LGS Solids (%)
8 1/2"	5,900'-8,000'	8.5-8.8	6-12	6-10	8-10	10.0-11.0	< 1%
8 1/2 "	8,000'-12,750'	11.2-11.4	12-18	12-15	6-8	10.0-11.0	3-6

### Production Interval: OptiDrill OBM

Hole Size (in)	MD (ft)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	O/W Ratio (%)	HPHT Fluid Loss (ml/30min)	CaCL (mg/l) X 10,000	Electrical Stability (mv)	LGS Solids (%)
6-1/8 "	12,750'-17,500'	15.0-15.5	20-30	8-10	85/15	12-15	250-350	500 +	3-6

- Drilling fluid properties are guidelines only.
- Mud weights for guidelines only, allow hole conditions to dictate actual mud weights.
- Hole conditions should be closely monitored and product mix adjusted accordingly.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# 1st Intermediate Interval

## 11" Hole (500' - 5,900')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

1st Intermediate Interval Drilling Fluid Properties									
Depth Interval (TVD)	Mud Weight (ppg)	Viscosity (sec/qt)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	pH	API Fluid Loss (ml/30min)	Hardness Mg/l)	Low Gravity Solids	Chlorides Mg/l (x1000)
500'-5,900'+/-	9.5-10.0	NA	NA	NA	8.0-10.0	NA	NA	<1.0	150-200

- Drill out with Saltwater maintaining chlorides as needed for fluid weight. Aerate the fluid as needed to maintain circulation.
- If a water flow is encountered, balance air and fluid weight as needed to maintain circulation
- Pump pre-hydrated NewGel and/or Flowzan/SaltGel sweeps for increased hole cleaning, along with LCM sweeps for seepage (Paper LCM while drilling with water)
- If water flows are encountered, spot heavy brine pills for trips, logs and casing operations.
- If hole conditions dictate a mud-up, system used will depend on chloride concentration of the fluid.
- Offset information indicates the 1st major loss zone to be at +/- 3600 ft.
- Shallow gas/overpressure was encountered on some offsets in the area at 3,700-4,000'. A 9.5-9.9 ppg fluid was needed to control pressure.

Challenges:	Strategies:
Gravel/Unconsolidated formation	If encountered, pump sweeps of pre-hydrated NewGel with a viscosity of 150 -300 sec/qt.
Water Flows (Trona)	If water flows become excessive, control hydrostatic as needed with air additions and fluid density.
Lost Circulation	While drilling with water, pump LCM sweeps consisting of paper. If drilling with mud, pump mixed LCM pills in the 20-30% LCM range.
Hole Cleaning	Pump sweeps on a regular basis and for any indications of insufficient hole cleaning. Circulate and pump sweeps before connections and for any anticipated down time.
Increase ROP with PDC Bits	Pump 20-40 bbl. Sweeps with NewEase 203, New100N, DynaDet, and SAPP. (FlexDrill Sweeps)
Hole Instability/Sloughing Shale	Consider a mud-up and Asphalt additions.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# 1st Intermediate Interval

## 11" Hole (500' - 5,900')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

---

---

### Offset Data:

- Wells in this area have encountered major losses at +/- 3600 ft.
- Gravel/unconsolidated formation has been encountered at 1380 ft.
- Gas/overpressure has been encountered at 3,700'-4,000'.

### Fluid Recommendations:

- Drill out cement, float collar and new formation. Test the integrity of the casing seat and squeeze if necessary.
- Drill out with Saltwater, aerating as needed to maintain circulation.
- If water is encountered, control flow with reduced air and fluid density.
- If a Trona Water flow is encountered additions of **Lime** and/or **Calcium Chloride** should be used to adjust alkalinities as needed.
- The use of a premix tank is highly recommended. Pre-Hydrate **NewGel** for use as sweeps and for viscosity when a mud up is needed. Fill premix tank with fresh water. Treat out hardness with **SodaAsh** as needed. Add 0.25-0.5 ppb **Caustic Soda** for a 10.0-10.5 pH. Begin additions of 20-25 ppb **NewGel** allow sufficient circulating time for maximum hydration. Add 1.0-2.0 ppb **CFL II**. Then mix additional **NewGel** (30-40 ppb total) or a 120+ funnel viscosity. The pre-hydrated bentonite can be pumped from the premix to the pill tank and pumped downhole for sweeps or can be added slowly to the **Saltwater** for viscosity and rheology control.
- If penetration rates slow sweeps with **New 100N**, **NewEase 203**, **SAPP**, and **DynaDet** should be considered. (1% **New 100N**, 1% **NewEase 203**, 0.5-0.75 ppb **SAPP**, 0.2 % **DynaDet**). "**Flex Sweeps**"
- For trips, an increase in mud weight may be necessary to kill water flows. 9.8-10.0 ppg brine should be considered for this operation.
- Seepage and/or lost circulation may become a problem. For seepage while drilling with water, pump 20-30 bbl pills containing Paper LCM.
- If losses become severe, consider a mud up and LCM sweeps of **Cedar Fiber** and **FiberSeal** should be pumped and incorporated into the system as needed. If losses continue, increase coarse LCM in active system to 15-20%. If losses continue the use of a **DynaPlug** Squeeze is strongly recommended.
- At TD increase funnel viscosity for logs and casing operations as hole conditions dictate. Suggest funnel viscosity be increased to 45-50 sec/qt, before logging operations be attempted.
- At 5,900' ( intermediate T.D.) short trip, check hole conditions. If hole conditions dictate, add pre-hydrated **New-Gel** from the premix tank to the active system to increase funnel viscosity to 45-50 sec/qt and spot in the open hole for logs and casing operations

**DRILL STRING PACK-OFF:** Rapid penetration rate during fast drilling often deteriorates to pack-off, a situation which can lead to lost circulation and/or stuck pipe. Pack-off is typically self-induced by exceeding the maximum rate of penetration for a given annular flow rate. The solution to this is to control the penetration rate to a level that the pumps can adequately clean the hole while maintaining rheological properties in line with existing hydraulic parameters.

**SOLIDS CONTROL:** It is of the utmost importance that the shale shakers and flow line cleaners be equipped with the finest screens possible, and yet handle the flow rate. The desander and desilter units should be evaluated periodically and serviced to maximize performance.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

## 2nd Intermediate Interval

### 8 1/2" Hole (5,900' - 12,750')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

2nd Intermediate Interval Drilling Fluid Properties								
Depth Interval (TVD)	Mud Weight (ppg)	Viscosity (sec/qt)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	pH	API Fluid Loss (ml/30min)	Hardness Mg/l)	Low Gravity Solids
5,900'-8,000'	8.6-8.8	32-36	6-12	6-10	10.0-11.0	8-10	100+	4-6
8,000'-12,750'	11.2-11.4	45-50	10-18	12-14	10.0-11.0	6-8	100+	4-6

- Drill out with water and or mud as hole conditions dictate. After mud-up , allow the system to revert to a fresh water polymer system.
- As mud weight is increased, seepage losses can become severe. Treat with LCM pills as needed. If pill treatments will not contain the losses at reasonable levels, by-pass the shakers, retaining the pills and allowing the LCM concentration to increase as needed.
- Hole instability can occur in the Mesa Verde in this area. If encountered, consider adding Asphalt, building to a 4-6 ppb concentration.
- High pressure may be encountered in the Castlegate/Blackhawk. Monitor closely for increased pressure while drilling and use caution on trips to minimize possible swabbing.
- Mud weight at Liner Interval T.D. is expected to be in the 11.2-11.4 ppg range.

<i>Challenges:</i>	<i>Strategies:</i>
Hole Instability/Sloughing Shale	Consider 4-6 ppb Asphalt
Increase in Formation pressure	Monitor well conditions and increase density as needed with <b>NewBar</b> as needed.
Seepage/Lost Circulation	As mud weight is increased (10.0ppg +) seepage and losses may become a problem. For seepage pump 50 bbl sweeps with 5-10 ppb <b>DynaFiber</b> and 10-20 ppb <b>NewCarb</b> as needed. For partial or total losses pump sweeps with 10-15 ppb <b>FiberSeal</b> and <b>Cedar Fiber</b> . Severity of losses will determine size and quantity of LCM added. If losses are not controlled with sweeps consider 10-15% LCM in active system. For severe losses the use of a <b>DynaPlug</b> squeeze should be considered.
Differential Sticking	Maintain mud weight as low as possible. Control Low Gravity Solids below 6%, and control fluid loss at 8-10 mls/30 min.
Increase ROP with PDC Bits	Pump 20-40 bbl. Sweeps with NewEase 203, New100N, DynaDet, and SAPP. (FlexDrill Sweeps)



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970



## 2nd Intermediate Interval

### 8 1/2" Hole (5,900'-12,750')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

---

---

### Offset Data:

Wells in this area have experienced losses as mud weights are increased to control formation pressure. LCM sweeps are strongly recommended for this reason. Mud weights should be kept as low as practical but increase to 11.2 ppg may be required by Liner TD at 12,750'.

- Loss zones on offset wells were at 9200 ft and 9500 ft.

### Fluid Recommendations:

- Drill out cement, float collar and new formation with the system from the previous interval. Test the integrity of the casing seat and squeeze if necessary.
- Drill out with water and or mud. If drilling out with water consider a mud up by +/- 7500 ft or as hole conditions dictate.
- Begin additions of 0.5-1.0 ppb **NewPHPA** and maintain throughout the interval.
- Maintain viscosity with PreHydrated **NewGel** until chlorides have dropped below 5000-7000 mg/l. After chlorides have dropped **NewGel** will not need to be pre-hydrated and can be added directly to the system.
- Begin additions of **NewPHPA**. Concentration of **NewPHPA** should be maintained at 0.5-1.0 ppb throughout the interval. As mud weight increases additions of **PHPA** should be switched from **NewPHPA DLMW** to the shorter chain **NewPHPA DSL**.
- If hole conditions dictate, consider 4-6 ppb Asphalt.
- If penetration rates slow sweeps with **New 100N**, **NewEase 203**, **SAPP**, and **DynaDet** should be considered. (1% **New 100N**, 1% **NewEase 203**, 0.5-0.75 ppb **SAPP**, 0.2 % **DynaDet**). "**Flex Sweeps**"
- Increase mud weight as needed to control formation pressures as needed. Mud weights should be maintained as low as practical to reduce chance of losses and differential sticking. Increase mud weight as needed with **NewBar**.
- As density increases additions of **NewEdge** and/or **DrillThin** should be added for rheology control.
- As bottom hole temperatures increase and additional fluid loss control is desired supplement the **NewPAC** with **DynaPlex** for fluid loss control. Lower API filtrate to 6-8 cc's with additions of **NewPAC** and **DynaPlex**.
- As mud weight is increased seepage and/or lost circulation may become a problem. For seepage pump 20-30 bbl pills containing a combination of **NewCarb** and **DynaFiber** mixed at a 2:1 ratio. If partial or total returns are encountered, LCM sweeps with a varied size distribution including **Cedar Fiber** and **Fiber Seal**, **PhenoSeal** and other assorted sizes should be considered and incorporated into the system as needed. 20-25% LCM in the active system may be required. The type, size and quantity of LCM used will depend on the severity of losses. If losses are severe a **DynaPlug** squeeze should be considered.
- At TD increase funnel viscosity for logs and casing operations as hole conditions dictate. Suggest funnel viscosity be increased to 50-55 sec/qt, before logging or casing operations be attempted.
- While circulating casing it is recommended to reduce Yield Points for cementing operations.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# Production Interval

## 6 1/8" Hole (12,750'-17,500')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

### Production Interval Drilling Fluid Properties

Depth Interval (TVD)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	O/W Ratio %	HTHP Fluid Loss (ml/30min)	Excess Lime (PPB)	Electrical Stability (MV)	Low Gravity Solids	CaCl Mg/l Water
12,750'-17,725'	15.0-15.5	25-35	8-10	85:15	12-15	2-4	500+	< 6	300K

### Drilling Fluid Recommendations: (12,750'-17,500')

- Displace to a OptiDrill OBM after finishing the liner job at 12,750'.
- After displacement, maintain the OptiDrill system within the parameters outlined above.
- Offsets in the area have encountered high rates of seepage in this interval. If indications of seepage are observed, sweeps of **NewCarb C**, **Dynafiber C & M**, **NewSeal**, and **CyberSeal** are recommended. Mixing ratios are recommended to be at 5:1 **NewCarb M** to **DynaFiber**, **NewSeal**, and **CyberSeal**. If losses continue to be a problem, consider trying different sizes and combinations until seepage is slowed.
- Maintain rheology low to reduce ECD values and reduce surge and swab during connections and trips.
- Drill as underbalanced as possible to help prevent losses and increase penetration rates.
- For pressure control, spot high weight pills with an equivalent mud weight to drilling ECD's. On trips in, stage these pills out and divert to storage for further use. High weight pills in excess of the drilling ECD should be avoided due to possible lost circulation.

Challenges	Strategies
Displacement	<ul style="list-style-type: none"> <li>• Have 1200-1300 bbls of OBM volume on location along with a pump capable of keeping up with displacement rates.</li> <li>• Pump a 10-20 bbl viscosified OBM spacer ahead of the OptiDrill (enough for 500 ft + separation)</li> <li>• A steady pump rate for either turbulent or plug flow should be used. Reciprocate and rotate to assist in minimizing channeling.</li> <li>• Do not shut down once displacement commences.</li> <li>• Should any contamination occur, isolate the contaminated fluid for reconditioning.</li> </ul>
Seepage/lost Circulation.	Pump LCM sweeps when seepage and/or losses are indicated. Sweeps should be a mixture of , NewCarb, DynaFiber, NewSeal, and CyberSeal. If lost returns are encountered, consider a Di-aseal M or cross linked polymer squeeze.
Maintaining Oil wet solids	For every 1.0 ppg mud weight increase, mix 0.02 gal/bbl OptiWet
Pressure control	<ul style="list-style-type: none"> <li>• Spot weighted pills calculated to give a bottom hole pressure equal to drilling ECD.</li> <li>• Do not exceed drilling bottom hole pressure with the ECD pill. Lost circulation has been a problem on offset wells.</li> <li>• Stage weighted pills out of the hole and recover for future use.</li> </ul>



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# Production Interval

## 6 1/8" Hole (12,750'-17,500')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

---

---

### Maintenance Procedure:

**HPHT** - Maintain HPHT values within programmed parameters. Additions of **OptiMul** and **OptiPlus**, at recommended concentrations should maintain the HTHP at recommended levels. If hole conditions indicate a need for lower HPHT values, **Opti G** at 2-4 ppb is recommended.

**Electrical Stability**— Electrical stability should be used as a guide not as an absolute in determining maintenance requirements. Actual values are not critical but should be observed for trends or changes. Decreases in electrical stability should be noted along with other mud properties to determine treatments. To increase electrical stability add emulsifiers and wetting agents **OptiMul** and **OptiPlus** or decrease water content.

**Oil/Water Ratio** - Maintain the oil/water ratio in the 90:10-80:20 range depending on mud weight and condition.. Higher water content will decrease the amount of **OptiVis** needed for rheology.

**Mud weight** - Maintain minimum fluid densities with solids equipment. Monitor hole conditions and all drilling parameters closely for indications of increases in formation pressures and adjust fluid densities accordingly. Drilling with a minimum amount of overbalance will reduce the possibility of losing returns and/or of differentially sticking the drill string. Mud weight on offset wells was in the 15.0-15.5 ppg range at T.D.

**Rheology** - Maintain solids as low as possible. Increase rheology as needed for hole cleaning with a combination of **OptiVis (Bentone 910)** and **Opti Vis RM or Opti Vis PS** and water content.

**Lime** - Maintain the excess Lime at 2-3 ppb excess.

**Hole cleaning** - Calculate rheology requirements based on ROP, pump rates and hole conditions. Adjust as needed .

**Mud losses downhole**—Monitor ECD's with Hy-Calc, maintaining the lowest values possible. If losses are encountered; sweeps containing **NewCarb, DynaFiber, Opti-G, and NewSeal** should be circulated to aid in the prevention of losses. If seepage losses continue and/or become severe, consider spotting a pill with **Magma Fiber (Fine & Regular)** and the above formulation. Keep the hole full at all times, and avoid excessive swabbing and/or surge actions when tripping.

**Solids Control** - Maintain low gravity solids at 4-6 % by volume. The high performance shakers should be equipped with the finest mesh screens that will handle the circulating volume and not cut barite out.

**Water Contamination**— Keep all water sources off the mud pits. If contamination occurs, treat with emulsifiers and Calcium Chloride as needed.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# Production Interval

6 1/8" Hole (12,750'-17,500')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah


**Recommended materials for relaxed filtrate OptiDrill system :**  
**( 85:15 Oil/Water Ratio)**

Product	Function	Concentration
<b>NewBar</b>	Weighting material	As needed
<b>OptiVis</b>	Organophilic Clay / Viscosifier	2-4 ppb
<b>OptiMul</b>	Primary Emulsifier	2.0 ppb
<b>OptiPlus</b>	Secondary Emulsifier	4.0 gal/bbl.
<b>OptiVis RM</b>	Low End Rheology Modifier	0.1-0.2 ppb
<b>Calcium Chloride Water</b>	Internal Phase	10.0%-20.0 % by volume
<b>Calcium Chloride</b>	Salinity/Activity	300,000 - 350,000 mg/l
<b>OptiG</b>	Fluid Loss control Additive	1.0-4.0 ppb
<b>Lime</b>	Alkalinity Additive	5 ppb
<b>NewCarb M</b>	Loss Circulation Material	10.0 ppb
<b>NewCarb F</b>	Loss Circulation Material	As required
<b>DynaFiber</b>	Loss Circulation Material	As required



**Newpark Drilling Fluids, LP**  
410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# WV 4D-12-8-21



## NOTICE

Utah Oil and Gas Conservation General Rule R649-3-21 states that,

- A well is considered completed when the well has been adequately worked to be capable of producing oil or gas or when well testing as required by the division is concluded.
- Within 30 days after the completion or plugging of a well, the following shall be filed:
  - Form 8, Well Completion or Recompletion Report and Log
  - A copy of electric and radioactivity logs, if run
  - A copy of drillstem test reports,
  - A copy of formation water analyses, porosity, permeability or fluid saturation determinations
  - A copy of core analyses, and lithologic logs or sample descriptions if compiled
  - A copy of directional, deviation, and/or measurement-while-drilling survey for each horizontal well

Failure to submit reports in a timely manner will result in the issuance of a Notice of Violation by the Division of Oil, Gas and Mining, and may result in the Division pursuing enforcement action as outlined in Rule R649-10, Administrative Procedures, and Section 40-6-11 of the Utah Code.

---

As of the mailing of this notice, the division has not received the required reports for

Operator: Questar Exploration & Production Co Today's Date: 02/14/2008

Well: API Number: Drilling Commenced:

See Attachment

43 047 3A268  
WV 4D-12-8-21  
8S 21E 12

To avoid compliance action, required reports should be mailed within 7 business days to:

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

If you have questions or concerns regarding this matter, please call (801) 538-5284.

cc: Well File  
Compliance File



Well:		API Number:	Commenced:
WV 5W-36-7-21	drlg rpts/wcr	4304734099	05/29/2003
WV 4D-12-8-12	drlg rpts/wcr	4304734268	09/26/2003
WVX 11D-22-8-21	drlg rpts/wcr	4304734902	03/15/2005
WV 3DML-13-8-21	drlg rpts/wcr	4304737923	09/27/2006
FR 7P-36-14-19	drlg rpts/wcr	4304738992	02/05/2007
SU 8M-12-7-21	drlg rpts/wcr	4304736096	03/18/2007
WV 12AD-8-8-22R	drlg rpts/wcr	4304739321	05/10/2007
WRU EIH 7AD-35-8-22	drlg rpts/wcr	4304738641	06/08/2007
RWS 14D-6-9-24	drlg rpts/wcr	4304737414	07/20/2007
RW 34-27ADR	drlg rpts/wcr	4304739445	08/07/2007
NBZ 8D-31-8-24	drlg rpts/wcr	4304737238	08/27/2007
WRU EIH 6D-5-8-23	drlg rpts/wcr	4304738994	09/04/2007
WRU EIH 9CD-26-8-22	drlg rpts/wcr	4304738649	10/03/2007

Form 3160-5  
(November 1994)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**SUNDRY NOTICES AND REPORTS ON WELLS**

*Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.*

FORM APPROVED  
OMB No. 1004-0135  
Expires July 31, 1996

5. Lease Serial No.

UTU-0806

6. If Indian, Allottee or Tribe Name

UTE INDIAN TRIBE

7. If Unit or CA/Agreement, Name and/or No.

WONSITS VALLEY UNIT

8. Well Name and No.

WV 4D-12-8-21

9. API Well No.

43-047-34268

10. Field and Pool, or Exploratory Area

WONSITS VALLEY

11. County or Parish, State

UINTAH

**SUBMIT IN TRIPLICATE - Other Instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

QUESTAR EXPLORATION & PRODUCTION, CO.

Contact: Jan Nelson

3a. Address

11002 E. 17500 S. VERNAL, UT 84078

3b. Phone No. (include area code)

435-781-4331

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

356' FNL 475' FWL, NWNW, SECTION 12, T8S, R21E

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

**TYPE OF SUBMISSION**

**TYPE OF ACTION**

☒ Notice of Intent

☐ Subsequent Report

☐ Final Abandonment Notice

☐ Acidize

☐ Alter Casing

☐ Casing Repair

☒ Change Plans

☐ Convert to Injection

Deepen

☐ Fracture Treat

☐ New Construction

☐ Plug and Abandon

☐ Plug Back

☐ Production (Start/Resume)

☐ Reclamation

☐ Recomplete

☐ Temporary Abandon

☐ Water Disposal

☐ Water Shut-Off

☐ Well Integrity

☒ Other **TD CHANGE**

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

QUESTAR EXPLORATION AND PRODUCTION COMPANY (QEP) REQUEST PERMISSION TO CHANGE THE TD FROM THE ORIGINALLY APPROVED 7,940 TO TEST THE WASATCH TO 17,500' TO TEST THE DAKOTA.

ATTACHED IS A REVISED DRILLING PLAN. CEMENT, BOP DIAGRAM, DRILLING FLUIDS PROGRAM AND WELLBORE DIAGRAM.

FOR TECHNICAL QUESTIONS, PLEASE CONTACT JIM DAVIDSON, CHIEF DRILLING ENGINEER FOR OPERAT  
(303) 308-3090.

COPY SENT TO OPERATOR

Date: 2-21-2008

Initials: KS

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

Laura Bills

Signature

*Laura Bills*

Title

Regulatory Affairs

Date

February 14, 2008

**THIS SPACE FOR FEDERAL OR STATE USE**

Approved by

*[Signature]*

Title

BRADLEY G. HILL  
Office  
ENVIRONMENTAL MANAGER

Date


02-19-08

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

**Federal Approval of this  
Action is Necessary**



**CONFIDENTIAL**

ONSHORE OIL & GAS ORDER NO. 1  
QUESTAR EXPLORATION & PRODUCTION COMPANY  
WV 4D-12-8-21

DRILLING PROGRAM

ONSHORE OIL & GAS ORDER NO. 1  
Approval of Operations on Onshore  
Federal Oil and Gas Leases

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas No. 1, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

1. **Formation Tops**

The estimated tops of important geologic markers are as follows:

<u>Formation</u>	<u>Depth</u>
Uinta	Surface
Green River	3,025'
Wasatch	6,425'
Mesaverde	9,325'
Sego	11,775'
Castlegate	11,925'
Blackhawk	12,253'
Mancos Shale	12,709'
Mancos B	13,133'
Frontier	15,839'
Dakota Silt	16,731'
Dakota	16,933'
TD	17,500'

2. **Anticipated Depths of Oil Gas Water and Other Mineral Bearing Zones**

The estimated depths at which the top and bottom of the anticipated water, oil, gas. Or other mineral bearing formations are expected to be encountered are as follows:

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
Gas	Wasatch	6,425'
Gas	Mesaverde	9,325'
Gas	Blackhawk	12,253'
Gas	Mancos Shale	12,709'
Gas	Mancos B	13,133'
Gas	Dakota	16,933'

All fresh water and prospectively valuable minerals encountered during drilling will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

DRILLING PROGRAM

All water shows and water-bearing sands will be reported to the BLM in Vernal, Utah. Copies of State of Utah form OGC-8-X are acceptable. If flows are detected, samples will be submitted to the BLM along with any water analyses conducted. Fresh water will be obtained from Wonsits Valley water right # A36125 (which was filed on May 7, 1964,) or Red Wash water right # 49-2153 (which was filed on March 25, 1960). It was determined by the Fish and Wildlife Service that any water right number filed before 1989 is not depleting to the Upper Colorado River System, to supply fresh water for drilling purposes. All water resulting from drilling operations will be disposed of at Red Wash Central Battery Disposal Site; SWSE, Section 27, T7S, R23E or Wonsits Valley Disposal Site; SWNW, Section 12, T8S, R21E.

**3. Operator's Specification for Pressure Control Equipment:**

- A. 13-5/8" 2000 psi annular BOP (schematic included) from surface casing seat to 9-5/8" casing point.
- B. 11" or 13-5/8" 10,000 psi double gate, 10,000 psi single gate, 10,000 psi annular BOP (schematic included) from 9-5/8" casing point to total depth. The choice of BOP stacks is based on the drilling contractor's availability.
- C. Functional test daily
- D. All casing strings shall be pressure tested (0.2 psi/foot or 1500 psi, whichever is greater) prior to drilling the plug after cementing; test pressure shall not exceed the internal yield pressure of the casing.
- E. Ram type preventers and associated equipment shall be tested to approved stack working pressure if isolated by test plug or to 50 percent of internal yield pressure of casing whichever is less. BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc..., for a 10M system and individual components shall be operable as designed.

DRILLING PROGRAM

4. **Casing Design:**

Hole Size	Csg. Size	Top (MD)	Bottom (MD)	Wt.	Grade	Thread	Cond.
26"	20"	sfc	40-60'	Steel	Cond.	None	Used
17-1/2"	13-3/8	sfc	500'	54.5	K-55	STC	New
12-1/4"	9-5/8"	sfc	6300'	47	HCP-110	Flush Jnt **	New
8-1/2"	7"	sfc	9,000'	26 SDrift	HCP-110	LTC	New
8-1/2"	7"	9000'	12,750'	29* SDrift	HCP-110	LTC	New
6-1/8"	4-1/2"	sfc	13,000'	15.1	P-110	LTC	New
6-1/8"	4-1/2"	13,000'	15,000'	15.1	Q-125	LTC	New
6-1/8"	4-1/2"	15,000'	17,500'	17.1	Q-125	LTC	New

Casing Strengths:				Collapse	Burst	Tensile (minimum)
13-3/8"	54.5 lb.	K-55	STC	1,130 psi	2,730 psi	547,000 lb.
9-5/8"	47 lb.	HCP-110	LTC	7,100 psi	9,440 psi	1,213,000 lb.
7"	29 lb.*	HCP-110	LTC	9,200 psi	11,220 psi	797,000 lb.
4-1/2"	15.1 lb.	P-110	LTC	14,350 psi***	14,420 psi	406,000 lb.
4-1/2"	15.1 lb.	Q-125	LTC	15,840 psi***	16,380 psi	438,000 lb.
4-1/2"	17.1 lb.	Q-125	LTC	19,010 psi	18,180 psi	493,000 lb.

\* Special Drift

\*\* Flush Jnt – VAM SLIJ II or LT&C based on availability

**MINIMUM DESIGN FACTORS:**

COLLAPSE: 1.125-1.3\*\*\*

BURST: 1.10

TENSION: 1.80

DRILLING PROGRAM

Area Fracture Gradient: 0.9 psi/foot  
Maximum anticipated mud weight: 15.4 ppg  
Maximum surface treating pressure: 12,500 psi

**5. Auxiliary Equipment**

- A. Kelly Cock – yes
- B. Float at the bit – yes
- C. Monitoring equipment on the mud system – visually and/or PVT/Flow Show
- D. Full opening safety valve on the rig floor – yes
- E. Rotating Head – yes  
If drilling with air the following will be used:
  - 1. The blooie line shall be at least 6” in diameter and extend at least 100’ from the well bore into the reserve/blooie pit.
  - 2. Blooie line ignition shall be provided by a continuous pilot (ignited when drilling below 500’).
  - 3. Compressor shall be tied directly to the blooie line through a manifold.
  - 4. A mister with a continuous stream of water shall be installed near the end of the blooie lines for dust suppression.

Surface hole and the first intermediate hole section (12-1/4” hole) will be drilled with air, air/mist, foam, or mud depending on hole conditions. Drilling below the first intermediate casing will be with water based drilling fluids consisting primarily of fresh water, bentonite, lignite, caustic, lime, soda ash and polymers. No chromates will be used. It is intended to use oil base mud in the production hole. Maximum anticipated mud weight is 15.4 ppg. The high mud density is required more for hole stability and not necessarily pore pressure.

No minimum quantity of weight material will be required to be kept on location.

PVT/Flow Show will be used from base of surface casing to TD.

Gas detector will be used from surface casing depth to TD.



DRILLING PROGRAM

**6. Testing, logging and coring program**

- A. Cores – none anticipated
- B. DST – none anticipated
- C. Logging – Mud logging – 4500' to TD  
GR-SP-Induction, Neutron Density, FMI
- D. Formation and Completion Interval: Mancos interval, final determination of completion will be made by analysis of logs.  
Stimulation – Stimulation will be designed for the particular area of interest as encountered.

**7. Cementing Program**

**20" Conductor:**

Cement to surface with construction cement.

**13-3/8" Surface Casing: sfc – 500' (MD)**

**Slurry:** 0' – 500'. 610 sks (731 cu ft) Premium cement + 0.25 lbs/sk Flocele + 2% CaCl<sub>2</sub>  
Slurry wt: 15.6 ppg, slurry yield: 1.20 ft<sup>3</sup>/sx, slurry volume: 17-1/2" hole + 100% excess.

**9-5/8" Intermediate Casing: sfc – 5,900' (MD)**

**Lead Slurry:** 0' – 5,500'. 1582 sks (2325 cu. ft) Foamed Lead 50/50 Poz cement + 0.1 % FDP-C766-05 (Low Fluid Loss Control) + 5 #/sx Silicate Compacted + 20 % SSA-1 + 0.1 % Versaset + 1.5 % Zonesalant 2000 (Foamer) Slurry wt: 14.3 ppg, (unfoamed) or 11.0 ppg. (foamed) Slurry yield: 1.47 ft<sup>3</sup>/sk (unfoamed), Slurry volume: 12-1/4" hole + 35 % excess.

**Tail Slurry:** 5,500' – 5,900'. 57 sks (15 bbls) Tail 50/50 Poz cement + 0.1 % FDP-C766-05 (Low Fluid Loss Control) + 5 #/sx Silicate Compacted + 20 % SSA-1 + 0.1 % Versaset Slurry wt: 14.3 ppg, Slurry yield: 1.47 ft<sup>3</sup>/sk, Slurry volume: 12-1/4" hole + 35% excess.

**7" Intermediate Casing: sfc - 12,750' (MD)**

**Foamed Lead Slurry 2:** sfc – 12,750'. 1271 sks (2021 cu ft) 50/50 Poz Premium + 20% SSA-1 + 3 % silicalite compacted + 3% Silicalite Compacted + 0.5% Halad 344 + 0.2% Halad 413 + 0.1% HR-12 + 0.7% Super CBL + 0.2% Suspend Slurry wt: 14.0 ppg,, Slurry yield: 1.59 ft<sup>3</sup>/sk, Slurry volume: 8-1/2" hole + 25% excess.

DRILLING PROGRAM

**4-1/2" Production Casing: sfc – 17,500' (MD)**

**Lead/Tail Slurry:** 6,500 - 17,500'. 939 sks (1399 cu ft) Premium Cement + 17.5% SSA-1, + 4% Microbond HT, + 0.2% Halad 344 + 0.5% Halad 413, + 0.3% CFR-3, + 0.9% HR-12, + 0.2% Super CBL, + 0.2% Suspend HT, 17.5% SSA-2. Slurry wt: 16.2 ppg, Slurry yield: 1.49 ft<sup>3</sup>/sk, Slurry volume: 6-1/8" hole + 35% in open hole section.

\*Final cement volumes to be calculated from caliper log with an attempt to be made to circulate cement to the surface on the intermediate string and 6,500' on the production string. A bond log will be run across the zone of interest and across zones as required by the authorized officer to insure protection of natural resources.

**8. Anticipated Abnormal Pressures and Temperatures, Other Potential Hazards**

No H<sub>2</sub>S has been encountered in or known to exist from previous wells drilled to similar depths in the general area. Maximum anticipated bottom hole pressure equals approximately 10,000 psi to 11,000 psi based on pressure transient work on the GB 9D-27-8-21. Maximum anticipated bottom hole temperature is 300° - 310° F.

**9. ADDITIONAL INFORMATION FOR OIL BASE MUD:**


A. See attached diagram of well pad layout. A reserve pit will be constructed for this location. This pit will be constructed so that a minimum of two vertical feet of freeboard exists above the top of the pit at all times and at least one-half of the holding capacity will be below ground level. The pit will be lined with a synthetic reinforced liner, 30 millimeters thick, with sufficient bedding used to cover any rocks prior to putting any fluids into the pit. The pad will be designed so that runoff from adjacent slopes does not flow into the reserve pit. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. At the beginning of drilling operations this reserve pit will have an open-ended dike placed in the pit that allows the fluids to migrate from one side of the pit to the other during the drilling of the surface and intermediate hole using water based mud. At the time that operations begin to drill the production hole with oil base mud, this dike will be extended, dividing the pit into two distinct, isolated halves allowing no migration of fluids from one side to the other. At that time all fluids will be removed from the end of the pit to be used as a cuttings pit. This cuttings pit will be used for oil based cuttings generated during drilling of the production hole.

**DRILLING PROGRAM**

- B.** Oil-base mud will be mixed in the closed circulating system and transferred to four 500-bbl tanks on location for storage prior to and after drilling operations. Drip pans will be installed below the rotary beams on the substructure and can be viewed on site from the cellar area. As the production section of the hole is drilled, the cuttings transported to the surface with the drilling fluid will be mechanically separated from the drilling fluid as waste by two shale-shakers and then cleaned/dried via a mud cleaner and/or centrifuge. These separated cuttings will be collected in a steel catch tank once they leave the closed circulating system and transported and placed into the cuttings half of the reserve pit.
- C.** Plastic material will underlay the rig, oil base mud/diesel storage tanks and mud pits. All tanks on location will be placed inside of berms. Any oily waste fluids and sediments generated at the work site during drilling operations or when cleaning the fluid containment system after drilling will also be placed into the cuttings half of the pit.
- D.** All rig ditches will be lined and directed to a lined sump for fluid recovery. A drip pan will be installed on the BOP stack, a mud bucket will be utilized as needed on connections and a vacuum system will be used on the rig floor for fluid recovery in those areas.
- E.** Once all waste has been placed in the cuttings portion of the pit and all necessary approvals obtained, the oilfield waste management consultant Soli-Bond or a similar company will mobilize equipment and personnel to the site to perform the cement based solidification/stabilization process in-situ for encapsulation. Soil will be backfilled over the processed material used on the cuttings side of the pit and that portion of the pit area will be returned to the existing grade bordering the pit. Please see the attached Soli-Bond Proposal for Processing and Disposal of Drilling Waste for specific details. The half of the reserve pit containing water base materials will be left to evaporate and will be closed and reclaimed at the time that portion of the pit is dry.


ONSHORE OIL & GAS ORDER NO. 1  
QUESTAR EXPLORATION & PRODUCTION COMPANY  
WV 4D-12-8-21


## DRILLING PROGRAM




ONSHORE OIL & GAS ORDER NO. 1  
QUESTAR EXPLORATION & PRODUCTION COMPANY  
WV 4D-12-8-21

## DRILLING PROGRAM





# Attachment I Diagrams of Choke Manifold Equipment



1-4 10M and 15M Choke Manifold Equipment -- Configuration of chokes may vary

[34 FR 39528, Sept. 27, 1969]

Last Updated March 25, 1997 by John Broderick





**Questar  
Exploration &  
Production Company**

***WV 4D-12-8-21***

***Sec 12-T8S-R21E  
Uintah County, Utah***

***Drilling Fluids Program***

***410 17<sup>th</sup> Street, Suite 460 Denver, CO 80202  
(303) 623-2205 (720) 904-7970 Fax***



## Newpark Drilling Fluids, LP

410 17<sup>th</sup> Street, Suite 460

■ Denver, Colorado 80202

■ (303) 623-2205

■ FAX (720) 904-7970

January 18, 2008

Mr. Jim Davidson  
Chief Drilling Engineer  
Questar Exploration & Production  
1331 17th Street, Suite 800  
Denver, Colorado 80202

RE: WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah Co, Utah

Mr. Davidson:

Newpark Drilling Fluids, LP is pleased to present the enclosed revised recommended drilling fluids program for the WV 4D-12-8-21 well to be drilled in Uintah County, Utah. This program is for drilling with Aerated Saltwater in the 1st intermediate to 5900 ft, a polymer fluid system in the 2nd intermediate interval to 12,750 ft, then to T.D. at 17,500 ft with OBM.

The Surface Interval will be pre-set at a depth of 500 ft.

For the 1st intermediate Interval, an aerated saltwater drilling fluid is planned.

Brine kill pills may be needed for trips, logs, and casing operations, depending on pressure encountered while drilling. Trona water flows in this area may require a mud weight of 9.5-9.8 ppg to control. Mud weight at interval T.D. at 5,900 is expected to be in the 8.8-9.0 ppg range.

In the 2nd intermediate interval, drill out with fresh water or mud-up before drilling out, as hole conditions dictate. When a mud-up is needed, mud-up to a NewPHPA/Polymer system. Mud weight in this interval is expected to be in the 11.2-11.4 ppg range at the 13,000 ft liner interval T.D.

In the Production interval, displace to a 12.0-12.5 ppg OptiDrill OBM system. Maintain fluid density as low as possible to increase penetration rates and reduce the possibility of lost circulation. Use high weight pills for well control during; trips, logs, and casing operations. Mud weight at T.D. is expected to be at +/-15.5 ppg.

The projected drilling time for this project is 65-70 days with an estimated material and engineering cost of \$500,000.00 assuming no unusual delays or problems are encountered. The estimate is based on minimal losses and a 15.0 ppg mud weight at TD. Costs will increase dramatically if severe losses are encountered.

All sack material and bulk barite will be furnished from our Grand Junction, Colorado facility, with OBM supplied from Newpark's Boulder, WY facility.

If you have any questions following your review of this proposal, please call.

Regards,

Estes Ward  
Operations Manager  
Newpark Drilling Fluids, LP

# Project Summary

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

Depth (ft)	Formations	Interval Comments	Mud Weight (ppg)	Mud Properties
500'	Uinta Surface T.D.	Hole size: 17 1/2" / Casing: 13 3/8"  AIR DRILLED	NA	NA
3,025'  5,900'	Green River Mahogeny  1st Intermediate T.D.	<b>Aerated Salt Water</b> Hole size: 11.0" / Casing: 9 5/8" Flush Joint  Drill out with saltwater aerating as needed to maintain circulation. When water is encountered reduce air as needed to control the flow. Pump pre-hydrated NewGel or Flowzan /SaltGelsweeps for increased hole cleaning and for any tight hole and/or torque. For trips, spot heavy brine if needed for trona flow, and at intermediate T.D. check hole conditions and spot high viscosity mud if needed. If hole conditions dictate a mud-up, base the system on the chloride content of the fluid.  Mud weight required at T.D. is expected to be in the 8.8-9.0 ppg range	9.5-10.0       9.5-10.0	Vis (sec/qt): Water  PV (cp): NA  YP (#s/100ft²): NA  FL (ml/30 min): NC  LGS %: < 1 %  pH: 10.5-10.8  Cl (mg/l): 150-200K
6,425' 9,325'  10,500' 11,775'  11,925' 12,253' 12,709'  12,750' +/-	Wasatch Mesa Verde  Sego Bucktongue  Castlegate Blackhawk Mancos Shale 2nd Intermediate T.D.	<b>NewPHPA/Polymer</b> Hole size: 8.5" / Liner: 7"  Mud up as hole conditions dictate to a NewPHPA/ Polymer system. Maintain properties as outlined in-creasing the PHPA concentration to 1 ppb. Lost circulation may be a problem in this interval. If lost circulation is encountered, pump LCM pills as needed. If LCM pills will not control losses, by-pass the shakers and increase the LCM concentration in the system as needed. If severe lost circulation is encountered, consider a DynaPlug squeeze. Hole instability may be encountered in the Mesa Verde. Monitor torque, pump pressure, connection fill, and trip conditions for indications of hole instability and consider adding Asphalt if hole conditions dictate.	8.8  10.0  11.0  11.2  11.2	Vis (sec/qt): 40-45  PV (cp) : 12-20  YP (#s/100ft²) : 10-12  FL (ml/30 min): 6-8  LGS %: 3-5  pH: 10.0-10.5  Cl (mg/l): 11-15K  PHPA: 1.0 ppb
13,133'  15,839' 16,731' 16,933'  17,500'	Mancos B  Frontier equiv. Dakota Silt Dakota  Total Depth	<b>OptiDrill OBM</b> Hole size: 6-1/8" / Casing: 4-1/2"  Drill out with the OptiDrill system, treating cement contamination as needed with OptiWet to prevent shaker blinding. Maintain hole cleaning during high ROP's with high viscosity sweeps. Use a 1:1 ratio of OptiVis RM and OptiVis. CO2 in the gas stream while drilling under balanced will require additional Lime, emulsifiers and wetting agent.  Maintain mud weight as needed for well control. Spot high weight ECD pills for trips, logs, and casing operations.	11.2       15.5	PV (cp): 15-25  YP (lbs/100ft²): 8-10  HPHT (mls/30 min.): <20  O/W : 80:20 - 85:15  ES: 500+  Lime: 2-4 ppb  LGS %: < 6



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 804-7870

# Project Summary

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

## DRILLING FLUID PROPERTIES

### Surface Hole: Air Drilled

Hole Size (in)	TVD (ft)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	API Fluid Loss (ml/30min)	Total Solids (%)
17 1/2 "	0-500'	NA	NA	NA	NA	NA

### 1st Intermediate Hole: Aerated Saltwater

Hole Size (in)	MD (ft)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	API Fluid Loss (ml/30min)	Chloride Mg/l (x1000)	LGS Solids (%)
11"	500'-5,900'	9.5-10.0	NA	NA	NA	150-200	< 1%

### 2nd Intermediate Interval: NewPHPA/Polymer

Hole Size (in)	MD (ft)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	API Fluid Loss (ml/30min)	pH	LGS Solids (%)
8 1/2"	5,900'-8,000'	8.5-8.8	6-12	6-10	8-10	10.0-11.0	< 1%
8 1/2 "	8,000'-12,750'	11.2-11.4	12-18	12-15	6-8	10.0-11.0	3-6

### Production Interval: OptiDrill OBM

Hole Size (in)	MD (ft)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	O/W Ratio (%)	HPHT Fluid Loss (ml/30min)	CaCL (mg/l) X 10,000	Electrical Stability (mv)	LGS Solids (%)
6-1/8 "	12,750'-17,500'	15.0-15.5	20-30	8-10	85/15	12-15	250-350	500 +	3-6

- Drilling fluid properties are guidelines only.
- Mud weights for guidelines only, allow hole conditions to dictate actual mud weights.
- Hole conditions should be closely monitored and product mix adjusted accordingly.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 804-7970

# 1st Intermediate Interval

11" Hole (500'- 5,900')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Utah, County Utah

1st Intermediate Interval Drilling Fluid Properties									
Depth Interval (TVD)	Mud Weight (ppg)	Viscosity (sec/qt)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	pH	API Fluid Loss (ml/30min)	Hardness Mg/l)	Low Gravity Solids	Chlorides Mg/l (x1000)
500'-5,900'+/-	9.5-10.0	NA	NA	NA	8.0-10.0	NA	NA	<1.0	150-200

- Drill out with Saltwater maintaining chlorides as needed for fluid weight. Aerate the fluid as needed to maintain circulation.
- If a water flow is encountered, balance air and fluid weight as needed to maintain circulation
- Pump pre-hydrated NewGel and/or Flowzan/SaltGel sweeps for increased hole cleaning, along with LCM sweeps for seepage (Paper LCM while drilling with water)
- If water flows are encountered, spot heavy brine pills for trips, logs and casing operations.
- If hole conditions dictate a mud-up, system used will depend on chloride concentration of the fluid.
- Offset information indicates the 1st major loss zone to be at +/- 3600 ft.
- Shallow gas/overpressure was encountered on some offsets in the area at 3,700-4,000'. A 9.5-9.9 ppg fluid was needed to control pressure.

Challenges:	Strategies:
Gravel/Unconsolidated formation	If encountered, pump sweeps of pre-hydrated NewGel with a viscosity of 150 -300 sec/qt.
Water Flows (Trona)	If water flows become excessive, control hydrostatic as needed with air additions and fluid density.
Lost Circulation	While drilling with water, pump LCM sweeps consisting of paper. If drilling with mud, pump mixed LCM pills in the 20-30% LCM range.
Hole Cleaning	Pump sweeps on a regular basis and for any indications of insufficient hole cleaning. Circulate and pump sweeps before connections and for any anticipated down time.
Increase ROP with PDC Bits	Pump 20-40 bbl. Sweeps with NewEase 203, New100N, DynaDat, and SAPP. (FlexDrill Sweeps)
Hole Instability/Sloughing Shale	Consider a mud-up and Asphalt additions.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 804-7970

# 1st Intermediate Interval

11" Hole (500' - 5,900')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

---

---

## Offset Data:

- Wells in this area have encountered major losses at +/- 3600 ft.
- Gravel/unconsolidated formation has been encountered at 1380 ft.
- Gas/overpressure has been encountered at 3,700'-4,000'.

## Fluid Recommendations:

- Drill out cement, float collar and new formation. Test the integrity of the casing seat and squeeze if necessary.
- Drill out with Saltwater, aerating as needed to maintain circulation.
- If water is encountered, control flow with reduced air and fluid density.
- If a Trona Water flow is encountered additions of **Lime** and/or **Calcium Chloride** should be used to adjust alkalinities as needed.
- The use of a premix tank is highly recommended. Pre-Hydrate **NewGel** for use as sweeps and for viscosity when a mud up is needed. Fill premix tank with fresh water. Treat out hardness with **SodaAsh** as needed. Add 0.25-0.5 ppb **Caustic Soda** for a 10.0-10.5 pH. Begin additions of 20-25 ppb **NewGel** allow sufficient circulating time for maximum hydration. Add 1.0-2.0 ppb **CFL II**. Then mix additional **NewGel** (30-40 ppb total) or a 120+ funnel viscosity. The pre-hydrated bentonite can be pumped from the premix to the pill tank and pumped downhole for sweeps or can be added slowly to the **Saltwater** for viscosity and rheology control.
- If penetration rates slow sweeps with **New 100N**, **NewEase 203**, **SAPP**, and **DynaDet** should be considered. (1% **New 100N**, 1% **NewEase 203**, 0.5-0.75 ppb **SAPP**, 0.2 % **DynaDet**). "**Flex Sweeps**"
- For trips, an increase in mud weight may be necessary to kill water flows. 9.8-10.0 ppg brine should be considered for this operation.
- Seepage and/or lost circulation may become a problem. For seepage while drilling with water, pump 20-30 bbl pills containing **Paper LCM**.
- If losses become severe, consider a mud up and **LCM** sweeps of **Cedar Fiber** and **FiberSeal** should be pumped and incorporated into the system as needed. If losses continue, increase coarse **LCM** in active system to 15-20%. If losses continue the use of a **DynaPlug Squeeze** is strongly recommended.
- At TD increase funnel viscosity for logs and casing operations as hole conditions dictate. Suggest funnel viscosity be increased to 45-50 sec/qt, before logging operations be attempted.
- At 5,900' (Intermediate T.D.) short trip, check hole conditions. If hole conditions dictate, add pre-hydrated **NewGel** from the premix tank to the active system to increase funnel viscosity to 45-50 sec/qt and spot in the open hole for logs and casing operations

**DRILL STRING PACK-OFF:** Rapid penetration rate during fast drilling often deteriorates to pack-off, a situation which can lead to lost circulation and/or stuck pipe. Pack-off is typically self-induced by exceeding the maximum rate of penetration for a given annular flow rate. The solution to this is to control the penetration rate to a level that the pumps can adequately clean the hole while maintaining rheological properties in line with existing hydraulic parameters.

**SOLIDS CONTROL:** It is of the utmost importance that the shale shakers and flow line cleaners be equipped with the finest screens possible, and yet handle the flow rate. The desander and desilter units should be evaluated periodically and serviced to maximize performance.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

## 2nd Intermediate Interval

8 1/2" Hole (5,900' - 12,750')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Utah, County Utah

2nd Intermediate Interval Drilling Fluid Properties								
Depth Interval (TVD)	Mud Weight (ppg)	Viscosity (sec/qt)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	pH	API Fluid Loss (ml/30min)	Hardness Mg/l	Low Gravity Solids
5,900'-8,000'	8.6-8.8	32-36	6-12	6-10	10.0-11.0	8-10	100+	4-6
8,000'-12,750'	11.2-11.4	45-50	10-18	12-14	10.0-11.0	6-8	100+	4-6

- Drill out with water and or mud as hole conditions dictate. After mud-up , allow the system to revert to a fresh water polymer system.
- As mud weight is increased, seepage losses can become severe. Treat with LCM pills as needed. If pill treatments will not contain the losses at reasonable levels, by-pass the shakers, retaining the pills and allowing the LCM concentration to increase as needed.
- Hole instability can occur in the Mesa Verde in this area. If encountered, consider adding Asphalt, building to a 4-6 ppb concentration.
- High pressure may be encountered in the Castlegate/Blackhawk. Monitor closely for increased pressure while drilling and use caution on trips to minimize possible swabbing.
- Mud weight at Liner Interval T.D. is expected to be in the 11.2-11.4 ppg range.

Challenges:	Strategies:
Hole Instability/Sloughing Shale	Consider 4-6 ppb Asphalt
Increase in Formation pressure	Monitor well conditions and increase density as needed with NewBar as needed.
Seepage/Lost Circulation	As mud weight is increased (10.0ppg +) seepage and losses may become a problem. For seepage pump 50 bbl sweeps with 5-10 ppb DynaFiber and 10-20 ppb NewCarb as needed. For partial or total losses pump sweeps with 10-15 ppb FiberSeal and Cedar Fiber. Severity of losses will determine size and quantity of LCM added. If losses are not controlled with sweeps consider 10-15% LCM in active system. For severe losses the use of a DynaPlug squeeze should be considered.
Differential Sticking	Maintain mud weight as low as possible. Control Low Gravity Solids below 6%, and control fluid loss at 8-10 mls/30 min.
Increase ROP with PDC Bits	Pump 20-40 bbl. Sweeps with NewEase 203, New100N, DynaDet, and SAPP. (FlexDrill Sweeps)



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970



## 2nd Intermediate Interval

8 1/2" Hole (5,900'-12,750')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

---

---

### Offset Data:

Wells in this area have experienced losses as mud weights are increased to control formation pressure. LCM sweeps are strongly recommended for this reason. Mud weights should be kept as low as practical but increase to 11.2 ppg may be required by Liner TD at 12,750'.

- Loss zones on offset wells were at 9200 ft and 9500 ft.

### Fluid Recommendations:

- Drill out cement, float collar and new formation with the system from the previous interval. Test the integrity of the casing seat and squeeze if necessary.
- Drill out with water and or mud. If drilling out with water consider a mud up by +/- 7500 ft or as hole conditions dictate.
- Begin additions of 0.5-1.0 ppb **NewPHPA** and maintain throughout the interval.
- Maintain viscosity with PreHydrated **NewGel** until chlorides have dropped below 5000-7000 mg/l. After chlorides have dropped **NewGel** will not need to be pre-hydrated and can be added directly to the system.
- Begin additions of **NewPHPA**. Concentration of **NewPHPA** should be maintained at 0.5-1.0 ppb throughout the interval. As mud weight increases additions of **PHPA** should be switched from **NewPHPA DLMW** to the shorter chain **NewPHPA DSL**.
- If hole conditions dictate, consider 4-6 ppb Asphalt.
- If penetration rates slow sweeps with **New 100N**, **NewEase 203**, **SAPP**, and **DynaDet** should be considered. (1% **New 100N**, 1% **NewEase 203**, 0.5-0.75 ppb **SAPP**, 0.2 % **DynaDet**). "**Flex Sweeps**"
- Increase mud weight as needed to control formation pressures as needed. Mud weights should be maintained as low as practical to reduce chance of losses and differential sticking. Increase mud weight as needed with **NewBar**.
- As density increases additions of **NewEdge** and/or **DrillThIn** should be added for rheology control.
- As bottom hole temperatures increase and additional fluid loss control is desired supplement the **NewPAC** with **DynaPlex** for fluid loss control. Lower API filtrate to 6-8 cc's with additions of **NewPAC** and **DynaPlex**.
- As mud weight is increased seepage and/or lost circulation may become a problem. For seepage pump 20-30 bbl pills containing a combination of **NewCarb** and **DynaFiber** mixed at a 2:1 ratio. If partial or total returns are encountered, LCM sweeps with a varied size distribution including **Cedar Fiber** and **Fiber Seal**, **PhenoSeal** and other assorted sizes should be considered and incorporated into the system as needed. 20-25% LCM in the active system may be required. The type, size and quantity of LCM used will depend on the severity of losses. If losses are severe a **DynaPlug** squeeze should be considered.
- At TD increase funnel viscosity for logs and casing operations as hole conditions dictate. Suggest funnel viscosity be increased to 50-55 sec/qt, before logging or casing operations be attempted.
- While circulating casing it is recommended to reduce Yield Points for cementing operations.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# **Production Interval** **6 1/8" Hole (12,750'-17,500')**

**Questar**  
**Exploration & Production**  
**WV 4D-12-8-21**  
**Sec 12-T8S-R21E**  
**Uintah, County Utah**

Production Interval Drilling Fluid Properties									
Depth Interval (TVD)	Mud Weight (ppg)	Plastic Viscosity (cp)	Yield Point (lb/100ft <sup>2</sup> )	O/W Ratio %	HTHP Fluid Loss (ml/30min)	Excess Lime (PPB)	Electrical Stability (MV)	Low Gravity Solids	CaCl Mg/l Water
12,750'-17,725'	15.0-15.5	25-35	8-10	85:15	12-15	2-4	500+	< 6	300K

## **Drilling Fluid Recommendations: (12,750'-17,500')**

- Displace to a OptiDrill OBM after finishing the liner job at 12,750'.
- After displacement, maintain the OptiDrill system within the parameters outlined above.
- Offsets in the area have encountered high rates of seepage in this interval. If indications of seepage are observed, sweeps of NewCarb C, Dynafiber C & M, NewSeal, and CyberSeal are recommended. Mixing ratios are recommended to be at 5:1 NewCarb M to DynaFiber , NewSeal, and CyberSeal. If losses continue to be a problem, consider trying different sizes and combinations until seepage is slowed.
- Maintain rheology low to reduce ECD values and reduce surge and swab during connections and trips.
- Drill as underbalanced as possible to help prevent losses and increase penetration rates.
- For pressure control, spot high weight pills with an equivalent mud weight to drilling ECD's. On trips in, stage these pills out and divert to storage for further use. High weight pills in excess of the drilling ECD should be avoided due to possible lost circulation.

Challenges	Strategies
Displacement	<ul style="list-style-type: none"> <li>• Have 1200-1300 bbls of OBM volume on location along with a pump capable of keeping up with displacement rates.</li> <li>• Pump a 10-20 bbl viscosified OBM spacer ahead of the OptiDrill (enough for 500 ft + separation)</li> <li>• A steady pump rate for either turbulent or plug flow should be used. Reciprocate and rotate to assist in minimizing channeling.</li> <li>• Do not shut down once displacement commences.</li> <li>• Should any contamination occur, isolate the contaminated fluid for reconditioning.</li> </ul>
Seepage/lost Circulation.	Pump LCM sweeps when seepage and/or losses are indicated. Sweeps should be a mixture of , NewCarb, DynaFiber, NewSeal, and CyberSeal. If lost returns are encountered, consider a Diaseal M or cross linked polymer squeeze.
Maintaining Oil wet solids	For every 1.0 ppg mud weight increase, mix 0.02 gal/bbl OptiWet
Pressure control	<ul style="list-style-type: none"> <li>• Spot weighted pills calculated to give a bottom hole pressure equal to drilling ECD.</li> <li>• Do not exceed drilling bottom hole pressure with the ECD pill. Lost circulation has been a problem on offset wells.</li> <li>• Stage weighted pills out of the hole and recover for future use.</li> </ul>



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
 Denver, CO. 80202  
 (303) 623-2205 FAX (720) 904-7970

# Production Interval

6 1/8" Hole (12,750'-17,500')

Questar  
Exploration & Production  
WV 4D-12-8-21  
Sec 12-T8S-R21E  
Uintah, County Utah

---

---

## Maintenance Procedure:

**HPHT** - Maintain HPHT values within programmed parameters. Additions of **OptiMul** and **OptiPlus**, at recommended concentrations should maintain the HTHP at recommended levels. If hole conditions indicate a need for lower HPHT values, **Opti G** at 2-4 ppb is recommended.

**Electrical Stability**— Electrical stability should be used as a guide not as an absolute in determining maintenance requirements. Actual values are not critical but should be observed for trends or changes. Decreases in electrical stability should be noted along with other mud properties to determine treatments. To increase electrical stability add emulsifiers and wetting agents **OptiMul** and **OptiPlus** or decrease water content.

**Oil/Water Ratio** - Maintain the oil/water ratio in the 90:10-80:20 range depending on mud weight and condition.. Higher water content will decrease the amount of **OptiVis** needed for rheology.

**Mud weight** - Maintain minimum fluid densities with solids equipment. Monitor hole conditions and all drilling parameters closely for indications of increases in formation pressures and adjust fluid densities accordingly. Drilling with a minimum amount of overbalance will reduce the possibility of losing returns and/or of differentially sticking the drill string. Mud weight on offset wells was in the 15.0-15.5 ppg range at T.D.

**Rheology** - Maintain solids as low as possible. Increase rheology as needed for hole cleaning with a combination of **OptiVis** (**Bentone 910**) and **Opti Vis RM** or **Opti Vis PS** and water content.

**Lime** - Maintain the excess Lime at 2-3 ppb excess.

**Hole cleaning** - Calculate rheology requirements based on ROP, pump rates and hole conditions. Adjust as needed .

**Mud losses downhole**—Monitor ECD's with Hy-Calc, maintaining the lowest values possible. If losses are encountered; sweeps containing **NewCarb**, **DynaFiber**, **Opti-G**, and **NewSeal** should be circulated to aid in the prevention of losses. If seepage losses continue and/or become severe, consider spotting a pill with **Magma Fiber (Fine & Regular)** and the above formulation. Keep the hole full at all times, and avoid excessive swabbing and/or surge actions when tripping.

**Solids Control** - Maintain low gravity solids at 4-6 % by volume. The high performance shakers should be equipped with the finest mesh screens that will handle the circulating volume and not cut barite out.

**Water Contamination**— Keep all water sources off the mud pits. If contamination occurs, treat with emulsifiers and Calcium Chloride as needed.



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

**Production Interval**  
**6 1/8" Hole (12,750'-17,500')**

**Questar**  
**Exploration & Production**  
**WV 4D-12-8-21**  
**Sec 12-T8S-R21E**  
**Uintah, County Utah**

**Recommended materials for relaxed filtrate OptiDrill system :**  
**( 85:15 Oil/Water Ratio)**


Product	Function	Concentration
<b>NewBar</b>	Weighting material	As needed
<b>OptiVis</b>	Organophilic Clay / Viscosifier	2-4 ppb
<b>OptiMul</b>	Primary Emulsifier	2.0 ppb
<b>OptiPlus</b>	Secondary Emulsifier	4.0 gal/bbl.
<b>OptiVis RM</b>	Low End Rheology Modifier	0.1-0.2 ppb
<b>Calcium Chloride Water</b>	Internal Phase	10.0%-20.0 % by volume
<b>Calcium Chloride</b>	Salinity/Activity	300,000 - 350,000 mg/l
<b>OptiG</b>	Fluid Loss control Additive	1.0-4.0 ppb
<b>Lime</b>	Alkalinity Additive	5 ppb
<b>NewCarb M</b>	Loss Circulation Material	10.0 ppb
<b>NewCarb F</b>	Loss Circulation Material	As required
<b>DynaFiber</b>	Loss Circulation Material	As required



**Newpark Drilling Fluids, LP**

410 17th Street, Suite 460  
Denver, CO. 80202  
(303) 623-2205 FAX (720) 904-7970

# WV 4D-12-8-21



## NOTICE OF LATE REPORTING

### DRILLING & COMPLETION INFORMATION

Utah Oil and Gas Conservation General Rule R649-3-6 states that,

- Operators shall submit monthly status reports for each drilling well (including wells where drilling operations have been suspended).

Utah Oil and Gas Conservation General Rule R649-3-21 states that,

- A well is considered completed when the well has been adequately worked to be capable of producing oil or gas or when well testing as required by the division is concluded.
- Within 30 days after the completion or plugging of a well, the following shall be filed:
  - Form 8, Well Completion or Recompletion Report and Log
  - A copy of electric and radioactivity logs, if run
  - A copy of drillstem test reports,
  - A copy of formation water analyses, porosity, permeability or fluid saturation determinations
  - A copy of core analyses, and lithologic logs or sample descriptions if compiled
  - A copy of directional, deviation, and/or measurement-while-drilling survey for each horizontal well

Failure to submit reports in a timely manner will result in the issuance of a Notice of Violation by the Division of Oil, Gas and Mining, and may result in the Division pursuing enforcement action as outlined in Rule R649-10, Administrative Procedures, and Section 40-6-11 of the Utah Code.

---

As of the mailing of this notice, the division has not received the required reports for

Operator: Questar Exploration & Production Co. Today's Date: 04/21/2008

Well: 43 047 34268 API Number: \_\_\_\_\_ Drilling Commenced: \_\_\_\_\_  
WV 4D-12-8-21  
8S 21E 12

☒ List Attached

To avoid compliance action, required reports should be mailed within 7 business days to:

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

If you have questions or concerns regarding this matter, please contact Rachel Medina  
at (801) 538-5260.

cc: Well File  
Compliance File

**NOTICE OF LATE REPORTING  
DRILLING & COMPLETION INFORMATION**

**ATTACHMENT**

Operator: Questar Exploration & Production Co.

Today's Date: 04/21/2008

Well:	API Number:	Drilling Commenced:
WV 5W-36-7-21	4304734099	05/29/2003
WV 4D-12-8-21	4304734268	09/26/2003
WV 3DML 13-8-21	4304737923	09/27/2006
SU 8M-12-7-21	4304736096	03/18/2007
WRU EIH 9CD26-8-22	4304738649	10/03/2007
NBE 12SWD-10-9-23	4304738875	10/22/2007
NBE 8CD-10-9-23	4304739341	10/27/2007
TU 3-35-7-21	4304738995	11/06/2007
WRU EIH 7AD-26-8-22	4304738637	11/19/2007
RW 43-26AG	4304736769	11/26/2007
RW 43-23AG	4304736770	11/26/2007
RW 21-26AD	4304736768	11/27/2007
RW 41-26AG	4304736818	11/28/2007
NBZ 6D-31-8-24	4304737235	12/05/2007
NBZ 4D-31-8-24	4304737236	12/05/2007
NBZ 9D-29-8-24	4304737244	12/05/2007



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**SUNDRY NOTICES AND REPORTS ON WELLS**

**Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.**

FORM APPROVED  
OMB No. 1004-0135  
Expires July 31, 1996

5. Lease Serial No.

**UTU-0806**

6. If Indian, Allottee or Tribe Name

**UTE TRIBE**

7. If Unit or CA/Agreement, Name and/or No.

**WONSITS VALLEY**

8. Well Name and No.

**WV 4D-12-8-21**

9. API Well No.

**43-047-34268**

10. Field and Pool, or Exploratory Area

**WONSITS VALLEY**

11. County or Parish, State

**Utah**

**SUBMIT IN TRIPLICATE - Other Instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

**Questar Exploration & Production Co.**

**Contact: Jan Nelson**

3a. Address

**11002 East 17500 South Vernal, UT 84078**

3b. Phone No. (include area code)

**435-781-4331**

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

**356' FNL 475' FWL, NWNW, SECTION 12, T8S, R21E**

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once Testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Questar Exploration & Production Co. set Conductor on 9/16/03. This location is on Questar's future drilling schedule.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

**Laura Bills**

Title

**Associate Regulatory Affairs Analyst**

Signature

*Laura Bills*

Date

**April 25, 2008**

**THIS SPACE FOR FEDERAL OR STATE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

**RECEIVED**

**APR 28 2008**

DIV. OF OIL, GAS & MINING

**CONFIDENTIAL**

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
QUESTAR EXPLORATION & PRODUCTION CO.

3. ADDRESS OF OPERATOR:  
11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078

PHONE NUMBER:  
(435) 781-4301

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 356' FNL 475' FWL

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E

COUNTY: UINTAH

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:  
UTU-0806

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:  
UTE TRIBE

7. UNIT or CA AGREEMENT NAME:  
WONSITS VALLEY UNIT

8. WELL NAME and NUMBER:  
WV 4D-12-8-21

9. API NUMBER:  
4304734268

10. FIELD AND POOL, OR WLDCAT:  
WONSITS VALLEY

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	STATUS REPORT

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

NAME (PLEASE PRINT) Laura Bills

TITLE Associate Regulatory Affairs Analyst

SIGNATURE

*Laura Bills*

DATE

5/5/2008

(This space for State use only)

RECEIVED CONFIDENTIAL  
MAY 06 2008  
DIV. OF OIL, GAS & MINING

CONFIDENTIAL

FORM 9

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-0806
2. NAME OF OPERATOR: QUESTAR EXPLORATION & PRODUCTION CO.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE TRIBE
3. ADDRESS OF OPERATOR: 11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: WONSITS VALLEY UNIT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 356' FNL 475' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E		8. WELL NAME and NUMBER: WV 4D-12-8-21
PHONE NUMBER: (435) 781-4301		9. API NUMBER: 4304734268
		10. FIELD AND POOL, OR WILDCAT: WONSITS VALLEY
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	STATUS REPORT

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

RECEIVED

JUN 09 2008

DIV. OF OIL, GAS &amp; MINING

NAME (PLEASE PRINT) <u>Laura Bills</u>	TITLE <u>Associate Regulatory Affairs Analyst</u>
SIGNATURE <u><i>Laura Bills</i></u>	DATE <u>6/3/2008</u>

(This space for State use only)

CONFIDENTIAL

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-0806
2. NAME OF OPERATOR: QUESTAR EXPLORATION & PRODUCTION CO.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE TRIBE
3. ADDRESS OF OPERATOR: 11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: WONSITS VALLEY UNIT
PHONE NUMBER: (435) 781-4301		8. WELL NAME and NUMBER: WV 4D-12-8-21
4. LOCATION OF WELL FOOTAGES AT SURFACE: 356' FNL 475' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E		9. API NUMBER: 4304734268
COUNTY: UINTAH		10. FIELD AND POOL, OR WILDCAT: WONSITS VALLEY
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	STATUS REPORT

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

NAME (PLEASE PRINT) <u>Laura Bills</u>	TITLE <u>Associate Regulatory Affairs Analyst</u>
SIGNATURE <u><i>Laura Bills</i></u>	DATE <u>8/12/2008</u>

(This space for State use only)

RECEIVED

CONFIDENTIAL

AUG 14 2008

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
QUESTAR EXPLORATION & PRODUCTION CO.

3. ADDRESS OF OPERATOR:  
11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078

PHONE NUMBER:  
(435) 781-4301

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 356' FNL 475' FWL

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E

COUNTY: UINTAH

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:  
UTU-0806

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:  
UTE TRIBE

7. UNIT or CA AGREEMENT NAME:  
WONSITS VALLEY UNIT

8. WELL NAME and NUMBER:  
WV 4D-12-8-21

9. API NUMBER:  
4304734268

10. FIELD AND POOL, OR WILDCAT:  
WONSITS VALLEY

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	STATUS REPORT

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

NAME (PLEASE PRINT) Laura Bills

SIGNATURE

*Laura Bills*

TITLE Associate Regulatory Affairs Analyst

DATE

9/2/2008

(This space for State use only)

RECEIVED

SEP 04 2008

CONFIDENTIAL

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**CONFIDENTIAL**

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-0806
2. NAME OF OPERATOR: QUESTAR EXPLORATION & PRODUCTION CO.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE TRIBE
3. ADDRESS OF OPERATOR: 11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: WONSITS VALLEY UNIT
PHONE NUMBER: (435) 781-4301		8. WELL NAME and NUMBER: WV 4D-12-8-21
4. LOCATION OF WELL FOOTAGES AT SURFACE: 356' FNL 475' FWL		9. API NUMBER: 4304734268
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E		10. FIELD AND POOL, OR WILDCAT: WONSITS VALLEY
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY STATUS REPORT
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

NAME (PLEASE PRINT) <u>Laura Bills</u>	TITLE <u>Associate Regulatory Affairs Analyst</u>
SIGNATURE <u><i>Laura Bills</i></u>	DATE <u>10/8/2008</u>

(This space for State use only)

RECEIVED

OCT 14 2008

**CONFIDENTIAL**

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-0806
2. NAME OF OPERATOR: QUESTAR EXPLORATION & PRODUCTION CO.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE TRIBE
3. ADDRESS OF OPERATOR: 11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: WONSITS VALLEY UNIT
PHONE NUMBER: (435) 781-4301		8. WELL NAME and NUMBER: WV 4D-12-8-21
4. LOCATION OF WELL FOOTAGES AT SURFACE: 356' FNL 475' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E		9. API NUMBER: 4304734268
		10. FIELD AND POOL, OR WILDCAT: WONSITS VALLEY
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	STATUS REPORT


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

RECEIVED

NOV 04 2008

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) <u>Laura Bills</u>	TITLE <u>Associate Regulatory Affairs Analyst</u>
SIGNATURE <u></u>	DATE <u>11/3/2008</u>

(This space for State use only)

**CONFIDENTIAL**



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-0806
2. NAME OF OPERATOR: QUESTAR EXPLORATION & PRODUCTION CO.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE TRIBE
3. ADDRESS OF OPERATOR: 11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: WONSITS VALLEY UNIT
PHONE NUMBER: (435) 781-4301		8. WELL NAME and NUMBER: WV 4D-12-8-21
4. LOCATION OF WELL FOOTAGES AT SURFACE: 356' FNL 475' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E		9. API NUMBER: 4304734268
		10. FIELD AND POOL, OR WILDCAT: WONSITS VALLEY
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	STATUS REPORT

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

NAME (PLEASE PRINT) Laura Bills	TITLE Associate Regulatory Affairs Analyst
SIGNATURE <i>Laura Bills</i>	DATE 12/2/2008

(This space for State use only)

RECEIVED

DEC 08 2008

CONFIDENTIAL

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-0806
2. NAME OF OPERATOR: QUESTAR EXPLORATION & PRODUCTION CO.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE TRIBE
3. ADDRESS OF OPERATOR: 11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: WONSITS VALLEY UNIT
PHONE NUMBER: (435) 781-4301		8. WELL NAME and NUMBER: WV 4D-12-8-21
4. LOCATION OF WELL FOOTAGES AT SURFACE: 356' FNL 475' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E		9. API NUMBER: 4304734268
COUNTY: UINTAH		10. FIELD AND POOL, OR WILDCAT: WONSITS VALLEY
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	STATUS REPORT

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

NAME (PLEASE PRINT) <u>Laura Bills</u>	TITLE <u>Associate Regulatory Affairs Analyst</u>
SIGNATURE <u><i>Laura Bills</i></u>	DATE <u>1/5/2009</u>

(This space for State use only)

RECEIVED

JAN 08 2009

**CONFIDENTIAL**

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator Questar Exploration and Production Co. Operator Account Number: N 5085  
Address: 11002 E. 17500 S.  
City Vernal  
State UT Zip 84078 Phone Number: (435) 781-4300 4324

**Well 1**

API Number	Well Name	QQ	Sec	Twp	Rng	County
4304734268	WV 4D-12-8-21	NWNW	12	080S	210E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
D	14864	17123		11/1/2007		
Comments:	WMMFD --- 1/29/2009					

**Well 2**

API Number	Well Name	QQ	Sec	Twp	Rng	County
4304734270	WV 5W-12-8-21	SWNW	12	080S	210E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
D	14864	17123		11/1/2007		
Comments:	WMMFD --- 1/29/2009					

**Well 3**

API Number	Well Name	QQ	Sec	Twp	Rng	County
4304734271	WV 6W-14-8-21	SENW	14	080S	210E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
D	14864	17123		11/1/2007		
Comments:	WMMFD RECEIVED --- 1/29/2009					

JAN 26 2009

**ACTION CODES:**

- A -Establish new entity for new well (single well only)
- B -Add new well to existing entity (group or unit well)
- C -Re-assign well from one existing entity to another existing entity
- D -Re-assign well from one existing entity to a new entity
- E -Other (Explain in 'comments' section)

DIV. OF OIL, GAS & MINING

**CONFIDENTIAL**

DAWN CALDWELL  
Name (Please Print)  
Dawn Caldwell  
Signature  
Office Admin 1/20/09  
Title Date

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-0806
2. NAME OF OPERATOR: QUESTAR EXPLORATION & PRODUCTION CO.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE TRIBE
3. ADDRESS OF OPERATOR: 11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: WONSITS VALLEY UNIT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 356' FNL 475' FWL		8. WELL NAME and NUMBER: WV 4D-12-8-21
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E		9. API NUMBER: 4304734268
COUNTY: UINTAH		10. FIELD AND POOL, OR WILDCAT: WONSITS VALLEY
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY STATUS REPORT
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

NAME (PLEASE PRINT) <u>Laura Bills</u>	TITLE <u>Associate Regulatory Affairs Analyst</u>
SIGNATURE <u><i>Laura Bills</i></u>	DATE <u>2/2/2009</u>

(This space for State use only)

RECEIVED

FEB 04 2009

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**CONFIDENTIAL**

FORM 9

5. LEASE DESIGNATION AND SERIAL NUMBER:  
UTU-0806

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL  
OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

6. INDIAN, ALLOTTEE OR TRIBE NAME:  
UTE TRIBE

7. UNIT or CA AGREEMENT NAME:  
WONSITS VALLEY UNIT

8. WELL NAME and NUMBER:  
WV 4D-12-8-21

2. NAME OF OPERATOR:  
QUESTAR EXPLORATION & PRODUCTION CO.

9. API NUMBER:  
4304734268

3. ADDRESS OF OPERATOR:  
11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078

PHONE NUMBER:  
(435) 781-4301

10. FIELD AND POOL, OR WILDCAT:  
WONSITS VALLEY

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 356' FNL 475' FWL

COUNTY: UINTAH

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E

STATE:  
UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY STATUS REPORT
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

NAME (PLEASE PRINT) Laura Bills

TITLE Associate Regulatory Affairs Analyst

SIGNATURE *Laura Bills*

DATE 3/4/2009

(This space for State use only)

RECEIVED

MAR 09 2009

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

CONFIDENTIAL

FORM APPROVED  
OMB No. 1004-0137  
Expires: July 31, 2010

**SUNDRY NOTICES AND REPORTS ON WELLS**  
***Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.***

5. Lease Serial No.  
UTU-0806

6. If Indian, Allottee or Tribe Name  
UTE TRIBE

**SUBMIT IN TRIPLICATE – Other instructions on page 2.**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator  
QUESTAR EXPLORATION AND PRODUCTION COMPANY

3a. Address  
11002 E 17500 S  
VERNAL, UT 84078

3b. Phone No. (include area code)  
435-781-4331

7. If Unit of CA/Agreement, Name and/or No.  
WONSITS VALLEY

8. Well Name and No.  
WV 4D-12-8-21

9. API Well No.  
43-047-34268

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
2167' FNL 586' FWL SWNW, SECTION 12-T8S-R21E

10. Field and Pool or Exploratory Area  
WONSITS VALLEY

11. Country or Parish, State  
UINTAH

**12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input checked="" type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

BASED ON THE CURRENT DATA FROM 3D SEISMIC QUESTAR EXPLORATION AND PRODUCTION COMPANY (QEP) WOULD LIKE TO KEEP THIS WELL BORE IN (TA) STATUS. QEP HAS FILED PAPER WORK PERTAINING TO THE REVISED DRILLING PLAN TO DRILL THIS WELL TO A DEEPER DEPTH AND APPROVAL HAS BEEN GRANTED. QEP IS REQUESTING A THREE (3) YEAR EXTENSION.

**REQUEST DENIED**

Utah Division of  
Oil, Gas and Mining

COPY SENT TO OPERATOR

Date: 5.4.2009

Initials: KS

Date: 4/28/09

By: [Signature]

See Requirements of R649-3-36

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)  
JAN NELSON

Title REGULATORY AFFAIRS

Signature

[Signature]

Date 03/31/2009

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED

APR 02 2009

DIV. OF OIL, GAS & MINING

**CONFIDENTIAL**

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-0806
2. NAME OF OPERATOR: QUESTAR EXPLORATION & PRODUCTION CO.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE TRIBE
3. ADDRESS OF OPERATOR: 11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: WONSITS VALLEY UNIT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 356' FNL 475' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E		8. WELL NAME and NUMBER: WV 4D-12-8-21 9. API NUMBER: 4304734268 10. FIELD AND POOL, OR WILDCAT: WONSITS VALLEY
		COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY STATUS REPORT
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

NAME (PLEASE PRINT) <u>Laura Bills</u>	TITLE <u>Associate Regulatory Affairs Analyst</u>
SIGNATURE <u><i>Laura Bills</i></u>	DATE <u>4/2/2009</u>

(This space for State use only)

**RECEIVED**

**APR 07 2009**

**DIV. OF OIL, GAS & MINING**



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**CONFIDENTIAL**

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. WELL DESIGNATION AND SERIAL NUMBER: UTU-0806
2. NAME OF OPERATOR: QUESTAR EXPLORATION & PRODUCTION CO.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE TRIBE
3. ADDRESS OF OPERATOR: 11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: WONSITS VALLEY UNIT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 356' FNL 475' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E		8. WELL NAME and NUMBER: WV 4D-12-8-21 9. API NUMBER: 4304734268 10. FIELD AND POOL, OR WILDCAT: WONSITS VALLEY
		COUNTY: UINTAH STATE: UTAH

**CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY STATUS REPORT
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

NAME (PLEASE PRINT) <u>Laura Bills</u>	TITLE <u>Associate Regulatory Affairs Analyst</u>
SIGNATURE <u><i>Laura Bills</i></u>	DATE <u>5/4/2009</u>

(This space for State use only)

**RECEIVED**

**MAY 07 2009**

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
QUESTAR EXPLORATION & PRODUCTION CO.

3. ADDRESS OF OPERATOR:  
11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078

PHONE NUMBER:  
(435) 781-4301

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 356' FNL 475' FWL

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E

5. LEASE DESIGNATION AND SERIAL NUMBER:  
UTU-0806

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:  
UTE TRIBE

7. UNIT or CA AGREEMENT NAME:  
WONSITS VALLEY UNIT

8. WELL NAME and NUMBER:  
WV 4D-12-8-21

9. API NUMBER:  
4304734268

10. FIELD AND POOL, OR WILDCAT:  
WONSITS VALLEY

COUNTY: UINTAH

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY STATUS REPORT
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/16/2003. This location is on Questar's future drilling schedule.

NAME (PLEASE PRINT) Laura Bills

TITLE Associate Regulatory Affairs Analyst

SIGNATURE

*Laura Bills*

DATE 6/4/2009

(This space for State use only)

RECEIVED  
JUN 08 2009  
DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**CONFIDENTIAL**

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
QUESTAR EXPLORATION & PRODUCTION CO.

3. ADDRESS OF OPERATOR:  
11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078

PHONE NUMBER:  
(435) 781-4331

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 356' FNL 475' FWL

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 12 8S 21E

5. LEASE DESIGNATION AND SERIAL NUMBER:  
UTU-0806

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:  
UTE TRIBE

7. UNIT or CA AGREEMENT NAME:  
WONSITS VALLEY UNIT

8. WELL NAME and NUMBER:  
WV 4D-12-8-21

9. API NUMBER:  
4304734268

10. FIELD AND POOL, OR WILDCAT:  
WONSITS VALLEY

COUNTY: UINTAH

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY STATUS REPORT
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Questar Exploration & Production Company set conductor on 09/26/2003. This location is on Questar's future drilling schedule.

NAME (PLEASE PRINT) JAN NELSON

TITLE Regulatory Affairs

SIGNATURE

DATE 7/1/2009

(This space for State use only)

RECEIVED  
JUL 06 2009

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QUESTAR EXPLORATION & PRODUCTION CO		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, UT, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 435 781-4362 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 1/31/2010	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input checked="" type="checkbox"/> <b>OTHER</b>	
	OTHER: Monthly Status Report	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> Questar Exploration & Production Company set conductor on 09/26/2003. This location is on Questar's future drilling schedule.		
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> August 05, 2009		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 8/5/2009	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QUESTAR EXPLORATION & PRODUCTION CO		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, UT, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 435 781-4362 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 8/1/2009	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	OTHER:	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> No activity on this well during the month of August, 2009.		
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> September 01, 2009		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 9/1/2009	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QUESTAR EXPLORATION & PRODUCTION CO		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, UT, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 435 781-4362 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 10/8/2009	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER:</b>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  No activity on this well for the month of September 2009.		
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> October 12, 2009		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 10/8/2009	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QUESTAR EXPLORATION & PRODUCTION CO		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, UT, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 435 781-4362 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 10/31/2009	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER:</b>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> No activity on this well during the month of October 2009.		
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> November 02, 2009		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 11/2/2009	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QUESTAR EXPLORATION & PRODUCTION CO		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, UT, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 435 781-4362 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 11/2/2009	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	OTHER:	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  No activity on this well during the month of November 2009.		
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> December 01, 2009		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 12/1/2009	



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QUESTAR EXPLORATION & PRODUCTION CO		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, UT, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 435 781-4362 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 12/31/2009	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	OTHER:	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  No activity on this well during the month of December 2009.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> January 05, 2010		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 1/4/2010	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QUESTAR EXPLORATION & PRODUCTION CO		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, UT, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 435 781-4362 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 1/31/2010	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER:</b>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> No activity on this well during the month of January 2010.		
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> February 02, 2010		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 2/1/2010	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QUESTAR EXPLORATION & PRODUCTION CO		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, UT, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 435 781-4362 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 3/31/2010	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	OTHER:	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  No activity on this well during the month of March 2010.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> April 05, 2010		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 4/5/2010	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QUESTAR EXPLORATION & PRODUCTION CO		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, UT, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 435 781-4362 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 4/30/2010	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	OTHER:	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  No activity on this well during the month of April 2010.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> May 06, 2010		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 5/6/2010	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QUESTAR EXPLORATION & PRODUCTION CO		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, UT, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 435 781-4362 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 2/28/2010	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	OTHER:	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  No activity on this well during the month of February 2010.		
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> March 03, 2010		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 3/3/2010	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QUESTAR EXPLORATION & PRODUCTION CO		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, UT, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 435 781-4362 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 3/31/2010	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER:</b>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  No activity on this well during the month of March 2010.		
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> April 05, 2010		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 4/5/2010	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QUESTAR EXPLORATION & PRODUCTION CO		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, UT, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 303 308-3068 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 5/31/2010	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	OTHER:	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> No activity on this well during the month of May 2010.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> June 07, 2010		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 6/2/2010	

Division of Oil, Gas and Mining  
**OPERATOR CHANGE WORKSHEET** (for state use only)

**ROUTING**  
 CDW

Change of Operator (Well Sold)

**X - Operator Name Change**

The operator of the well(s) listed below has changed, effective:

**6/14/2010**

<b>FROM: (Old Operator):</b> N5085-Questar Exploration and Production Company 1050 17th St, Suite 500 Denver, CO 80265  Phone: 1 (303) 308-3048	<b>TO: (New Operator):</b> N3700-QEP Energy Company 1050 17th St, Suite 500 Denver, CO 80265  Phone: 1 (303) 308-3048
--	--

**CA No.**

**Unit:**

**WONSITS VALLEY**

WELL NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
SEE ATTACHED								

**OPERATOR CHANGES DOCUMENTATION**

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 6/28/2010
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 6/28/2010
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 6/24/2010
- Is the new operator registered in the State of Utah: Business Number: 764611-0143
- (R649-9-2) Waste Management Plan has been received on: Requested
- Inspections of LA PA state/fee well sites complete on: n/a
- Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 8/16/2010 BIA not yet
- Federal and Indian Units:**  
The BLM or BIA has approved the successor of unit operator for wells listed on: 8/16/2010
- Federal and Indian Communization Agreements ("CA"):**  
The BLM or BIA has approved the operator for all wells listed within a CA on: N/A
- Underground Injection Control ("UIC")** Division has approved UIC Form 5 Transfer of Authority to **Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 6/29/2010

**DATA ENTRY:**

- Changes entered in the **Oil and Gas Database** on: 6/30/2010
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 6/30/2010
- Bond information entered in RBDMS on: 6/30/2010
- Fee/State wells attached to bond in RBDMS on: 6/30/2010
- Injection Projects to new operator in RBDMS on: 6/30/2010
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a

**BOND VERIFICATION:**

- Federal well(s) covered by Bond Number: ESB000024
- Indian well(s) covered by Bond Number: 965010693
- (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number 965010695
- The **FORMER** operator has requested a release of liability from their bond on: n/a

**LEASE INTEREST OWNER NOTIFICATION:**

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

**COMMENTS:**



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

5. LEASE DESIGNATION AND SERIAL NUMBER:  
See attached

**SUNDRY NOTICES AND REPORTS ON WELLS**

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:  
See attached

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

7. UNIT or CA AGREEMENT NAME:  
See attached

1. TYPE OF WELL

OIL WELL ☐ GAS WELL ☐ OTHER \_\_\_\_\_

8. WELL NAME and NUMBER:  
See attached

2. NAME OF OPERATOR:

Questar Exploration and Production Company *N5085*

9. API NUMBER:  
Attached

3. ADDRESS OF OPERATOR:

1050 17th Street, Suite 500 Denver

STATE CO ZIP 80265

PHONE NUMBER:  
(303) 672-6900

10. FIELD AND POOL, OR WILDCAT:  
See attached

4. LOCATION OF WELL

FOOTAGES AT SURFACE: See attached

COUNTY: Attached

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE:

UTAH

**11 CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>6/14/2010</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Operator Name Change</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective June 14, 2010 Questar Exploration and Production Company changed its name to QEP Energy Company. This name change involves only an internal corporate name change and no third party change of operator is involved. The same employees will continue to be responsible for operations of the properties described on the attached list. All operations will continue to be covered by bond numbers:

Federal Bond Number: 965002976 (BLM Reference No. ESB000024)

Utah State Bond Number: ~~965003033~~

Fee Land Bond Number: ~~965003033~~ *965010695*

BIA Bond Number: ~~799446~~ *965010693*

The attached document is an all inclusive list of the wells operated by Questar Exploration and Production Company. As of June 14, 2010 QEP Energy Company assumes all rights, duties and obligations as operator of the properties as described on the list

NAME (PLEASE PRINT) Morgan Anderson

TITLE Regulatory Affairs Analyst

SIGNATURE *Morgan Anderson*

DATE 6/23/2010

(This space for State use only)

**RECEIVED**

**JUN 28 2010**

DIV. OF OIL, GAS & MINING

(See Instructions on Reverse Side)

**APPROVED** *6/30/2009*  
*Earlene Russell*  
Division of Oil, Gas and Mining  
Earlene Russell, Engineering Technician

Questar Exploration Production Company (N5085) to QEP Energy Company (N3700)  
WONSITS VALLEY  
effective June 14, 2010

well_name	sec	tpw	rng	api	entity	mineral lease	type	stat	C
WV 43	11	080S	210E	4304715471	5265	Federal	OW	P	
WV 48	10	080S	210E	4304715476	5265	Federal	OW	P	
WV 53	10	080S	210E	4304720003	5265	Federal	OW	P	
WV 55	14	080S	210E	4304720005	5265	Federal	OW	P	
WV 62	10	080S	210E	4304720024	5265	Federal	OW	P	
WV 65	15	080S	210E	4304720041	5265	Federal	OW	P	
WV 83 WG	23	080S	210E	4304720205	17123	Federal	GW	P	
WV 103	14	080S	210E	4304730021	5265	Federal	OW	P	
WV 104	15	080S	210E	4304730022	5265	Federal	OW	P	
WV 105	10	080S	210E	4304730023	5265	Federal	OW	P	
WV 109	15	080S	210E	4304730045	5265	Federal	OW	P	
WV 110	14	080S	210E	4304730046	5265	Federal	OW	P	
WV 112	15	080S	210E	4304730048	5265	Federal	OW	P	
WV 124	15	080S	210E	4304730745	5265	Federal	OW	P	
WV 128	10	080S	210E	4304730798	5265	Federal	OW	P	
WV 132	15	080S	210E	4304730822	5265	Federal	OW	P	
WV 136	21	080S	210E	4304731047	5265	Federal	OW	S	
WV 137	11	080S	210E	4304731523	5265	Federal	OW	P	
WV 133	15	080S	210E	4304731706	5265	Federal	OW	P	
WV 144	10	080S	210E	4304731807	5265	Federal	OW	P	
WV 145	18	080S	220E	4304731820	17123	Federal	GW	P	
WV 121	14	080S	210E	4304731873	5265	Federal	OW	TA	
WV 135-2	21	080S	210E	4304732016	5265	Federal	OW	P	
WV 130	22	080S	210E	4304732307	5265	Federal	OW	P	
WV 119	21	080S	210E	4304732461	5265	Federal	OW	P	
WV 54 WG	07	080S	220E	4304732821	17123	Federal	GW	P	
WV 69 WG	18	080S	220E	4304732829	17123	Federal	GW	P	
WV 38 WG	08	080S	220E	4304732831	17123	Federal	GW	P	
WV 49 WG	08	080S	220E	4304732832	17123	Federal	GW	P	
WV 138 WG	18	080S	220E	4304733054	17123	Federal	GW	P	
WV 14 WG	12	080S	210E	4304733070	17123	Federal	GW	P	
WV 11 WG	12	080S	210E	4304733085	17123	Federal	GW	P	
WV 81 WG	24	080S	210E	4304733086	17123	Federal	GW	S	
WV 146 WG	19	080S	220E	4304733128	17123	Federal	GW	P	
WV 1W-14-8- 21	14	080S	210E	4304733220	17123	Federal	GW	P	
WV 5W-13- 8-21	13	080S	210E	4304733221	17123	Federal	GW	P	
WV 46 WG	07	080S	220E	4304733241	17123	Federal	GW	P	
WV 9W-14-8-21	14	080S	210E	4304733269	17123	Federal	GW	P	
WV 7W-13-8-21	13	080S	210E	4304733270	17123	Federal	GW	P	
WV 1W-18-8-22	18	080S	220E	4304733294	17123	Federal	GW	P	
WV 11W-8-8-22	08	080S	220E	4304733295	17123	Federal	GW	P	
WV 3W-8-8-22	08	080S	220E	4304733493	17123	Federal	GW	S	
WV 5W-7-8-22	07	080S	220E	4304733494	17123	Federal	GW	S	
WV 11W-7-8-22	07	080S	220E	4304733495	17123	Federal	GW	P	
WV 13W-7-8-22	07	080S	220E	4304733496	17123	Federal	GW	P	
WV 1W-7-8-22	07	080S	220E	4304733501	17123	Federal	GW	P	
WV 3W-7-8-22	07	080S	220E	4304733502	17123	Federal	GW	P	
WV 7WRG-7-8-22	07	080S	220E	4304733503	5265	Federal	OW	P	
WV 16W-9-8-21	09	080S	210E	4304733529	17123	Federal	GW	P	

Bonds: BLM = ESB000024

BIA = 965010693

State = 965010695

Questar Exploration Production Company (N5085) to QEP Energy Company (N3700)  
WONSITS VALLEY  
effective June 14, 2010

well_name	sec	tpw	rng	api	entity	mineral lease	type	stat	C
WV 1W-12-8-21	12	080S	210E	4304733531	17123	Federal	GW	S	
WV 1W-13-8-21	13	080S	210E	4304733532	17123	Federal	GW	S	
WV 3W-18-8-22	18	080S	220E	4304733533	17123	Federal	GW	P	
WV 9W-12-8-21	12	080S	210E	4304733534	17123	Federal	GW	P	
WV 11W-12-8-21	12	080S	210E	4304733535	17123	Federal	GW	P	
WV 11W-13-8-21	13	080S	210E	4304733536	17123	Federal	GW	P	
WV 13W-12-8-21	12	080S	210E	4304733537	17123	Federal	GW	S	
WV 13W-18-8-22	18	080S	220E	4304733538	17123	Federal	GW	P	
WV 16G-9-8-21	09	080S	210E	4304733565	5265	Federal	OW	P	
WV 1W-21-8-21	21	080S	210E	4304733602	17123	Federal	GW	P	
WV 3W-13-8-21	13	080S	210E	4304733603	17123	Federal	GW	S	
WV 3W-22-8-21	22	080S	210E	4304733604	17123	Federal	GW	P	
WV 3W-24-8-21	24	080S	210E	4304733605	17123	Federal	GW	P	
WV 13W-14-8-21	14	080S	210E	4304733607	17123	Federal	GW	P	
WV 1W-24-8-21	24	080S	210E	4304733613	17123	Federal	GW	P	
WV 11W-18-8-22	18	080S	220E	4304733626	17123	Federal	GW	P	
WV 2W-10-8-21	10	080S	210E	4304733655	17123	Federal	GW	P	
WV 4W-11-8-21	11	080S	210E	4304733657	17123	Federal	GW	P	
WV 12W-10-8-21	10	080S	210E	4304733659	17123	Federal	GW	S	
WV 12G-10-8-21	10	080S	210E	4304733660	5265	Federal	OW	P	
WV 15W-9-8-21	09	080S	210E	4304733661	17123	Federal	GW	P	
WV 15G-9-8-21	09	080S	210E	4304733662	5265	Federal	OW	P	
WV 2W-13-8-21	13	080S	210E	4304733791	17123	Federal	GW	P	
WV 6W-13-8-21	13	080S	210E	4304733792	17123	Federal	GW	P	
WV 8W-13-8-21	13	080S	210E	4304733793	17123	Federal	GW	P	
WV 10W-1-8-21	01	080S	210E	4304733794	17123	Federal	GW	TA	
WV 10W-13-8-21	13	080S	210E	4304733795	17123	Federal	GW	P	
WV 12W-7-8-22	07	080S	220E	4304733808	17123	Federal	GW	P	
WV 6W-8-8-22	08	080S	220E	4304733811	17123	Federal	GW	P	
WV 7W-8-8-22	08	080S	220E	4304733812	17123	Federal	GW	P	
WV 10W-7-8-22	07	080S	220E	4304733813	17123	Federal	GW	P	
WV 12W-8-8-22	08	080S	220E	4304733815	17123	Federal	GW	P	
WV 14W-7-8-22	07	080S	220E	4304733816	17123	Federal	GW	P	
WV 16W-7-8-22	07	080S	220E	4304733817	17123	Federal	GW	P	
WV 6W-7-8-22	07	080S	220E	4304733828	17123	Federal	GW	P	
WV 6W-18-8-22	18	080S	220E	4304733842	17123	Federal	GW	P	
WV 6WC-18-8-22	18	080S	220E	4304733843	17123	Federal	GW	P	
WV 6WD-18-8-22	18	080S	220E	4304733844	17123	Federal	GW	P	
WV 5W-23-8-21	23	080S	210E	4304733860	17123	Federal	GW	P	
WV 7W-23-8-21	23	080S	210E	4304733861	17123	Federal	GW	P	
WV 8W-12-8-21	12	080S	210E	4304733862	17123	Federal	GW	P	
WV 10W-12-8-21	12	080S	210E	4304733863	17123	Federal	GW	P	
WV 14W-12-8-21	12	080S	210E	4304733864	17123	Federal	GW	P	
WV 16W-12-8-21	12	080S	210E	4304733865	17123	Federal	GW	P	
WV 1W-15-8-21	15	080S	210E	4304733902	17123	Federal	GW	S	
WV 1W-22-8-21	22	080S	210E	4304733903	17123	Federal	GW	S	
WV 1W-23-8-21	23	080S	210E	4304733904	17123	Federal	GW	P	
WV 6W-11-8-21	11	080S	210E	4304733906	17123	Federal	GW	P	
WV 7W-24-8-21	24	080S	210E	4304733908	17123	Federal	GW	P	

Bonds: BLM = ESB000024

BIA = 956010693

State = 965010695

Questar Exploration Production Company (N5085) to QEP Energy Company (N3700)  
WONSITS VALLEY  
effective June 14, 2010

well_name	sec	tpw	rng	api	entity	mineral lease	type	stat	C
WV 10W-11-8-21	11	080S	210E	4304733910	17123	Federal	GW	P	
WV 11W-15-8-21	15	080S	210E	4304733911	17123	Federal	GW	P	
WV 13W-11-8-21	11	080S	210E	4304733913	17123	Federal	GW	S	
WV 13W-15-8-21	15	080S	210E	4304733914	17123	Federal	GW	P	
WV 15W-10-8-21	10	080S	210E	4304733916	17123	Federal	GW	P	
WV 15W-15-8-21	15	080S	210E	4304733917	17123	Federal	GW	P	
WV 5W-14-8-21	14	080S	210E	4304733953	17123	Federal	GW	P	
WV 7W-14-8-21	14	080S	210E	4304733955	17123	Federal	GW	P	
WV 8W-11-8-21	11	080S	210E	4304733957	17123	Federal	GW	S	
WV 8W-14-8-21	14	080S	210E	4304733958	17123	Federal	GW	P	
WV 9W-15-8-21	15	080S	210E	4304733959	17123	Federal	GW	P	
WV 12W-13-8-21	13	080S	210E	4304733961	17123	Federal	GW	P	
WV 14W-13-8-21	13	080S	210E	4304733962	17123	Federal	GW	P	
WV 15W-14-8-21	14	080S	210E	4304733963	17123	Federal	GW	P	
WV 2W-18-8-22	18	080S	220E	4304733986	17123	Federal	GW	P	
WV 8W-18-8-22	18	080S	220E	4304733989	17123	Federal	GW	P	
WV 10W-18-8-22	18	080S	220E	4304733991	17123	Federal	GW	P	
WV 12W-18-8-22	18	080S	220E	4304733993	17123	Federal	GW	S	
WV 14W-18-8-22	18	080S	220E	4304733995	17123	Federal	GW	P	
WV 8W-1-8-21	01	080S	210E	4304734009	17123	Federal	GW	OPS	C
WV 4W-17-8-22	17	080S	220E	4304734038	17123	Federal	GW	P	
WV 12G-1-8-21	01	080S	210E	4304734108	5265	Federal	OW	TA	
WV 2W-14-8-21	14	080S	210E	4304734140	17123	Federal	GW	P	
GH 2W-21-8-21	21	080S	210E	4304734141	17123	Federal	GW	P	
WV 2W-23-8-21	23	080S	210E	4304734142	17123	Federal	GW	P	
WV 3W-21-8-21	21	080S	210E	4304734143	17123	Federal	GW	P	
WV 4W-13-8-21	13	080S	210E	4304734144	17123	Federal	GW	P	
WV 4W-21-8-21	21	080S	210E	4304734145	17123	Federal	GW	P	
WV 4W-22-8-21	22	080S	210E	4304734146	17123	Federal	GW	P	
WV 16W-11-8-21	11	080S	210E	4304734155	5265	Federal	GW	P	
WV 3W-19-8-22	19	080S	220E	4304734187	17123	Federal	GW	P	
WV 4W-23-8-21	23	080S	210E	4304734188	17123	Federal	GW	P	
WV 6W-23-8-21	23	080S	210E	4304734189	17123	Federal	GW	S	
WV 2W-15-8-21	15	080S	210E	4304734242	17123	Federal	GW	P	
WV 2W-22-8-21	22	080S	210E	4304734243	17123	Federal	GW	P	
WV 4W-14-8-21	14	080S	210E	4304734244	17123	Federal	GW	S	
WV 6W-12-8-21	12	080S	210E	4304734245	5265	Federal	GW	TA	
WV 7W-15-8-21	15	080S	210E	4304734246	17123	Federal	GW	P	
WV 8W-15-8-21	15	080S	210E	4304734247	17123	Federal	GW	P	
WV 12W-12-8-21	12	080S	210E	4304734248	17123	Federal	GW	TA	
WV 14W-15-8-21	15	080S	210E	4304734249	17123	Federal	GW	P	
WV 16W-10-8-21	10	080S	210E	4304734250	17123	Federal	GW	P	
WV 16W-15-8-21	15	080S	210E	4304734251	17123	Federal	GW	P	
WV 3W-12-8-21	12	080S	210E	4304734267	17123	Federal	GW	OPS	C
WV 4D-12-8-21	12	080S	210E	4304734268	17123	Federal	GW	OPS	C
WV 6W-14-8-21	14	080S	210E	4304734271	17123	Federal	GW	S	
WV 9W-11-8-21	11	080S	210E	4304734274	17123	Federal	GW	OPS	C
WV 10W-14-8-21	14	080S	210E	4304734275	17123	Federal	GW	P	
WV 11W-14-8-21	14	080S	210E	4304734277	17123	Federal	GW	P	

Bonds: BLM = ESB000024

BIA = 956010693

State = 965010695

Questar Exploration Production Company (N5085) to QEP Energy Company (N3700)  
WONSITS VALLEY  
effective June 14, 2010

well_name	sec	tpw	rng	api	entity	mineral lease	type	stat	C
WV 12W-14-8-21	14	080S	210E	4304734279	17123	Federal	GW	TA	
WV 14M-11-8-21	11	080S	210E	4304734280	17123	Federal	GW	P	
WV 14W-14-8-21	14	080S	210E	4304734281	17123	Federal	GW	S	
WV 16G-14-8-21	14	080S	210E	4304734283	5265	Federal	OW	P	
WV 3MU-15-8-21	15	080S	210E	4304734289	17123	Federal	GW	P	
WV 4MU-15-8-21	15	080S	210E	4304734291	17123	Federal	GW	P	
WV 5MU-15-8-21	15	080S	210E	4304734293	17123	Federal	GW	P	
WV 6W-15-8-21	15	080S	210E	4304734294	17123	Federal	GW	P	
WV 10W-15-8-21	15	080S	210E	4304734295	17123	Federal	GW	P	
WV 4W-24-8-21	24	080S	210E	4304734330	17123	Federal	GW	P	
WV 8M-23-8-21	23	080S	210E	4304734339	17123	Federal	GW	P	
WV 8W-24-8-21	24	080S	210E	4304734340	17123	Federal	GW	P	
WV 2W-8-8-22	08	080S	220E	4304734468	17123	Federal	GW	P	
WV 8W-7-8-22	07	080S	220E	4304734469	17123	Federal	GW	S	
WV 8W-22-8-21	22	080S	210E	4304734564	17123	Federal	GW	P	
WV 14MU-10-8-21	10	080S	210E	4304735879	17123	Federal	GW	P	
WV 13MU-10-8-21	10	080S	210E	4304736305	17123	Federal	GW	P	
WV 3D-13-8-21	13	080S	210E	4304737923	17123	Federal	GW	OPS	C
WV 14DML-12-8-21	12	080S	210E	4304737924	17123	Federal	GW	P	
WV 15AML-12-8-21	12	080S	210E	4304737925	17123	Federal	GW	OPS	C
WV 13DML-10-8-21	10	080S	210E	4304737926	17123	Federal	GW	P	
WV 4DML-15-8-21	15	080S	210E	4304737927	17123	Federal	GW	P	
WV 11AD-14-8-21	14	080S	210E	4304738049	17123	Federal	GW	P	
WV 6-24-8-21	24	080S	210E	4304738663	17123	Federal	GW	P	
WV 2ML-24-8-21	24	080S	210E	4304738664		Federal	GW	APD	C
WV 16C-14-8-21	14	080S	210E	4304738737	17123	Federal	GW	P	
WV 7BML-24-8-21	24	080S	210E	4304738970		Federal	GW	APD	C
WV 7AML-12-8-21	12	080S	210E	4304739035		Federal	GW	APD	C
WV 14BML-12-8-21	12	080S	210E	4304739036		Federal	GW	APD	C
WV 14B-13-8-21	13	080S	210E	4304739037		Federal	GW	APD	C
WV 4B-14-8-21	14	080S	210E	4304739038		Federal	GW	APD	C
WV 13A-15-8-21	15	080S	210E	4304739039	17123	Federal	GW	P	
WV 8D-15-8-21	15	080S	210E	4304739040	17123	Federal	GW	P	
WV 4BD-23-8-21	23	080S	210E	4304739041	17123	Federal	GW	P	
WV 7CML-11-8-21	11	080S	210E	4304739042		Federal	GW	APD	C
WV 7BD-23-8-21	23	080S	210E	4304739044	17123	Federal	GW	P	
WV 2CML-7-8-22	07	080S	220E	4304739155		Federal	GW	APD	C
WV 13AD-8-8-22R(RIGSKID)	08	080S	220E	4304739321	17123	Federal	GW	P	
WV 2B-22-8-21	22	080S	210E	4304740262		Federal	GW	APD	C
WV 8D-22-8-21	22	080S	210E	4304740263		Federal	GW	APD	C
WV 7A-24-8-21	24	080S	210E	4304740331		Federal	GW	APD	C



## United States Department of the Interior

### BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, UT 84145-0155

<http://www.blm.gov/ut/st/en.html>



IN REPLY REFER TO:  
3100  
(UT-922)

JUL 28 2010

#### Memorandum

To: Vernal Field Office, Price Field Office, Moab Field Office

From: Chief, Branch of Minerals

*Roya L. Bankert*

Subject: Name Change Recognized

Attached is a copy of the Certificate of Name Change issued by the Texas Secretary of State and a decision letter recognizing the name change from the ~~Eastern States~~ Office. We have updated our records to reflect the name change in the attached list of leases.

The name change from **Questar Exploration and Production Company** into **QEP Energy Company** is effective June 8, 2010.

cc: MMS  
UDOGM

RECEIVED

AUG 16 2010

DIV. OF OIL, GAS & MINERALS

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QEP ENERGY COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, Ut, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 303 308-3068 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 6/30/2010	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	OTHER:	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  No activity on this well during the month of June 2010.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> July 14, 2010		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 7/7/2010	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5.LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
		<b>7.UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>1. TYPE OF WELL</b> Gas Well		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>2. NAME OF OPERATOR:</b> QEP ENERGY COMPANY		<b>9. API NUMBER:</b> 43047342680000
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, Ut, 84078		<b>PHONE NUMBER:</b> 303 308-3068 Ext
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
		<b>COUNTY:</b> UINTAH
		<b>STATE:</b> UTAH

**11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION  OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 7/31/2010			

**12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.**  

No activity on this well during the month of July 2010.

Accepted by the

Utah Division of

Oil, Gas and Mining

**FOR RECORD ONLY**

August 04, 2010

<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 8/3/2010	



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QEP ENERGY COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, Ut, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 303 308-3068 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 8/31/2010	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	OTHER: <input style="width: 100px;" type="text"/>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> No activity on this well during the month of August 2010.		
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> September 07, 2010		
<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 9/7/2010	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>			
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806			
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE			
<b>2. NAME OF OPERATOR:</b> QEP ENERGY COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY			
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South, Vernal, Ut, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21			
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000			
<b>PHONE NUMBER:</b> 303 308-3068 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY			
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH			
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>					
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>				
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 9/30/2010  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input checked="" type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> QEP Energy Company requests approval to plug and abandon the referenced well as follows: 1. Cut off the 20" conductor 3' below ground level. 2. Fill up the 40' of conductor with class G cement and weld on the dry hole marker.					
<div style="text-align: right;"> <b>Accepted by the Utah Division of Oil, Gas and Mining</b>   <b>Date:</b> <u>September 09, 2010</u>  <b>By:</b> <u><i>Dan K. Quist</i></u> </div>					
<b>NAME (PLEASE PRINT)</b> Jan Nelson		<b>PHONE NUMBER</b> 435 781-4331			
<b>SIGNATURE</b> N/A		<b>TITLE</b> Permit Agent			
<b>DATE</b> 9/7/2010					

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QEP ENERGY COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, Ut, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 303 308-3068 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>  <input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 9/30/2010	<b>TYPE OF ACTION</b>  <div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE   <input type="checkbox"/> CHANGE TO PREVIOUS PLANS   <input type="checkbox"/> CHANGE WELL STATUS   <input type="checkbox"/> DEEPEN   <input type="checkbox"/> OPERATOR CHANGE   <input type="checkbox"/> PRODUCTION START OR RESUME   <input type="checkbox"/> REPERFORATE CURRENT FORMATION   <input type="checkbox"/> TUBING REPAIR   <input type="checkbox"/> WATER SHUTOFF   <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING   <input type="checkbox"/> CHANGE TUBING   <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS   <input type="checkbox"/> FRACTURE TREAT   <input type="checkbox"/> PLUG AND ABANDON   <input type="checkbox"/> RECLAMATION OF WELL SITE   <input type="checkbox"/> SIDETRACK TO REPAIR WELL   <input type="checkbox"/> VENT OR FLARE   <input type="checkbox"/> SI TA STATUS EXTENSION   <input type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR   <input type="checkbox"/> CHANGE WELL NAME   <input type="checkbox"/> CONVERT WELL TYPE   <input type="checkbox"/> NEW CONSTRUCTION   <input type="checkbox"/> PLUG BACK   <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION   <input type="checkbox"/> TEMPORARY ABANDON   <input type="checkbox"/> WATER DISPOSAL   <input type="checkbox"/> APD EXTENSION           OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> No activity on this well during the month of September 2010.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> October 07, 2010		
<b>NAME (PLEASE PRINT)</b> Jan Nelson		<b>PHONE NUMBER</b> 435 781-4331
<b>SIGNATURE</b> N/A		<b>TITLE</b> Permit Agent
<b>DATE</b> 10/6/2010		

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QEP ENERGY COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, Ut, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 303 308-3068 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 10/31/2010			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  

No activity on this well during the month of October 2010.

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**  
 November 02, 2010

<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 11/2/2010	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QEP ENERGY COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, Ut, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 303 308-3068 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 11/30/2010			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
 No activity on this well during the month of November 2010.

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**

<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 12/2/2010	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QEP ENERGY COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, Ut, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 303 308-3068 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 12/31/2010			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  

No activity on this well during the month of December 2010.

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**

<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 1/10/2011	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QEP ENERGY COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, Ut, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 303 308-3068 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 1/31/2011			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  

No activity on this well during the month of January 2011.

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**

<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 2/7/2011	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0806
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> UTE
<b>2. NAME OF OPERATOR:</b> QEP ENERGY COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> WONSITS VALLEY
<b>3. ADDRESS OF OPERATOR:</b> 11002 East 17500 South , Vernal, Ut, 84078		<b>8. WELL NAME and NUMBER:</b> WV 4D-12-8-21
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0356 FNL 0475 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 12 Township: 08.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047342680000
<b>PHONE NUMBER:</b> 303 308-3068 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WONSITS VALLEY
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input checked="" type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion: 2/4/2011			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
 On February 4, 2011, QEP Energy Company plugged the above mentioned well by filling the conductor pipe from 40' to surface with 65 sacks of cement cutting off the conductor pipe 3' below ground level, welding on a dry hole marker and then backfill.

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**  
 2/9/2011

<b>NAME (PLEASE PRINT)</b> Jan Nelson	<b>PHONE NUMBER</b> 435 781-4331	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A	<b>DATE</b> 2/9/2011	





**31. INITIAL PRODUCTION****INTERVAL A (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL B (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL C (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL D (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)**

N/A

**33. SUMMARY OF POROUS ZONES (Include Aquifers):**

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

**34. FORMATION (Log) MARKERS:**

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)

**35. ADDITIONAL REMARKS (Include plugging procedure)**

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Jan Nelson

TITLE Permit Agent

SIGNATURE

DATE 2/14/2011

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340  
Fax: 801-359-3940